

TABLE OF CONTENTS

APPLICATION EPA FORM 7520-6	
AREA OF REVIEW	A
MAPS OF AREA AND AREA OF REVIEW	B
WELL DATA AND CORRECTIVE ACTION PLAN	C
UNDERGROUND SOURCES OF DRINKING WATER	D
<i>Information on underground source of drinking water included in Attachment D</i>	E
MAPS AND CROSS SECTIONS OF GEOLOGIC STRUCTURE OF AREA	F
Geological data on injection and confining zones included in Attachment F	G
OPERATING DATA	H
MAXIMUM INJECTION PRESSURE/FRACTURE CLOSURE PRESSURE	I
WELL STIMULATION	J
INJECTION PROCEDURES	K
SUMMARY OF LOGS AND TEST RUN THE PAST FIVE YEARS	L
CONSTRUCTION DETAILS (Well Schematic)	M
<i>Applies to Class III wells only</i>	N
PLANS FOR WELL FAILURE	O
MONITORING PROGRAM	P
PLUGGING AND ABANDONMENT PLAN	Q
FINANCIAL ASSURANCE MECHANISM	R
<i>Aquifer Exemptions (NOT REQUIRED)</i>	S
EXISTING EPA PERMITS	T
DESCRIPTION OF BUSINESS	U
MICHIGAN DEQ FORMS AND ADDITIONAL INFORMATION	V
MDEQ Form 7200-1 (Application For Permit)	
MDEQ Form 7200-3 (Environmental Impact Assessment)	
MDEQ Form 7200-14 (Injection Well Data)	
Surveyed Plat of Well Location	



United States Environmental Protection Agency

Underground Injection Control Permit Application

(Collected under the authority of the Safe Drinking Water Act. Sections 1421, 1422, 40 CFR 144)

I. EPA ID Number

T/A

C

Read Attached Instructions Before Starting
For Official Use Only

Application approved
mo day year

Date received
mo day year

Permit Number

Well ID

FINDS Number

II. Owner Name and Address

III. Operator Name and Address

Owner Name

Team Completion, L.L.C.

Owner Name

Team Completion, L.L.C.

Street Address

PO Box 1104

Phone Number

(231) 258-9130

Street Address

PO Box 1104

Phone Number

(231) 258-9130

City

Kalkaska

State

MI

ZIP CODE

49646

City

Kalkaska

State

MI

ZIP CODE

49646

IV. Commercial Facility

V. Ownership

VI. Legal Contact

VII. SIC Codes

☒ Yes
☐ No

☒ Private
☐ Federal
☐ Other

☒ Owner
☐ Operator

SIC Codes
Oil and Gas - 1311 (NAICS - 211111)
Sanitary Landfill - 4953 (NAICS - 562212)

VIII. Well Status (Mark "x")

☒ A.

Operating

Date Started

mo day year

07/23/2004

☒ B.

Modification/Conversion

☐ C.

Proposed

IX. Type of Permit Requested (Mark "x" and specify if required)

☒ A.

Individual

☐ B.

Area

Number of Existing Wells

1

Number of Proposed Wells

1

Name(s) of field(s) or project(s)

Weber 4-8 Salt Water Disposal Well

X. Class and Type of Well (see reverse)

A. Class(es)

(enter code(s))

II

B. Type(s)

(enter code(s))

D

C. If class is "other" or type is code 'x,' explain

Presently permitted as Class II, Type D
Proposed as Class II Type D and Class I
non-hazardous.

D. Number of wells per type (if area permit)

1

XI. Location of Well(s) or Approximate Center of Field or Project

XII. Indian Lands (Mark "x")

Latitude

Longitude

Township and Range

Deg Min Sec

Deg Min Sec

Deg Min Sec

Sec Twp Range

1/4 Sec

Feet From

Line

Feet From

Line

Line

Line

Line

Line

Line

Line

Line

Line

Line

Line

Line

Line

Line

Line

☐ Yes
☒ No

XIII. Attachments

(Complete the following questions on a separate sheet(s) and number accordingly; see instructions)

For Classes I, II, III, (and other classes) complete and submit on a separate sheet(s) Attachments A-U (pp 2-6) as appropriate. Attach maps where required. List attachments by letter which are applicable and are included with your application.

XIV. Certification

I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32)

A. Name and Title (Type or Print)

Don Tinker, Member

B. Phone No. (Area Code and No.)

(231) 357-1016

C. Signature

D. Date Signed

06/25/2008

ATTACHMENT A
AREA OF REVIEW

An Area Of Review (AOR) of a radius of 1/4 mile from the well bore was used for this permit application. A volumetric fillup calculation of the area of the emplaced fluid showed that the injected fluid would be less than 1/4 mile (1320') from the well bore after 30 years of injection at an average rate of 87.5 GPM or 3000 BPD.

The volumetric fillup calculation was made utilizing the following formula:

$$r = \sqrt{\frac{(Q) \times (.1337) \sim \text{convert to ft}^3}{(\pi h \Phi) \times (1 - S_w)}}$$

*this is not the
equation that
is used in the
regs.*

where: r = radius of volumetric fillup (feet)
 Q = volume of waste injected (gallons)
 π = 3.1416
 h = thickness of injection zone (feet)
 Φ = porosity expressed as decimal
 S_w = immoveable water saturation

Solution after 10 years of injection at average rate of 3000 BPD or 87.5 GPM:

Q = 459,900,000 gals.

h = 450 feet

Φ = 12.0 %

S_w = 30 %

$$r = \sqrt{\frac{(459,900,000) \times (.1337)}{(3.1416 \times 450 \times 0.12) \times (1 - .30)}} = 720'$$

Solution after 20 years of injection at average rate of 3000 BPD
or 87.5 GPM:

$$Q = 919,800,000 \text{ gals.}$$

$$h = 450 \text{ feet}$$

$$\Phi = 12.0 \%$$

$$S_w = 30 \%$$

$$r = \sqrt{\frac{(918,800,000) \times (.1337)}{(3.1416 \times 450 \times 0.12) \times (1 - .30)}} = 1018'$$

Solution after 30 years of injection at average rate of 3000 BPD
or 87.5 GPM:

$$Q = 1,379,700,000 \text{ gals.}$$

$$h = 450 \text{ feet}$$

$$\Phi = 12.0 \%$$

$$S_w = 30 \%$$

$$r = \sqrt{\frac{(1,379,700,000) \times (.1337)}{(3.1416 \times 100 \times 0.12) \times (1 - .30)}} = 1246'$$

ATTACHMENT B
MAPS OF AREA AND AREA OF REVIEW


The following maps are included in this Attachment:

- A state map indicating plant location.
- Local map showing surface and subsurface location off all wells found within the 1/4 mile Area of Review (AOR) that penetrate the proposed injection zone.
- Local map showing 1/4 mile AOR and all wells found that penetrate the proposed injection zone within Section 8, the West Quarter of Section 9, the South Quarter of Section 5 of Township 25 North, Range 11 West of Grand Traverse County Michigan.
- A Topographic map showing residences, roads, surface facilities, bodies of water, well locations and 1/4 mile Area of Review. Property Owners Within the Area of Review (AOR) are shown on Table B-1.




Figure B-2

Local map showing surface and subsurface location off all wells found within the 1/4 mile AOR) that penetrate the proposed injection zone.



Local map showing all wells found that penetrate the proposed injection zone within the West quarter of Section 9, South quarter of Section 5 and all of Section 8 of T25N, R11W, Grand Traverse County MI



Surface location of vertical drilled wells shown on map. See Figure B-2 for bottom location of Directional drilled wells within 1/4 mile AOR.

MI Permit #	36221	Weber	4-8
MI Permit #	33597	Bott	Berry 1-8
MI Permit #	34147	Berry	et al 1-8
MI Permit #	34419	Weber	3-8
MI Permit #	34594	Berry	2-8

Figure B-4




TABLE B-1


Property Owners Within Sec. 4, 5, 8 and 9 of T25N, R11W
Mayfield Township, Grand Traverse County, Michigan.

<u>TAX ID # (28-09)</u>	<u>Owner</u>	<u>Address</u>
004-010-00	Jim Schmuckal	S.M 37
004-010-10	Laurel & York Ash	Jasper Tr.
004-010-11	Heather Pfau & Nick Kreiser	6701 Jasper Tr.
004-010-20	Brian Steinebach	M 113
004-010-40	Elizabeth Hewlette	3730 W M 113
004-010-50	Sheryl Mcmorris	3712 W M 113
004-010-55	Brad & Cory Swy	3694 W M 113
004-010-60	Joe Galligan	Jasper Tr.
004-010-65	Laurel & York Ash	Jasper Tr.
004-010-70	Laurel & York Ash	6655 Jasper Tr
004-013-00	Jesse Bishop	6901 S M 37
005-009-00	Karl Stevens	4516 Miller Rd
005-011-00	Kathy Jacobs	4680 Miller Rd
005-011-20	Kathy Jacobs	4680 Miller Rd
005-011-21	Suzanne Jacobs	4622 Miller Rd
005-011-30	Mason Stevens	4606 Miller Rd
005-012-00	Mary Jo Lhamon	4068 Miller Rd
005-014-00	Allen Deater	4224 Miller Rd
005-014-01	Jason Deater	4170 Miller Rd
005-015-00	Al Howard	SM ?
005-016-00	Peggy Herndon	
005-019-00	Wayne Bancroft	5150 Miller Rd
005-019-10	Michael Moore	4342 Miller Rd
008-001-00	Weber	
008-001-01	Weber	4029 Miller Rd
008-003-00	Berry	7390 S M37
008-004-00	Herdon	7082 Miller Rd
008-005-00	Miller	4691 Miller Rd
008-008-05	Joe Wolf	7288 Bott Rd
008-008-10	Justin Wolf	7390 Bott Rd
008-008-00	Owen Bott	
008-009-00	Ron Bott	7622 Bott Rd
008-009-10	Greg Bott	7700 Bott Rd
008-009-20	Frank Bott	7134 Hannah Rd
008-011-00	Stan Wolf	7764 S M37
008-012-00	Rodney Nesky	7580 S M37
008-012-01	???	
008-013-00	William Bott	Bott Rd
009-007-10	Peggy Herndon	W M 113
009-007-11	Patricia Kelly	3791 W M 113
009-010-00	Dorothy Weber	7305 S M 37
009-011-00	Weber Trust	7345 S M 37
009-013-00	Armond Snyder	7601 S M 37
009-014-00	Brad Vanwingerden	7525 S M 37

From Mayfield Township Zoning Administration

Figure B-5

Property Map Mayfield Township, Grand Traverse County, Michigan.



ATTACHMENT C
WELL DATA AND CORRECTIVE ACTION PLAN

In addition to the presently permitted Weber #4-8 salt water disposal well, there are 4 other vertical penetrations of the proposed injection zone within the 1/4 mile Area of Review. Three of the wells were directionally drilled and this information is summarized below. The surface locations of all five wells and the subsurface locations of the three directionally drilled wells are shown Figure B-2.

Construction details for the Weber #4-8 saltwater disposal well are presented in Attachment "M". The other vertical well in the AOR is the Berry et al 1-8 (Permit #34147). Drilling started on this well in December 1980. After the hole was lost at 771', a cement plug was set and the well re-drilled to a depth of 6112'. The Berry et al 1-8 was plugged on December 10, 1982.

Construction and plugging records for Berry et al 1-8 and the other three wells drilled within the 1/4 mile Area of Review are included at the end of Attachment "C".

Directionally Drilled Wells Within AOR

Well Name & Number	Permit No.	Start Drilling	Drilling Completed	Total Depth	Status
Bott Berry 1-8	33597	03-16-80	03-31-80	6220	Plugged 10-06-80
Weber 3-8	34419	03-18-81	03-31-81	6273	Plugged 06-13-86
Berry 2-8	34594	05-16-81	05-25-81	6225	Plugged 02-06-86

Bott Berry #1-8 (Permit # 33597)

The Bott Berry #1-8 was drilled as a vertical well in March 1980. On April 1, 1980, cement plugs were set in the Bott Berry #1-8 (Permit # 33597) and the well directionally drilled. This directional drilling performed under Michigan Permit Number 33644 is summarized below:

Well Name & Number	Permit No.	Start Drilling	Drilling Completed	Total Depth	Status
Bott Berry 1-8A	33644	04-02-80	04-10-80	6310	Directionally drilled from 4416' to 6310' MD (4416' to 6208.6' TVD)

Cement Plugs:

Apr. 1, 1980 100 sacks spotted with open ended drill pipe at 6150'
200 sacks kick off plug spotted at 4850'.

Apr. 10, 1980 125 sacks spotted with open ended drill pipe at 6270'
240 sacks kick off plug spotted at 3850'.

Sep. 1980 Removed 8 5/8" casing from 2904'. Spotted 75 sacks
cement at 2945'. Spotted 75 sacks cement at 1831'.
Spotted 100 sacks cement at 887'.

Weber #3-8 (Permit # 34419)

The Weber #3-8 was drilled as a vertical well in March 1981. On March 31, 1981, cement plugs were set in the Weber #3-8 (Permit # 34419) at three different times and the well directionally drilled. The following table summarizes this directional drilling which was performed under Michigan Permit Numbers 34489, 34506 and 34968.

Well Name & Number	Permit No.	Start Drilling	Drilling Completed	Total Depth	Status
Weber 3-8A	34489	04-01-81	04-07-81	6323'	Directionally drilled from 3736' to 6323' MD (3735.8' 6268.5 TVD)
Weber 3-8B	34506	04-09-81	04-16-81	6154	Directionally drilled from 3546' to 6154' MD (3545.8' to 6061.1 TVD)
Weber 3-8C	34968	09-10-81	09-17-81	6149	Directionally drilled from 3734' to 6149' MD (3734' to 6126' TVD)

Cement Plugs:

Mar. 1981 100 sacks spotted with open ended drill pipe at 6169'
 250 sacks kick off plug spotted at 4089'

Apr. 1981 125 sacks spotted with open ended drill pipe at 6293'
 250 sacks kick off plug spotted at 4030'

Sep. 1981 Cement Retainer set 5840', 50 sacks cement under
 retainer & 30 sacks cement on top. Removed 5 ½" casing
 from 4418'. 165 sacks kick off plug from 4012' to 3550'
 On Sep. 17, 1981 ran 5 ½" to 6149' (MD) and cemented
 with 100 sacks of fill up and 200 sacks of good cement.

June 1986 Cement Retainer set 6000', squeezed perfs. W/ 50 sacks
 cement under retainer & 50 sacks cement on top. Cut and
 pulled 5 ½". Spotted 75 sacks cement at 2600' and 75
 sacks cement at 1700'. Spotted 75 sacks cement at 900'.
 Placed 15 sacks at surface. Cut off 3' below ground
 level and welded a ½" plate.

Bott Berry #2-8 (Permit # 34594)

The Bott Berry #2-8 was drilled as a vertical well in May 1981.
On Jan. 11, 1983, cement plugs were set in the Bott Berry #2-8
(Permit # 34594) and the well directionally drilled. This
directional drilling performed under Michigan Permit Number
36359 is summarized below:

Well Name & Number	Permit No.	Start Drilling	Drilling Completed	Total Depth	Status
Bott Berry 2-8A	36359	01-17-83	01-25-83	6063'	Directionally drilled from 4416' to 6310' MD (4416' to 6208.6' TVD)

Cement Plugs:

Jan. 11, 1983 Cement Retainer set 5950'. Perf. Would not take cement. Placed 50 sacks cement on top retainer. Cut and pulled 5 ½" at 4500'. Spotted 75 sacks cement at 2600' and 75 sacks cement at 1700'. Spotted 100 sacks as kick off plug.

Pages C-5 through C-7 list all non-fresh water artificial penetrations located in the Michigan Department of Natural Resources records for Sections 4, 5, 6, 7, 8, 9, 16, 17, and 18 of Township 25 North, Range 11 West, Grand Traverse County, Michigan.

All wells are located in Grand Traverse Co., T25N R11W Bottom Hole | locations Grand Traverse Co., T25N R11W

[illegible]

[illegible]

APR 30 1980

Page C-8

STATE OF MICHIGAN
DEPARTMENT OF NATURAL RESOURCES
LOG OF OIL, GAS, DISPOSAL OR STORAGE WELL (ACT 61)
Submit in DUPLICATE Within 30 Days after Well Completion

APR 25 1980

 PERMIT NUMBER
33597

DEEPENING PERMIT NUMBER

 NAME(S) & ADDRESS OF OWNER(S) SHOWN ON PERMIT
Traverse Corporation
P. O. Box 1036
Traverse City, MI 49684

 NAME & ADDRESS OF DRILLING CONTRACTOR(S)
Cedco Drilling Co. RIG #21
P. O. Box 36
Gaylord, MI 49735

 LEASE NAME(S) & WELL NUMBER SHOWN ON PERMIT
Bott Berry #1-8

 DIRECTIONALLY DRILLED
YES ☐ NO ☒

 SURFACE LOCATION
NW SW NE

 SECTION
8

 TOWNSHIP
25N

 RANGE
11W

 TOWNSHIP NAME
Mayfield

FOOTAGES (North/South) 814 Ft. from South Line and 320' (East/West) Ft. from West Line of quarter section

 COUNTY NAME
Grand Traverse

SUBSURFACE LOCATION

SECTION

TOWNSHIP

RANGE

TOWNSHIP NAME

FOOTAGES (North/South) (East/West) Ft. from Line and Ft. from Line of quarter section

COUNTY NAME

 DRILLING BEGUN
3-16-80

 TOTAL DEPTH OF WELL
Driller 6220' Log 6213'

 TYPE WELL
DRY HOLE

ELEVATIONS

 DRILLING COMPLETED
3-31-80

 FORMATION AT T.D.
Niagaran

 FT. DRLD. - ROTARY TOOLS
From 0 To T.D.

K.B. 1083'

R.F.

 WELL COMPLETED
4-1-80

 PRODUCING FORMATION(S)
NONE

 FT. DRLD. - CABLE TOOLS
From To

R.T. 1082'

Grd.

1067.9'

CASING, CASING LINERS AND CEMENTING

PERFORATIONS

SIZE	WHERE SET	CEMENT	Ft. Pulled	DATE	NUMBER HOLES	INTERVAL PERFORATED	OPEN	
16"	68'	NONE	NONE				YES	NO
11 3/4"	830'	450 SX	NONE					
8 5/8"	3346'	240 SX	NONE					

GROSS PAY INTERVALS

ALL OTHER OIL AND GAS SHOWS OBSERVED OR LOGGED

FORMATION	OIL OR GAS	FROM	TO	FORMATION	OIL OR GAS	DEPTH	WHERE OBSERVED (X)					
							Sam- ples	Odor	Pits	Mud Line	Gas Log.	Fill Up

STIMULATION BY ACID OR FRACTURING

WATER FILL UP (F.U.) OR LOST CIRCULATION (L.C.) (X)

DATE	Interval Treated	Materials and amount used	FORMATION	F.U.	L.C.	DEPTH	AMOUNT

MECHANICAL LOGS, LIST EACH TYPE RUN

DEPTH CORRECTION DEVIATION SURVEY PLUGGED BACK

Brand	(X)	LOG TYPES	LOGGED INTERVALS	DEPTH	CORRECT'N	RUN AT	DEGREES	YES	NO	DEPTH
Schlumberger	X	CNL/FDC	200-6212'							
Birdwell		DLL	5661-6197'							

PRODUCTION TEST DATA

OIL - Bbls/day	GRAVITY - °API	COND. Bbls/day	GAS - MCF/day	WATER - Bbls/day	H ₂ S - Grains/100 cu. ft.	B.H.P. AND DEPTH

I AM RESPONSIBLE FOR THIS REPORT. WITHIN MY KNOWLEDGE ALL FACTS ARE TRUE AND COMPLETE.

DATE	TITLE	SIGNATURE
4-23-80	G. W. Walker, Vice President -	<i>G. W. Walker</i>

NOTICE REPORT COMPLETE SAMPLE AND FORMATION RECORDS AND LOGS TO BE FILED WITH INFORMATION ON REVERSE SIDE R - 7210

FORMATION RECORD

(ATTACH ADDITIONAL SHEETS IF NECESSARY)

ELEVATION USED: 1083' K.B.	GEOLOGIST NAME: Darrell L. Potter	TOPS TAKEN FROM: <input type="checkbox"/> DRILLERS LOG <input checked="" type="checkbox"/> SAMPLE LOG <input checked="" type="checkbox"/> ELECTRIC LOG
-------------------------------	--------------------------------------	---

FROM	TO	FORMATION (TYPE, COLOR, HARDNESS)	FROM	TO	FORMATION (TYPE, COLOR, HARDNESS)
NOTE: IF WELL DIRECTIONALLY DRILLED, ADD TRUE VERTICAL DEPTH FORMATION TOPS WHERE APPROPRIATE.					
740		Base of the Drift			
1472		Antrim			
1712		Traverse Formation			
1780		Traverse Lime			
2331		Bell Shale			
2435		Dundee			
2643		Detroit River Formation			
2659		Detroit River Salt			
3280		Base of Salt			
3733		Bois Blanc			
4122		Bass Island			
4416		SALINA "G"			
4449		F Unit			
4482		F Salt			
5079		E Unit			
5200		D Unit			
5226		C Shale			
5305		B Unit			
5333		B Salt			
5742	5830	A2 Carb (dol., lt/m.gy-brn., vfxln, w/pels, f.suc.)			
	5868	Dol., lt/m.gy-brn., vfxln, anhydritic			
5868	5894	A-1 Evaporite (Salt)			
5894	5970	Anhy.			
5970	6075	A1 Carb (Dol., lt/m.brn., vfxln, arg. carb.)			
6075	6115	A1 Evap (Anhy.)			
6115	6176	Reef (Dol., lt/m.brn, vfxln, f.intxln por., no fluor.)			
6176	6213	Gray Niagaran (Dol., m.gy-brn. arg. bcm. m.gy. arg.)			
6213		T.D. - DRY & ABANDONED			
IF WELL WAS CORED, ATTACH CORE DESCRIPTION					
DRILL STEM TEST DATA					

→ long string casing cement ends @ 2222' (within Traverse Lime)

STATE OF MICHIGAN
DEPARTMENT OF NATURAL RESOURCES
GEOLOGICAL SURVEY DIVISION

APR 25 1980

CASING 4x

Page C-10

WELL PLUGGING RECORD

(Submit in TRIPLICATE Within 30 Days After Plugging is Completed)

PERMIT NUMBER
33597

FIELD NAME

COMPLETE NAME(S) AND ADDRESS OF WELL OWNER

Traverse Corporation, P. O. Box 1036, Traverse City, MI 49684

COMPLETE LEASE OR FARM NAME(S)

Bott Berry

WELL NUMBER
#1-8

WELL LOCATION

NW ¼ SW ¼ NE ¼ SEC. 8 T.25N R. 11W

TOWNSHIP
Mayfield

COUNTY
G. Traverse

TYPE OF WELL (Oil, Gas, Dry Hole, etc.)

DRY HOLE

TOTAL DEPTH

6220'

FORMATION

Niagaran

DATE PLUGGING STARTED

3-31-80

DATE PLUGGING COMPLETED

4-1-80

DEPT. REPRESENTATIVE(S) WHO ISSUED PERMIT OR WITNESSED PLUGGING

Wm. Booker

CASING RECORD

SIZE CASING	DEPTH SET	AMOUNT RECOVERED	SHOT OR RIPPED
16"	68'	NONE	
11 3/4"	830'	NONE	
8 5/8"	3346'	NONE	

BRIDGES OR PLUGS

TYPE (Brush, Stone, Cement, Mechanical, etc.)	DEPTH PLACED	SACKS OF CEMENT AND ADDITIVES
CEMENT	6150'	100 sx
CEMENT	4850'	200 sx
(Kickoff Plug)		

Were tools, tubing, casing, etc., lost or left in the hole before or during plugging?

☒ YES ☐ NO

If yes, give details:

16" from 0 to 68' 11 3/4" from 0 to 830' 8 5/8" from 0 to 3346'

Did a Service Company pump mud, spot cement, or set bridge plugs?

☒ YES ☐ NO

If yes, give name and address:

Allied Cementing
Mt. Pleasant, MI 48858

Was the well plugged by a Company or Contractor other than Owner or Operator?

☒ YES ☐ NO

If yes, give name and address:

Cedco Drilling Company Rig #21
Gaylord, MI 49735
Forest Rosborough

Representatives of Owner, Operator, Company, or Contractor who witnessed plugging:

DESCRIBE IN DETAIL HOW WELL WAS PLUGGED Went in hole with drill pipe open ended to 6150' and spotted 100 sacks of cement. Came up the hole to 4850' and spotted 200 sacks of cement for kickoff plug.

(USE REVERSE SIDE IF NEEDED)

CERTIFICATION

I certify that I am authorized by said Owner or Operator to make this report; and that this report was prepared under my supervision and direction, and that the facts stated herein are true, correct and complete to the best of my knowledge.

NAME AND TITLE (Typed or Printed)

G. W. Walker, Vice President - Exploration

COMPANY NAME AND ADDRESS

Traverse Corporation
P. O. Box 1036
Traverse City, MI 49684

SIGNATURE

DATE (Month, Day, Year)

4-23-80

OPERATORS USE

Description of Detail (cont.) or Other Supplemental Data:

DEPARTMENT USE ONLY

Supplemental Plugging Data and Site Conditions:

4/30/80 All records in. Hole was directionally drilled by PN-33645 Bott-Berry 1-8A.
OK for G.S. approval.

J. Snider

FINAL INSPECTIONS BY DEPARTMENT REPRESENTATIVES

SIGNATURE	DIVISION	DATE
<i>John R. Snider</i>	<i>Geology</i>	<i>4/30/80</i>

STATE OF MICHIGAN
DEPARTMENT OF NATURAL RESOURCES

MAY 2 1980

LOG OF OIL, GAS, DISPOSAL OR STORAGE WELL (ACT 61)

Submit in DUPLICATE Within 30 Days after Well Completion

PERMIT NUMBER

33644

DEEPENING PERMIT NUMBER

NAME(S) & ADDRESS OF OWNER(S) SHOWN ON PERMIT

Traverse Corporation
P. O. Box 1036
Traverse City, MI 49684

NAME & ADDRESS OF DRILLING CONTRACTOR(S)

Cedco Drilling Company RIG #21
P. O. Box 36
Gaylord, MI 49735

LEASE NAME(S) & WELL NUMBER SHOWN ON PERMIT

Bott Berry #1-8A

DIRECTIONALLY DRILLED

YES ☒ NO ☐

SURFACE LOCATION

NW SW NE

SECTION

8

TOWNSHIP

25N

RANGE

11W

TOWNSHIP NAME

Mayfield

FOOTAGES

814

(North/South)

South

Line and 320

(East/West)

West

Ft. from Line of quarter section

COUNTY NAME

Grand Traverse

SUBSURFACE LOCATION

SW SW NE

SECTION

8

TOWNSHIP

25N

RANGE

11W

TOWNSHIP NAME

Mayfield

FOOTAGES

634

(North/South)

South

Line and 600'

(East/West)

West

Ft. from Line of quarter section

COUNTY NAME

Grand Traverse

D
A
T
E
DRILLING BEGUN

4-2-80

TOTAL DEPTH OF WELL

Driller 6310' Log 6306'

TYPE WELL

DRY HOLE

ELEVATIONS

DRILLING COMPLETED

4-9-80

FORMATION AT T.D.

Niagaran

FT. DRLD. - ROTARY TOOLS

From 0 To T.D.

K.B.

1083'

R.F.

WELL COMPLETED

4-10-80

PRODUCING FORMATION(S)

NONE

FT. DRLD. - CABLE TOOLS

From To

R.T.

1082'

Grd.

1067.9'

CASING, CASING LINERS AND CEMENTING

PERFORATIONS

SIZE	WHERE SET	CEMENT	Ft. Pulled	DATE	NUMBER HOLES	INTERVAL PERFORATED	OPEN	
No casing set - well kicked off from							YES	NO
Bott Berry #1-8 Permit #33597								

GROSS PAY INTERVALS

ALL OTHER OIL AND GAS SHOWS OBSERVED OR LOGGED

FORMATION	OIL OR GAS	FROM	TO	FORMATION	OIL OR GAS	DEPTH	WHERE OBSERVED (X)					
							Sam- ples	Odor	Pits	Mud Line	Gas Log	Fill Up

STIMULATION BY ACID OR FRACTURING

WATER FILL UP (F.U.) OR LOST CIRCULATION (L.C.) (X)

DATE	Interval Treated	Materials and amount used	FORMATION	F.U.	L.C.	DEPTH	AMOUNT

MECHANICAL LOGS, LIST EACH TYPE RUN

DEPTH CORRECTION DEVIATION SURVEY PLUGGED BACK

Brand	(X)	LOG TYPES	LOGGED INTERVALS	DEPTH	CORRECT'N	RUN AT	DEGREES	YES	NO	DEPTH
Schlumberger	X	FDC/CNL/GR	4400-6306'			See Oil Well Drilling Control report attached.				
Birdwell										
O-Log										

PRODUCTION TEST DATA

OIL - Bbls/day	GRAVITY - °API	COND. Bbls/day	GAS - MCF/day	WATER - Bbls/day	H ₂ S - Grains/100 cu. ft.	B.H.P. AND DEPTH

I AM RESPONSIBLE FOR THIS REPORT. THE INFORMATION IS COMPLETE AND CORRECT.

DATE	NAME AND TITLE (PRINT)	SIGNATURE
4-29-80	G. W. Walker, Vice President-Exploration	<i>G. W. Walker</i>

NOTICE REPORT COMPLETE SAMPLE AND FORMATION RECORD AND DRILL STEM TEST INFORMATION ON REVERSE SIDE R - 7210

FORMATION RECORD

(ATTACH ADDITIONAL SHEETS IF NECESSARY)

ELEVATION USED: 1190' K.B.	GEOLOGIST NAME: G. W. Walker	TOPS TAKEN FROM: <input type="checkbox"/> DRILLERS LOG <input type="checkbox"/> SAMPLE LOG <input checked="" type="checkbox"/> ELECTRIC LOG
-------------------------------	---------------------------------	--

FROM	TO	FORMATION (TYPE, COLOR, HARDNESS)	FROM	TO	FORMATION (TYPE, COLOR, HARDNESS)
NOTE: IF WELL DIRECTIONALLY DRILLED, ADD TRUE VERTICAL DEPTH FORMATION TOPS WHERE APPROPRIATE.					
4416' MD		Salina G	4416' TVD		
4450' MD		F Unit	4450' TVD		
4482' MD		F Salt	4482' TVD		
5090' MD		E Unit	5084.8' TVD		
5214' MD		D Unit	5201.5' TVD		
5229' MD		D Salt	5216.7' TVD		
5243' MD		C Shale	5229.6' TVD		
5324' MD		B Unit	5308.1' TVD		
5354' MD		B Salt	5337.13' TVD		
5769' MD		A2 Carb	5738.6' TVD		(Dol., lt-m.brn, vfxln, hd,dns, w/some pels)
5892' MD		A2 Evap	5858.5' TVD		(Salt 5892-5985'; Anhy. 5985-6002')
6002' MD		A1 Carb	5965.9' TVD		(Dol., lt-m.brn, vfxln, hd, anhydte, arg.)
6135' MD		A1 Evap	6095.1' TVD		(Anhy, wh.)
6171' MD		Reef	6130.3' TVD		(Dol., buf-tan-lt.brn, vfxln, f-g intr xln por. wk.fluor.)
6251' MD		Gray Niagaran	6208.6' TVD		(Dol, lt.gry, vfxln, hd,dns,arg.)
6310' MD		T.D. - Dry & Temporarily Abandoned			
IF WELL WAS CORED, ATTACH CORE DESCRIPTION					
DRILL STEM TEST DATA					

SEP 25 1980

WELL PLUGGING RECORD

(Submit in TRIPLICATE Within 30 Days After Plugging is Completed)

PERMIT NUMBER
33644

FIELD NAME

OCT 20 1980
ANSWERING HAS COPY

COMPLETE NAME(S) AND ADDRESS OF WELL OWNER

Traverse Corporation, P. O. Box 1036, Traverse City, MI 49684

COMPLETE LEASE OR FARM NAME(S)

Bott Berry

WELL NUMBER
#1-8A

WELL LOCATION

NW ¼ SW ¼ NE ¼ SEC. 8 T. 25N R. 11W

TOWNSHIP
Mayfield

COUNTY
Grand Traverse

TYPE OF WELL (Oil, Gas, Dry Hole, etc.)

DRY HOLE

TOTAL DEPTH
6310'

FORMATION
Niagaran

DATE PLUGGING STARTED
9-22-80

DATE PLUGGING COMPLETED
9-22-80

DEPT. REPRESENTATIVE(S) WHO ISSUED PERMIT OR WITNESSED PLUGGING
Wm. Booker

CASING RECORD

SIZE CASING	DEPTH SET	AMOUNT RECOVERED	SHOT OR RIPPED
No casing set - well		kicked off from	
Bott Berry #1-8 well		Permit #33597	

BRIDGES OR PLUGS

TYPE (Brush, Stone, Cement, Mechanical, etc.)	DEPTH PLACED	SACKS OF CEMENT AND ADDITIVES
CEMENT	6270	125 SX
CEMENT	3850	240 SX
Kickoff plug - temporarily abandoned		

Were tools, tubing, casing, etc., lost or left in the hole before or during plugging?

☒ YES ☐ NO

If yes, give details:

16" from 0 to 68'; 11 3/4" from 0 to 830
8 5/8" from 2904-3346'

Did a Service Company pump mud, spot cement, or set bridge plugs?

☒ YES ☐ NO

If yes, give name and address:

Halliburton
Kalkaska, Michigan

Was the well plugged by a Company or Contractor other than Owner or Operator?

☒ YES ☐ NO

If yes, give name and address:

Pool
Kalkaska, Michigan

Representatives of Owner, Operator, Company, or Contractor who witnessed plugging:

Mike Babcock

DESCRIBE IN DETAIL HOW WELL WAS PLUGGED

Rigged up casing crew. Rigged up McCullough and ran free-point test. Found 8 5/8" casing free at 2920'. Shot off 8 5/8" casing at 2904'. Pulled out of hole. Rigged down casing crew. Rigged up Halliburton. Ran 2 7/8" tubing in hole open ended to 2945' and spotted 75 sacks of cement. Pulled up the hole to 1831' and spotted 75 sacks of cement. Pulled up the hole to 887' and spotted 100 sacks of cement. Pulled tubing out of the hole. Cut 11 3/4" casing 3' below ground level and welded on steel plate. 4/10/80 went in hole w/drill pipe open-ended to 6270' and spotted 125 sx of cmt. Came up the hole to 3850 and spotted 240 sx of cmt. for kick off plug.

(USE REVERSE SIDE IF NEEDED)

CERTIFICATION

I certify that I am authorized by said Owner or Operator to make this report; and that this report was prepared under my supervision and direct control, and that the facts stated herein are true, correct and complete to the best of my knowledge."

NAME AND TITLE (Typed or Printed)

Christopher B. Keister, Geologist

SIGNATURE

Christopher B. Keister

DATE (Month, Day, Year)

9-24-80

COMPANY NAME AND ADDRESS

Traverse Corporation
P. O. Box 1036
Traverse City, MI 49684

STATE OF MICHIGAN
DEPARTMENT OF NATURAL RESOURCES
LOG OF OIL, GAS, DISPOSAL OR STORAGE WELL (ACT 61)
Submit in DUPLICATE Within 30 Days after Well Completion

PERMIT NUMBER

Page C-15

34147

AUG 25 1983

DEEPENING PERMIT NUMBER

NAME(S) & ADDRESS OF OWNER(S) SHOWN ON PERMIT Great Lakes Niagaran Lost Hole - and Industrial Natural Gas Skidded Rig P.O. Box 227, Traverse City, Michigan 49684				NAME & ADDRESS OF DRILLING CONTRACTOR(S) L & G 2			
LEASE NAME(S) & WELL NUMBER SHOWN ON PERMIT 1-8						DIRECTIONALLY DRILLED YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>	
SURFACE LOCATION NE SW NE		SECTION 8	TOWNSHIP 25N	RANGE 11W	TOWNSHIP NAME Mayfield		
FOOTAGES (North/South) 854 Ft. from S		Line and 700 Ft. from W			COUNTY NAME Grand Traverse		
SUBSURFACE LOCATION		SECTION	TOWNSHIP	RANGE	TOWNSHIP NAME		
FOOTAGES (North/South)		Line and			COUNTY NAME		
Line and		Ft. from			Line of quarter section		
DATE	DRILLING BEGUN 12/10/80		TOTAL DEPTH OF WELL Driller 771 Log		TYPE WELL Lost Hole Dry & Abandon		ELEVATIONS K.B. 1098 R.F. R.T. Grd.
	DRILLING COMPLETED 12/11/80		FORMATION AT T.O. Drift		FT. DRLD. - ROTARY TOOLS From 0 To 871		
	WELL COMPLETED 12/11/80		PRODUCING FORMATION(S)		FT. DRLD. - CABLE TOOLS From To		

CASING, CASING LINERS AND CEMENTING

PERFORATIONS

SIZE	WHERE SET	CEMENT	Ft. Pulled	DATE	NUMBER HOLES	INTERVAL PERFORATED	OPEN	
							YES	NO
16	77	Driven						
11 3/4	562	Lost Hole	60'					

GROSS PAY INTERVALS

ALL OTHER OIL AND GAS SHOWS OBSERVED OR LOGGED

FORMATION	OIL OR GAS	FROM	TO	FORMATION	OIL OR GAS	DEPTH	WHERE OBSERVED (X)					
							Sam- ples	Odor	Pits	Mud Line	Gas Log	Fill Up

STIMULATION BY ACID OR FRACTURING

WATER FILL UP (F.U.) OR LOST CIRCULATION (L.C.) (X)

DATE	Interval Treated	Materials and amount used	FORMATION	F.U.	L.C.	DEPTH	AMOUNT

MECHANICAL LOGS, LIST EACH TYPE RUN

DEPTH CORRECTION DEVIATION SURVEY PLUGGED BACK

Brand	(X)	LOG TYPES	LOGGED INTERVALS	DEPTH	CORRECT'N	RUN AT	DEGREES	YES	NO	DEPTH
Schlumberger										
Birdwell										

PRODUCTION TEST DATA

- Bbls/day	GRAVITY - °API	COND. Bbls/day	GAS - MCF/day	WATER - Bbls/day	H ₂ S - Grains/100 cu. ft.	S.H.P. AND DEPTH

I AM RESPONSIBLE FOR THIS REPORT. THE INFORMATION IS COMPLETE AND CORRECT.

DATE	NAME AND TITLE (PRINT)	SIGNATURE
1-26-81	Darrell L. Potter, Geologist	<i>Darrell L. Potter</i>

NOTICE REPORT COMPLETE SAMPLE AND FORMATION RECORD AND DRILL STEM TEST INFORMATION ON REVERSE SIDE R - 7210

FORMATION RECORD

(ATTACH ADDITIONAL SHEETS IF NECESSARY)

All in
Page C-16

EVALUATION USED: KB	GEOLOGIST NAME: Darrell L. Potter	TOPS TAKEN FROM:		
		<input checked="" type="checkbox"/> DRILLERS LOG	<input checked="" type="checkbox"/> SAMPLE LOG	<input type="checkbox"/> ELECTRIC LOG

FROM	TO	FORMATION (TYPE, COLOR, HARDNESS)	FROM	TO	FORMATION (TYPE, COLOR, HARDNESS)
NOTE: IF WELL DIRECTIONALLY DRILLED, ADD TRUE VERTICAL PATH FORMATION TOPS WHERE APPROPRIATE.					
0	771	Drift Lost Hole - Casing stuck at 562 - skidded rig			
771	871	Coldwater shale			
871		Total Depth			
IF WELL WAS CORED, ATTACH CORE DESCRIPTION					
DRILL STEM TEST DATA					

WELL PLUGGING RECORD

(Submit in TRIPLICATE Within 30 Days After Plugging is Completed)

PERMIT NUMBER

34147

FIELD NAME

None

AUG 25 1983

OWNER NAME(S) AND ADDRESS OF WELL OWNER

Great Lakes Niagaran & Industrial Natural Gas, P O Box 227, Traverse City, Michigan 49684

COMPLETE LEASE OR FARM NAME(S)

WELL NUMBER

WELL LOCATION

NE 1/4 SW 1/4 NE 1/4 SEC. 08 T. 25N R. 11W

TOWNSHIP

Mayfield

COUNTY

Grand Traverse

TYPE OF WELL (Oil, Gas, Dry Hole, etc.)

Dry Hole - Lost Hole

TOTAL DEPTH

871

FORMATION

Drift

DATE PLUGGING STARTED

12/11/80

DATE PLUGGING COMPLETED

12/11/80

DEPT. REPRESENTATIVE(S) WHO ISSUED PERMIT OR WITNESSED PLUGGING

Al Walton

CASING RECORD

SIZE CASING	DEPTH SET	AMOUNT RECOVERED	SHOT OR RIPPED
16	77	None	None
11 3/4	562	60'	Shot

BRIDGES OR PLUGS

TYPE (Brush, Stone, Cement, Mechanical, etc.)	DEPTH PLACED	SACKS OF CEMENT AND ADDITIVES
Cement	Top 16"	25 Sacks

Were tools, tubing, casing, etc., lost or left in the hole before or during plugging?

☒ YES ☐ NO

If yes, give details:

11 3/4" casing 60'-562

Did a Service Company pump mud, set cement, or set bridge plugs?

☐ YES ☒ NO

If yes, give name and address:

Was the well plugged by a Company or contractor other than Owner or Operator?

☐ YES ☒ NO

If yes, give name and address:

Representatives of Owner, Operator, Company, or Contractor who witnessed plugging:

DESCRIBE IN DETAIL HOW WELL WAS PLUGGED 25 sacks cement in top of 16"

(USE REVERSE SIDE IF NEEDED)

CERTIFICATION

I certify that I am authorized by said Owner or Operator to make this report; and that this report was prepared under my supervision and direction, and that the facts stated herein are true, correct and complete to the best of my knowledge."

NAME AND TITLE (Typed or Printed)

Darrell L. Potter, Consulting Geologist

SIGNATURE

Darrell L. Potter

DATE (Month, Day, Year)

1/26/81

COMPANY NAME AND ADDRESS

Great Lakes Niagaran
P O Box 227
Traverse City, Michigan 49684

STATE OF MICHIGAN
DEPARTMENT OF NATURAL RESOURCES
LOG OF OIL, GAS, DISPOSAL OR STORAGE WELL (ACT 61)
Submit in DUPLICATE Within 30 Days after Well Completion

PERMIT NUMBER

47

(34147)

DEEPENING PERMIT NUMBER

NAME(S) & ADDRESS OF OWNER(S) SHOWN ON PERMIT Great Lakes Niagaran P O Box 227 Traverse City, Michigan 49684				NAME & ADDRESS OF DRILLING CONTRACTOR(S) L & G Rig 2			
LEASE NAME(S) & WELL NUMBER SHOWN ON PERMIT Berry et al 1-8						DIRECTIONALLY DRILLED YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>	
SURFACE LOCATION NESWNE		SECTION 8		TOWNSHIP 25N		RANGE 11W	
FOOTAGES (North/South) 854 Ft. from S		Line and 700		FOOTAGES (East/West) Ft. from W		Line of quarter section	
SUBSURFACE LOCATION		SECTION		TOWNSHIP		RANGE	
FOOTAGES (North/South)		Line and		FOOTAGES (East/West)		Line of quarter section	
TOWNSHIP NAME Mayfield		COUNTY NAME Grand Traverse		TOWNSHIP NAME		COUNTY NAME	
DRILLING BEGUN December 9, 1980		TOTAL DEPTH OF WELL Driller 6110 Log 6112		TYPE WELL Oil		ELEVATIONS	
DRILLING COMPLETED January 1, 1981		FORMATION AT T.D. Gray Niagaran		FT. DRLD. - ROTARY TOOLS From 0 To 6112		K.B. 1098.9	R.F. 1097.4
WELL COMPLETED		PRODUCING FORMATION(S) Niagaran Reef		FT. DRLD. - CABLE TOOLS From To		R.T.	Grd. 1085.1

CASING, CASING LINERS AND CEMENTING

PERFORATIONS

SIZE	WHERE SET	CEMENT	Ft. Pulled	DATE	NUMBER HOLES	INTERVAL PERFORATED	OPEN	
							YES	NO
16"	85'	Driven	None	1-23-81	6	6002, 6003	X	
11 3/4	872	450 Sacks	None			6005, 6006		
8 5/8	3384	250 Sacks	None			6009, 6010		
5 1/2	6110	475 Sacks	None					

GROSS PAY INTERVALS

ALL OTHER OIL AND GAS SHOWS OBSERVED OR LOGGED

FORMATION	OIL OR GAS	FROM	TO	FORMATION	OIL OR GAS	DEPTH	WHERE OBSERVED (X)					
							Sam- ples	Odor	Pits	Mud Line	Gas Log	Fill Up
Niagaran Reef	Oil	5995	6057	None								

STIMULATION BY ACID OR FRACTURING

WATER FILL UP (F.U.) OR LOST CIRCULATION (L.C.) (X)

DATE	Interval Treated	Materials and amount used	FORMATION	F.U.	L.C.	DEPTH	AMOUNT
1-23-81	6002-3, 6005-6	250 Gallons - 28%	None				
1-24-81	6009-10	750 Gallons - 28%					

MECHANICAL LOGS, LIST EACH TYPE RUN

DEPTH CORRECTION DEVIATION SURVEY PLUGGED BACK

Brand	(X)	LOG TYPES	LOGGED INTERVALS	DEPTH	CORRECT'N	RUN AT	DEGREES	YES	NO	DEPTH
Schlumberger	X	CNL/FDC	200-6110							
Birdwell		Dual Later	5700-6110							
Q-Ind		Micro Later	5700-6110							

PRODUCTION TEST DATA

OIL - Bbls/day	GRAVITY - °API	COND. Bbls/day	GAS - MCF/day	WATER - Bbls/day	H ₂ S - Grains/100 cu. ft.	B.H.P. AND DEPTH
227	49	---	370	0		3197/6005

I AM RESPONSIBLE FOR THIS REPORT. THE INFORMATION IS COMPLETE AND CORRECT.

DATE February 17, 1981 NAME AND TITLE (PRINT) Linda McConnell, Consulting Geologist SIGNATURE *Linda McConnell*

NOTICE REPORT COMPLETE SAMPLE AND FORMATION RECORD AND DRILL STEM TEST INFORMATION ON REVERSE SIDE

R - 7210

(ATTACH ADDITIONAL SHEETS IF NECESSARY)

TO		FORMATION (TYPE, COLOR, HARDNESS)	FROM	TO	FORMATION (TYPE, COLOR, HARDNESS)
NOTE: IF WELL DIRECTIONALLY DRILLED, ADD TRUE VERTICAL DEPTH FORMATION TOPS WHERE APPROPRIATE.					
0	780	Base of Drift	Niagaran Reef	5995	5995
780	1494	Antrim	5995	6057	Dolomite, buff-medium brown finely crystalline, good crystalline porosity, abundant rhombs, good fluorescence, good cut, kicks on gas detector, mostly C-4
1494	1708	Traverse Formation			
1708	1784	Traverse Limestone			
1784	2348	Bell Shale			
2348	2453	Dundee			
2453	2508	Reed City Zone			
2508	2523	Reed City Anhydrite			
2523	2548	Detroit River Formation	6057	6112	Dolomite, AA, oil/water contact, fluorescence, and cut decreasing
2548	3301	Detroit River Salt			
3301	3571	Amherstberg			
3571	3737	Bois Bland			
3737	4142	Bass Island	Total Depth	6112	6112
4142	4432	Salina G-Unit			
4432	4467	F-Unit			
4467	4500	F-Salt			
4500	5104	E-Unit			
5104	5223	D-Unit			
5223	5251	C-Shale			
5251	5336	B-Unit			
5336	5354	B-Salt			
5354		5731			
A-2	Carbonate	5731			
731	5740	Dolomite, light gray to brown, very finely crystal- line, dense, argillaceous			
740	5760	Dolomite, AA, slightly sucrosic			
760	5816	Dolomite, medium to dark brown very finely crystal- line, dense argillaceous			
A-2	Evaporite	5816	IF WELL WAS CORED, ATTACH CORE DESCRIPTION		
816	5912	Anhydrite, white to buff, with minor dolomite inter- bedded	DRILL STEM TEST DATA		
A-1	Carbonate	5912			
912	5995	Dolomite, light to medium brown, dense, very finely crystalline, interbedded with anhydrite (rabbit ears?), white, 3 intervals of anhydrite 5921-29, 5951-58, and 5171-75			

STATE OF MICHIGAN
DEPARTMENT OF NATURAL RESOURCES
GEOLOGICAL SURVEY DIVISION

DEC 21 1982

WELL PLUGGING RECORD

(Submit in TRIPLICATE Within 30 Days After Plugging is Completed)

PERMIT NUMBER 34147
FIELD NAME Mayfield 8

COMPLETE NAME(S) AND ADDRESS OF WELL OWNER
Great Lakes Niagaran, P.O. Box 466, Traverse City, MI 49684

COMPLETE LEASE OR FARM NAME(S)
Berry

WELL LOCATION NE 1/4 SW 1/4 NE 1/4 SEC. 8 T.25N R. 11W TOWNSHIP Mayfield COUNTY Grand Traverse

WELL NUMBER 1-8

TYPE OF WELL (Oil, Gas, Dry Hole, etc.)
Oil

TOTAL DEPTH 6110 FORMATION Niagaran

DATE PLUGGING STARTED 12/3/82 DATE PLUGGING COMPLETED 12/10/82 DEPT. REPRESENTATIVE(S) WHO ISSUED PERMIT OR WITNESSED PLUGGING Jerry Wendal

CASING RECORD

SIZE CASING	DEPTH SET	AMOUNT RECOVERED	SHOT OR RIPPED
16"	74	-	
11 3/4"	872	-	
8 5/8"	3384	2700'	
5 1/2"	6110	3450'	

BRIDGES OR PLUGS

TYPE (Brush, Stone, Cement, Mechanical, etc.)	DEPTH PLACED	SACKS OF CEMENT AND ADDITIVES
Cement	5950	100 sx
Cement	3450	100 sx
Cement	2700	75 sx
Cement	1800	75 sx
Cement	875	100 sx
Cement	surface	10 sx

Were tools, tubing, casing, etc., lost or left in the hole before or during plugging?

☒ YES ☐ NO

If yes, give details:

See Casing Record Above

Did a Service Company pump mud, spot cement, or set bridge plugs?

☒ YES ☐ NO

If yes, give name and address:

Dowell
Kalkaska

Was the well plugged by a Company or Contractor other than Owner or Operator?

☒ YES ☐ NO

If yes, give name and address:

T & J Tank
Kalkaska

Representatives of Owner, Operator, Company, or Contractor who witnessed plugging:

John Vandekerkhof

DESCRIBE IN DETAIL HOW WELL WAS PLUGGED

Set 5 1/2" retainer at 5950'. Spotted 40 sx below and 60 sx on top of retainer. Cut 5 1/2" off at 3450'. Spotted 100 sx at 3450'. Cut and pulled 8 5/8" at 2700'. Spotted 75 sx at 2700'. Spotted 75 sx at 1800'. Spotted 100 sx at 875'. Spotted 10sx on top of 11 3/4" csg.(Surface). Cutt off casing 3' below ground level, and welded on 1/2" steel plate.

(USE REVERSE SIDE IF NEEDED)

CERTIFICATION

"I certify that I am authorized by said Owner or Operator to make this report; and that this report was prepared under my supervision and direct that the facts stated herein are true, correct and complete to the best of my knowledge."

NAME AND TITLE (Typed or Printed) Paul D. McConnell, President
McConnell Consulting, Inc.

COMPANY NAME AND ADDRESS
McConnell Consulting, Inc.
1515 Cass
Traverse City, MI 49684

SIGNATURE

Paul D. McConnell

DATE (Month, Day, Year)

12/17/82

STATE OF MICHIGAN
DEPARTMENT OF NATURAL RESOURCES
LOG OF OIL, GAS, DISPOSAL OR STORAGE WELL (ACT 61)

APR 17 1981

PERMIT NUMBER

34419

Page C-21

Submit in DUPLICATE Within 30 Days after Well Completion

LANCING HAS ORIGINAL COPY

DEEPENING PERMIT NUMBER

NAME(S) & ADDRESS OF OWNER(S) SHOWN ON PERMIT

Traverse Oil Company
P. O. Box 1053
Traverse City, MI 49684

NAME & ADDRESS OF DRILLING CONTRACTOR(S)

Nicor Drilling Rtg #21
P. O. Box 36
Gaylord, MI 49735

LEASE NAME(S) & WELL NUMBER SHOWN ON PERMIT

Weber #3-8

DIRECTIONALLY DRILLED

YES ☐ NO ☒

SURFACE LOCATION

SE NW NE

SECTION

8

TOWNSHIP

25N

RANGE

11W

TOWNSHIP NAME

Mayfield

FOOTAGES

(North/South)

(East/West)

854

Ft. from North

Line and 1140

Ft. from West

Line of quarter section

COUNTY NAME

Grand Traverse

SUBSURFACE LOCATION

SECTION

TOWNSHIP

RANGE

TOWNSHIP NAME

FOOTAGES

(North/South)

(East/West)

Ft. from

Line and

Ft. from

Line of quarter section

COUNTY NAME

DRILLING BEGUN

3-18-81

TOTAL DEPTH OF WELL

Driller 6283 Log 6273

TYPE WELL

DRY HOLE

ELEVATIONS

DRILLING COMPLETED

3-30-81

FORMATION AT T.D.

Niagaran

FT. DRLD. - ROTARY TOOLS

From 0 To T.D.

K.B. 1108.2'

R.F. 1106.7'

WELL COMPLETED

NA

PRODUCING FORMATION(S)

None

FT. DRLD. - CABLE TOOLS

From To

R.T.

Grd. 1093.2'

CASING, CASING LINERS AND CEMENTING

PERFORATIONS

SIZE	WHERE SET	CEMENT	Ft. Pulled	DATE	NUMBER HOLES	INTERVAL PERFORATED	OPEN	
							YES	NO
16"	52'	DRIVEN	NONE					
11 3/4"	866'	585 SX	NONE					
8 5/8"	3388'	400 SX	NONE					

GROSS PAY INTERVALS

ALL OTHER OIL AND GAS SHOWS OBSERVED OR LOGGED

FORMATION	OIL OR GAS	FROM	TO	FORMATION	OIL OR GAS	DEPTH	WHERE OBSERVED (X)					
							Sam- ples	Odor	Pits	Mud Line	Gas Log	Fill Up

STIMULATION BY ACID OR FRACTURING

WATER FILL UP (F.U.) OR LOST CIRCULATION (L.C.) (X)

DATE	Interval Treated	Materials and amount used	FORMATION	F.U.	L.C.	DEPTH	AMOUNT

MECHANICAL LOGS, LIST EACH TYPE RUN

DEPTH CORRECTION DEVIATION SURVEY PLUGGED BACK

Brand	(X)	LOG TYPES	LOGGED INTERVALS	DEPTH	CORRECT'N	RUN AT	DEGREES	YES	NO	DEPTH
Schlumberger	X	LD/CNI	200-6270'							
Birdwell		Dipmeter	5650-6272'							

PRODUCTION TEST DATA

OIL - Bbls/day	GRAVITY - °API	COND. Bbls/day	GAS - MCF/day	WATER - Bbls/day	H ₂ S - Grains/100 cu. ft.	B.H.P. AND DEPTH

I AM RESPONSIBLE FOR THIS REPORT. THE INFORMATION IS COMPLETE AND CORRECT.

DATE	NAME AND TITLE (PRINT)	SIGNATURE
4-15-81	Rudolph S. Cadena, Drilling Supervisor	<i>Rudolph S. Cadena</i>

NOTICE REPORT COMPLETE SAMPLE AND FORMATION RECORD AND DRILL STEM TEST INFORMATION ON REVERSE SIDE R - 7210

FORMATION RECORD

(ATTACH ADDITIONAL SHEETS IF NECESSARY)

Page C-22

ELEVATION USED:	GEOLOGIST NAME:	TOPS TAKEN FROM:	
1108.2' KB	Christopher B. Keister	<input type="checkbox"/> DRILLERS LOG	<input type="checkbox"/> SAMPLE LOG <input checked="" type="checkbox"/> ELECTRIC LOG

FROM	TO	FORMATION (TYPE, COLOR, HARDNESS)	FROM	TO	FORMATION (TYPE, COLOR, HARDNESS)
NOTE: IF WELL DIRECTIONALLY DRILLED, ADD TRUE VERTICAL DEPTH FORMATION TOPS WHERE APPROPRIATE.					
	770	Base of Drift			
886	1496	Sunbury			
1496	1732	Antrim			
1732	1790	Traverse Formation			
1790	2344	Traverse Lime			
2344	2448	Bell Shale			
2448	2516	Dundee			
2516	2539	Reed City Anhydrite			
2539	2630	Reed City Dolomite			
2630	2670	Detroit River Anhydrite			
2670	3272	Detroit River Salt			
3298	3524	Massive Anhydrite			
3524	3735	Amherstburg			
3735	4138	Bois Blanc			
4138	4429	Bass Islands			
4429	4460	Salina G Unit			
4460	4496	F Unit			
4496	5098	F Salt			
5098	5220	E Unit			
5220	5232	D Unit			
5232	5247	D Salt			
5247	5320	C Shale			
5320	5362	B Unit			
5362	5757	B Salt			
5757	5872	A2 Carb			
5872	6002	A2 Evap			
6002	6122	A1 Carb			
6122	6151	A1 Evap			
6151	6216	Brown Niagaran			
6216		Gray Niagaran			
6273		Logger's T.D.			
6283		Driller's T.D.			

IF WELL WAS CORED, ATTACH CORE DESCRIPTION

DRILL STEM TEST DATA

STATE OF MICHIGAN
DEPARTMENT OF NATURAL RESOURCES
GEOLOGICAL SURVEY DIVISION

APR 17 1981

Page C-23

WELL PLUGGING RECORD

(Submit in TRIPLICATE Within 30 Days After Plugging is Completed)

PERMIT NUMBER

34419

FIELD NAME

COMPLETE NAME(S) AND ADDRESS OF WELL OWNER

Traverse Oil Company, P. O. Box 1053, Traverse City, MI 49684

COMPLETE LEASE OR FARM NAME(S)

Weber

WELL NUMBER

#3-8

WELL LOCATION

SE ¼ NW ¼ NE ¼ SEC. 8 T. 25N R. 11W

TOWNSHIP

Mayfield

COUNTY

Grand Traverse

TYPE OF WELL (Oil, Gas, Dry Hole, etc.)

DRY HOLE

TOTAL DEPTH

6283'

FORMATION

Niagaran

DATE PLUGGING STARTED

3-31-81

DATE PLUGGING COMPLETED

3-31-81

DEPT. REPRESENTATIVE(S) WHO ISSUED PERMIT OR WITNESSED PLUGGING

William Booker

CASING RECORD

SIZE CASING	DEPTH SET	AMOUNT RECOVERED	SHOT OR RIPPED
16"	52'	NONE	-
11 3/4"	866'	NONE	-
8 5/8"	3388'	NONE	-

BRIDGES OR PLUGS

TYPE (Brush, Stone, Cement, Mechanical, etc.)	DEPTH PLACED	SACKS OF CEMENT AND ADDITIVES
CEMENT	6169'	100 sx
CEMENT	4089'	250 sx
(Kickoff Plug)		

Were tools, tubing, casing, etc., lost or left in the hole before or during plugging?

☒ YES ☐ NO

If yes, give details:

Casing as listed above

Did a Service Company pump mud, spot cement, or set bridge plugs?

☒ YES ☐ NO

If yes, give name and address:

Dowell
Kalkaska, MI 49646

Was the well plugged by a Company or Contractor other than Owner or Operator?

☒ YES ☐ NO

If yes, give name and address:

Nicor Drilling
Gaylord, MI 49735
Rudolph S. Cadena

Representatives of Owner, Operator, Company, or Contractor who witnessed plugging:

DESCRIBE IN DETAIL HOW WELL WAS PLUGGED. Went in hole with drill pipe open ended to 6169' and spotted 100 sacks of cement. Pulled up the hole to 4089' and spotted 250 sacks of Hi-dense cement for kickoff plug.

(USE REVERSE SIDE IF NEEDED)

CERTIFICATION

I certify that I am authorized by said Owner or Operator to make this report; and that this report was prepared under my supervision and direction, and that the facts stated herein are true, correct and complete to the best of my knowledge.

NAME AND TITLE (Type or Printed)

Rudolph S. Cadena, Drilling Supervisor

COMPANY NAME AND ADDRESS

Traverse Oil Company
P. O. Box 1053
Traverse City, MI 49684

SIGNATURE

Rudolph S. Cadena

DATE (Month, Day, Year)

4-15-81

Description of Detail (cont.) or Other Supplemental Data:

DEPARTMENT USE ONLY

Supplemental Plugging Data and Site Conditions:

5/19/81 can recommend approval. Hole redrilled under PN34489 (Booker)

FINAL INSPECTIONS BY DEPARTMENT REPRESENTATIVES

SIGNATURE	DIVISION	DATE
William Booker	Geological Survey	5 Dec 81

STATE OF MICHIGAN
DEPARTMENT OF NATURAL RESOURCES

APR 17 1981

LOG OF OIL, GAS, DISPOSAL OR STORAGE WELL (ACT 61)

Submit in DUPLICATE Within 30 Days after Well Completion

PERMIT NUMBER
34489

MAY 01 1981

DEEPENING PERMIT NUMBER

LANSING HAS ORIGINAL COPY

NAME(S) & ADDRESS OF OWNER(S) SHOWN ON PERMIT Traverse Oil Company P. O. Box 1053 Traverse City, MI 49684				NAME & ADDRESS OF DRILLING CONTRACTOR(S) Nicor Drilling P. O. Box 36 Gaylord, MI 49735 Rig #21				
LEASE NAME(S) & WELL NUMBER SHOWN ON PERMIT Weber #3-8A						DIRECTIONALLY DRILLED YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>		
SURFACE LOCATION SE NW NE		SECTION 8		TOWNSHIP 25N		RANGE 11W		
TOWNSHIP NAME Mayfield		COUNTY NAME Grand Traverse						
FOOTAGES (North/South) 854 Ft. from North		Line and 1140		Ft. from West		Line of quarter section		
SUBSURFACE LOCATION SW NW NE		SECTION 8		TOWNSHIP 25N		RANGE 11W		
TOWNSHIP NAME Mayfield		COUNTY NAME Grand Traverse						
FOOTAGES (North/South) 800 Ft. from North		Line and 572		Ft. from West		Line of quarter section		
DATE	DRILLING BEGUN 4-1-81		TOTAL DEPTH OF WELL Driller 6320' Log 6323'		TYPE WELL DRY HOLE		ELEVATIONS	
	DRILLING COMPLETED 4-7-81		FORMATION AT T.D. Niagaran		FT. DRLD. - ROTARY TOOLS From 0 To T D		K.B. 1108.2'	R.F. 1106.7'
	WELL COMPLETED NA		PRODUCING FORMATION(S) NONE		FT. DRLD. - CABLE TOOLS From To		R.T.	Grd. 1093.2'

CASING, CASING LINERS AND CEMENTING

PERFORATIONS

SIZE	WHERE SET	CEMENT	Ft. Pulled	DATE	NUMBER HOLES	INTERVAL PERFORATED	OPEN	
No additional casing set	see Weber #3-8-						YES	NO
	Permit #34419							

GROSS PAY INTERVALS

ALL OTHER OIL AND GAS SHOWS OBSERVED OR LOGGED

FORMATION	OIL OR GAS	FROM	TO	FORMATION	OIL OR GAS	DEPTH	WHERE OBSERVED (X)					
							Samples	Odor	Pits	Mud Line	Gas Log.	Fill Up

STIMULATION BY ACID OR FRACTURING

WATER FILL UP (F.U.) OR LOST CIRCULATION (L.C.) (X)

DATE	Interval Treated	Materials and amount used	FORMATION	F.U.	L.C.	DEPTH	AMOUNT

MECHANICAL LOGS, LIST EACH TYPE RUN

DEPTH CORRECTION DEVIATIONS SURVEY PLUGGED BACK

Brand	(X)	LOG TYPES	LOGGED INTERVALS	DEPTH	CORRECT'N	RUN AT	DEGREES	YES	NO	DEPTH
Schlumberger	X	LDT/CNL/GR	3700-6321							
Birdwell		Dipmeter	5764-6312							

PRODUCTION TEST DATA

OIL - Bbls/day	GRAVITY - °API	COND. Bbls/day	GAS - MCF/day	WATER - Bbls/day	H ₂ S - Grains/100 cu. ft.	B.H.P. AND DEPTH

I AM RESPONSIBLE FOR THIS REPORT. THE INFORMATION IS COMPLETE AND CORRECT.

DATE	NAME AND TITLE (PRINT)	SIGNATURE
4-15-81	Rudolph S. Cadena, Drilling Supervisor	<i>Rudolph S. Cadena</i>

NOTICE REPORT COMPLETE SAMPLE AND FORMATION RECORD AND DRILL STEM TEST INFORMATION ON SEPARATE SHEET

FORMATION RECORD

(ATTACH ADDITIONAL SHEETS IF NECESSARY)

Page C-26

ELEVATION USED: 1108.2' KB	GEOLOGIST NAME: Christopher B. Keister	TOPS TAKEN FROM: <input type="checkbox"/> DRILLERS LOG <input type="checkbox"/> SAMPLE LOG <input checked="" type="checkbox"/> ELECTRIC LOG
-------------------------------	---	--

FROM	TO	FORMATION (TYPE, COLOR, HARDNESS)	FROM	TO	FORMATION (TYPE, COLOR, HARDNESS)
NOTE: IF WELL DIRECTIONALLY DRILLED, ADD TRUE VERTICAL DEPTH FORMATION TOPS WHERE APPROPRIATE.					
3736'	MD	Bois Blanc	3735.8'	TVD	
4142'	MD	Bass Island	4137.2'	TVD	
4442'	MD	Salina G Unit.	4430.1'	TVD	
4476'	MD	F Unit	4463.3'	TVD	
4510'	MD	F Salt	4496.5'	TVD	
5126'	MD	E Unit	5095.3'	TVD	
5249'	MD	D Unit	5214.3'	TVD	
5264'	MD	D Salt	5228.8'	TVD	
5278'	MD	C Shale	5242.3'	TVD	
5355'	MD	B Unit	5317.0'	TVD	
5397'	MD	B Salt	5357.9'	TVD	
5794'	MD	A2 Carb	5748.7'	TVD	
5910'	MD	A2 Evap	5862.9'	TVD	
6032'	MD	A1 Carb	5982.8'	TVD	
6148'	MD	A1 Evap	6096.7'	TVD	
6184'	MD	Brown Niagaran	6132.0'	TVD	
6266'	MD	Gray Niagaran	6212.5'	TVD	
6230'	MD	Driller's T.D.	6265'	TVD	
6323'	MD	Logger's T.D.	6268.5'	TVD	
IF WELL WAS CORED, ATTACH CORE DESCRIPTION					
DRILL STEM TEST DATA					

APR 17 1981

WELL PLUGGING RECORD

(Submit in TRIPLICATE Within 30 Days After Plugging is Completed)

PERMIT NUMBER

34489

APR 23 1981

FIELD NAME

COMPLETE NAME(S) AND ADDRESS OF WELL OWNER

Traverse Oil Company, P. O. Box 1053, Traverse City, MI 49684

COMPLETE LEASE OR FARM NAME(S)

Weber

WELL NUMBER

#3-8A

WELL LOCATION

SE 1/4 NW 1/4 NE 1/4 SEC. 8 T. 25N R. 11W

TOWNSHIP

Mayfield

COUNTY

Grand-Traverse

TYPE OF WELL (Oil, Gas, Dry Hole, etc.)

DRY HOLE

TOTAL DEPTH

6320'

FORMATION

Niagaran

DATE PLUGGING STARTED

4-8-81

DATE PLUGGING COMPLETED

4-8-81

DEPT. REPRESENTATIVE(S) WHO ISSUED PERMIT OR WITNESSED PLUGGING

William Booker

CASING RECORD

SIZE CASING	DEPTH SET	AMOUNT RECOVERED	SHOT OR RIPPED
No additional casing set - see Weber #3-8 Permit #34419			

BRIDGES OR PLUGS

TYPE (Brush, Stone, Cement, Mechanical, etc.)	DEPTH PLACED	SACKS OF CEMENT AND ADDITIVES
CEMENT	6293'	125 sx
CEMENT	4030'	250 sx
	(Kickoff Plug)	

Were tools, tubing, casing, etc., lost or left in the hole before or during plugging?

☒ YES ☐ NO

If yes, give details:

16" from 0 to 52'; 11 3/4" from 0 to 866'
8 5/8" from 0 to 3388'

Did a Service Company pump mud, spot cement, or set bridge plugs?

☒ YES ☐ NO

If yes, give name and address:

Dowell
Kalkaska, Michigan

Was the well plugged by a Company or Contractor other than Owner or Operator?

☒ YES ☐ NO

If yes, give name and address:

Nicor Drilling
Gaylord, Michigan 49735

Representatives of Owner, Operator, Company, or Contractor who witnessed plugging:

Rudolph S. Cadena

DESCRIBE IN DETAIL HOW WELL WAS PLUGGED. Went in hole with drill pipe open ended to 6293' and spotted 125 sacks of Class A cement. Pulled up the hole to 4030' and spotted 250 sacks of Hi-dense cement for kickoff plug.

(USE REVERSE SIDE IF NEEDED)

CERTIFICATION

I certify that I am authorized by said Owner or Operator to make this report; and that this report was prepared under my supervision and direction, and that the facts stated herein are true, correct and complete to the best of my knowledge."

NAME AND TITLE (Typed or Printed)

Rudolph S. Cadena, Drilling Supervisor

COMPANY NAME AND ADDRESS

Traverse Oil Company
P. O. Box 1053
Traverse City, MI 49684

SIGNATURE

Rudolph S. Cadena

DATE (Month, Day, Year)

4-15-81

Description of Detail (cont.) or Other Supplemental Data:

DEPARTMENT USE ONLY

Supplemental Plugging Data and Site Conditions:

- 5/19/81 can recommend approval. Hole redrilled under PN35006.
(Booker)

FINAL INSPECTIONS BY DEPARTMENT REPRESENTATIVES

SIGNATURE	DIVISION	DATE
William Booker	Geological Engineering	5-20-81

STATE OF MICHIGAN
DEPARTMENT OF NATURAL RESOURCES
LOG OF OIL, GAS, DISPOSAL OR STORAGE WELL (ACT 61)
Submit in **DUPLICATE** Within 30 Days after Well Completion
LANSING HAS ORIGINAL

NOV 5 1981

PERMIT NUMBER 34506

Page C-29

DEEPENING PERMIT NUMBER

NAME(S) & ADDRESS OF OWNER(S) SHOWN ON PERMIT Traverse Oil Company P. O. Box 1053 Traverse City, MI 49684				NAME & ADDRESS OF DRILLING CONTRACTOR(S) Nicor Drilling Company P. O. Box 36 Gaylord, MI 49735				
LEASE NAME(S) & WELL NUMBER SHOWN ON PERMIT Weber #3-88						DIRECTIONALLY DRILLED YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>		
SURFACE LOCATION SE NW NE		SECTION 8	TOWNSHIP 25N	RANGE 11W	TOWNSHIP NAME Mayfield			
FOOTAGES (North/South) 854 Ft. from North		Line and 1140		Ft. from West		COUNTY NAME Grand Traverse		
SUBSURFACE LOCATION SE NE NE		SECTION 8	TOWNSHIP 25N	RANGE 11W	TOWNSHIP NAME Mayfield			
FOOTAGES (North/South) 820 Ft. from North		Line and 903		Ft. from East		COUNTY NAME Grand Traverse		
DATE	DRILLING BEGUN 4-09-81		TOTAL DEPTH OF WELL Driller 6154' Log 6138'		TYPE WELL NEGATIVE COMPLETION		ELEVATIONS	
	DRILLING COMPLETED 4-16-81		FORMATION AT T.D. Niagaran		FT. DRLD. - ROTARY TOOLS From 0 To T.D.			K.B. 1108.2'
	WELL COMPLETED		PRODUCING FORMATION(S) None		FT. DRLD. - CABLE TOOLS From To			R.T. Grd. 1093.2'

CASING, CASING LINERS AND CEMENTING

PERFORATIONS

SIZE	WHERE SET	CEMENT	Ft. Pulled	DATE	NUMBER HOLES	INTERVAL PERFORATED	OPEN	
							YES	NO
5 1/2"	6154'	350 SX	4418'	5/28	11	5956-5966'	X	

GROSS PAY INTERVALS

ALL OTHER OIL AND GAS SHOWS OBSERVED OR LOGGED

FORMATION	OIL OR GAS	FROM	TO	FORMATION	OIL OR GAS	DEPTH	WHERE OBSERVED (X)					
							Sam- ples	Odor	Pits	Mud Line	Gas Log.	Fill Up

STIMULATION BY ACID OR FRACTURING

WATER FILL UP (F.U.) OR LOST CIRCULATION (L.C.) (X)

DATE	Interval Treated	Materials and amount used	FORMATION	F.U.	L.C.	DEPTH	AMOUNT
5/29	5956-66'	1250 gals. 28% HCL					

MECHANICAL LOGS, LIST EACH TYPE RUN

DEPTH CORRECTION DEVIATION SURVEY PLUGGED BACK

Brand	(X)	LOG TYPES	LOGGED INTERVALS	DEPTH	CORRECT'N	RUN AT	DEGREES	YES	NO	DEPTH
Schlumberger	X	CNL/FDC	3370-6135'		SEE ATTACHED	SURVEY	REPORT			
Birdwell		DLL/Micro	5750-6130'							

PRODUCTION TEST DATA

OIL - Bbls/day	GRAVITY - °API	COND. Bbls/day	GAS - MCF/day	WATER - Bbls/day	H ₂ S - Grains/100 cu. ft.	B.H.P. AND DEPTH

I AM RESPONSIBLE FOR THIS REPORT. THE INFORMATION IS COMPLETE AND CORRECT.

DATE 11-2-81	NAME AND TITLE (PRINT) Christopher B. Kesiter, Geologist	SIGNATURE <i>Christopher B. Kesiter</i>
-----------------	---	--

NOTICE REPORT COMPLETE SAMPLE AND FORMATION RECORD AND DRILL STEM TEST INFORMATION ON REVERSE SIDE

R - 7210

FORMATION RECORD

(ATTACH ADDITIONAL SHEETS IF NECESSARY)

Page C-30

ELEVATION USED: 1108.2' KB	GEOLOGIST NAME: Daniel J. Hendrix	TOPS TAKEN FROM: <input type="checkbox"/> DRILLERS LOG <input type="checkbox"/> SAMPLE LOG <input checked="" type="checkbox"/> ELECTRIC LOG
-------------------------------	--------------------------------------	--

FROM	TO	FORMATION (TYPE, COLOR, HARDNESS)	FROM	TO	FORMATION (TYPE, COLOR, HARDNESS)
NOTE: IF WELL DIRECTIONALLY DRILLED, ADD TRUE VERTICAL DEPTH FORMATION TOPS WHERE APPROPRIATE.					
3546'	MD	Amherstburg	3545.8'		TVD
3734'		Bois Blanc	3733.8'		TVD
4146'		Bass Island	4141.1'		TVD
4446'		Salina G Unit	4434.2'		TVD
4479'		F Unit	4466.6'		TVD
4512'		F Salt	4498.9'		TVD
5134'		E Unit	5103.5'		TVD
5264'		D Unit	5228.6'		TVD
5277'		D Salt	5241.1'		TVD
5292'		C Shale	5255.5'		TVD
5370'		B Unit	5330.6'		TVD
5410'		B Salt	5369.2'		TVD
5783'		A2 Carbonate	5719.2'		TVD
5871'		A2 Evaporite	5800.4'		TVD
5934'		A1 Carbonate	5858.5'		TVD
5964'		Niagaran Reef	5886.2'		TVD
6134'		Logger's Total Depth	6042.7'		TVD
6154'		Driller's Total Depth	6061.1'		TVD
IF WELL WAS CORED. ATTACH CORE DESCRIPTION					
DRILL STEM TEST DATA					

STATE OF MICHIGAN
DEPARTMENT OF NATURAL RESOURCES
GEOLOGICAL SURVEY DIVISION

NOV 5 1981

DANSING HAS CCM Page C-31

WELL PLUGGING RECORD

(Submit in TRIPLICATE Within 30 Days After Plugging is Completed)

PERMIT NUMBER

34506

FIELD NAME

COMPLETE NAME(S) AND ADDRESS OF WELL OWNER

Traverse Oil Company, P. O. Box 1053, Traverse City, Michigan 49684

COMPLETE LEASE OR FARM NAME(S)

Weber

WELL NUMBER

#3-8B

WELL LOCATION

SE 1/4 NW 1/4 NE 1/4 SEC. 8

T. 25N

R. 11W

TOWNSHIP

Mayfield

COUNTY

Grand Traverse

TYPE OF WELL (Oil, Gas, Dry Hole, etc.)

NEGATIVE COMPLETION - DRY HOLE

TOTAL DEPTH

6154'

FORMATION

Niagaran

DATE PLUGGING STARTED

9-2-81

DATE PLUGGING COMPLETED

9-4-81

DEPT. REPRESENTATIVE(S) WHO ISSUED PERMIT OR WITNESSED PLUGGING

Jerome F. Wendel

CASING RECORD

SIZE CASING	DEPTH SET	AMOUNT RECOVERED	SHOT OR RIPPED
5 1/2"	6154'	4418'	CUT

BRIDGES OR PLUGS

TYPE (Brush, Stone, Cement, Mechanical, etc.)	DEPTH PLACED	SACKS OF CEMENT AND ADDITIVES
CEMENT RETAINER	5840'	50 sx under & 30 sx on top
CEMENT-KICKOFF PLUG	4012-3550'	165 sacks

Were tools, tubing, casing, etc., lost or left in the hole before or during plugging?

☒ YES ☐ NO

If yes, give details:

16" from 0 to 52', 11 3/4" from 0 to 866', 8 5/8" from 0 to 3388', 5 1/2" from 4418' to 6154'

Did Service Company pump mud, spot cement, or set bridge plugs?

☒ YES ☐ NO

If yes, give name and address:

McCullough
Kalkaska, Michigan

Was the well plugged by a Company or Contractor other than Owner or Operator?

☒ YES ☐ NO

If yes, give name and address:

Reef Petroleum
Traverse City, MI 49684

Representatives of Owner, Operator, Company, or Contractor who witnessed plugging:

Larry Anderson

DESCRIBE IN DETAIL HOW WELL WAS PLUGGED

Tripped in hole with 5 1/2" EZSV retainer and set at 5840'. Filled and circulated hole. Put 50 sacks of cement under retainer and 30 sacks of cement on top. Pulled 6 stands and reverse circulated. Stood back 76 stands and laid down 40 joints. Rigged down BOPs and tubing spool. Welded slips to casing. Pulled slips out. Freepoint 5 1/2" casing - free at 4418'. Cut 5 1/2" casing at 4418'. Pulled 5 1/2" casing - 99 joints + 1 - 25' cut off. Bottom at 4012'. Circulated hole with fresh water. Mixed 165 sacks of cement 4012' to 3550' for kickoff plug. Pulled 12 stands. Reverse circulated. Laid down tubing.

(USE REVERSE SIDE IF NEEDED)

CERTIFICATION

"I certify that I am authorized by said Owner or Operator to make this report; and that this report was prepared under my supervision and direction and that the facts stated herein are true, correct and complete to the best of my knowledge."

NAME AND TITLE (Typed or Printed)

Christopher B. Keister, Geologist

COMPANY NAME AND ADDRESS

Traverse Oil Company
P. O. Box 1053
Traverse City, MI 49684

SIGNATURE

Christopher B. Keister

DATE (Month, Day, Year)

11-2-81

Description of Detail (cont.) or Other Supplemental Data:

DEPARTMENT USE ONLY

Supplemental Plugging Data and Site Conditions:

12/1/81 All records in. Hole directionally drilled under PN34968 Weber 3-8"C".
OK for GS approval. (Snider)

FINAL INSPECTIONS BY DEPARTMENT REPRESENTATIVES

SIGNATURE

DIVISION

DATE

John H. Snider

Geology

12/1/81

DATE	HOLES	DEPTH	ACID	REMARKS
			CUT REC.	DST 1
CORE 1				
CORE 2				
CORE 3				
CORE 4			IHMP	FSIP
CORE 5			ISIP	FHMP
CORE 6			IFP	
CORE 7			FFP	
CORE 8				
9/10/81 Plan to K0 at 3700' w/dyna drill.				
W/ dyna drill. Plan to K0 at 3700' w/dyna drill. Plan to put away reserve pit fl down the 113/4" 8/58" annulus. Will spud this PM Dir S85°W (JFW) 9/14/81 last survey: 5589' md 7.75° angle dir S11°W, vert sect 218.61 IHMP FSIP				
TVD 5577.94 coords S92.90, W198.5 ISIP FHMP				
Keeping pits pumped off down the IFP				
annl below torn lnr. Pre May 1st FFP				
guidelines on pit lnr (JFW) 9/16/81 mud 10.8 vis 29 w/l 18 chls 200,000 PPM. Last survey MD 5808 DST 3				
TVD 5793 vert sec 259.0, dir S12½°W Coords 5103.0 and 238' W (JFW)				
9/17/81 ran full str 5½" csg to 6149 (MD) cmdt w/100 sx fill up & 200 sx tail slurry (Dowell) drld compld 11 am 9/16 putting away &				
drlg. fluids down the annulus Rig IHMP FSIP				
to move to Berry 2-14 A (CLEON, ISIP FHMP				
MANISTEE) (JFW) 10/14/81 pits have been pumped off and filled in FFP				
Leveling loc prior to setting prod equip Will go on pump immediately (JFW)				
CORRECTIONS				
R7304 R/73				

Unit PI A Permit No. 34968
Co. Mosbacher Prod. Co.
Lease Weber No. 3-8C
Twp. Mayfield Co. Gr. Trav.
Loc. SE NW NE Sec. 8 T. 25 R. 11
from and from line of 1/4 Sec.
Contractor Will Notify
Comm. 9/17/81 Comp. 8
PLUGGING SUMMARY

HOLES			CASING			CEMENT		
Dia.	Depth		Dia.	Wt.	Depth	Sacks	TOC	
16"			52"		driven, existing			
11 3/4"			866		circul.			
8 5/8"			3380		300SX TOC		2910	
KOP	@		3800		perfs: 5066-		80	
5Y2	@		6149					

HOLES			CASING			CEMENT		
Dia.	Depth		Dia.	Wt.	Depth	Sacks	TOC	
16"			52"		driven, existing			
11 3/4"			866		circul.			
8 5/8"			3380		300SX TOC		2910	
KOP	@		3800		perfs: 5066-		80	
5Y2	@		6149					

KB 1109.8'
RIH w/ 51/2" cmt. ret. to 6000' &
squeeze off perfs. w/ 50 sx thru
& 50 sx on top. FP, cut & pull
5 1/2" csg. Rerun DP to 3450'
& spot 100 sx below 8 5/8" csg.
shoe. FP, cut & pull 8 5/8" csg.
Run DP to 2600' & spot 75sx below
Od top. Pull DP to 1700 & spot
75sx @ 11 top. Pull DP to 900 &
spot 75sx below sur. csg. shoe.
Place 15sx @ the top. Cut off
sg. 3' below gr. level & weld
in a 1/2" steel plate.

Date PI 9/3/81 Permit No. 35006
Co. Trav Oil Co.
Lease Weber No. 3-8B
Twp. Mayfield Co. Grand Trav.
Loc. SE NW NE, Sec. 8 25N R. 11W
from and from line of 1/4 Sec.
Contractor Dowell Tally Compl Rig
Comm. plug 9/3/81 Comp. 8
PLUGGING SUMMARY

HOLES			CASING			CEMENT		
Dia.	Depth		Dia.	Wt.	Depth	Sacks	TOC	
16"	52							
5 1/2"	6154							
Lower perfs:	5993-95-97-99-6001-05-07							
7 holes in	14' 5956-66 (1 JSPF or 11							
holes								

HOLES			CASING			CEMENT		
Dia.	Depth		Dia.	Wt.	Depth	Sacks	TOC	
16"	52							
5 1/2"	6154							
Lower perfs:	5993-95-97-99-6001-05-07							
7 holes in	14' 5956-66 (1 JSPF or 11							
holes								

RIH w/ 5 1/2" cmt ret to 5850 Squeeze 50
sx thru & spot 35 sx on top. Freept
and pull 5 1/2" csg. Spot 200 sx HiDense
KOP at 4000'. Calculated TOC 3475'.
KOP at 3700' in the BI.

Unit MDSBACHER VERGE
Co. Trav Oil Co. Permit No. 34968
Lease Weber No. 3-8C
Twp. Mayfield Co. Grand Trav.
Loc. SE NW NE, Sec. 8 T. 25H R. 11W
from and from line of 1/4 Sec.
Contractor Reef Drlg.
Comm. 8
PLUGGING SUMMARY

HOLES			CASING			CEMENT		
Dia.	Depth		Dia.	Wt.	Depth	Sacks	TOC	
16"	52							
11 3/4"	866							
8 5/8"	@ 3380						10C 2910	
5Y2	@ 6149							

HOLES			CASING			CEMENT		
Dia.	Depth		Dia.	Wt.	Depth	Sacks	TOC	
16"	52							
11 3/4"	866							
8 5/8"	@ 3380						10C 2910	
5Y2	@ 6149							

16" 60# condr existing: 113/4"
42# H40 new exiting: 85/8" 32#
K55 existing: 5 1/2" 15.5# K55
6450' w/ 300 sx.
SAME SURF AS PH 34413. 34489. 34506

Bar 5 1/2" for 0149
on 9/17/81
Frac on 9/25/81

Fractured 15-3000
Prod. Corp 7/16/82

Form	Depth	Log	Datum	Form	Depth	Log	Datum
Drift				B.B.			
				BI			
				Sal			
				F			
				E			
				D			
				C			
				BEV			
				A2C			
				A2Ev			
				A1C			
				Pay			
				A-1 Ev			
				BN			
				Pay			
				GN			
				CI			
				Cinn			
				U			
				Trent			
				Pay			
				BRF			
				Gw			
				SP			
				Pdc			
				Camb			
				PE			
				TD			
				PBTD			
				I.P.			
Sylv.							
Plug g Permit				CORES, D.S.T.'s, Shows, L.C.Z.'s.			
Plug g Comm.							
Plug g Comp.							
Plug g Record							
Site Recl'm							
Site App'l.							
R-7217							

P/N 321968

Form	Depth	Log	Datum	Form	Depth	Log	Datum
Drift				BI			
				Sal			
				F			
				E			
				C			
				BEV			
				A2C			
				A2Ev			
				A1C			
				Pay			
				A-1 Ev			
				BN			
				Pay			
				GN			
				CI			
				Cinn			
				U			
				Trent			
				Pay			
				BRF			
				Gw			
				SP			
				Pdc			
				Camb			
				PE			
				TD			
				PBTD			
				I.P.			
Sylv.							
Plug g Permit				CORES, D.S.T.'s, Shows, L.C.Z.'s.			
Plug g Comm.							
Plug g Comp.							
Plug g Record							
Site Recl'm							
Site App'l.							
R-7217							

P/N 35006

Form	Depth	Log	Datum	Form	Depth	Log	Datum
Drift				BI			
				Sal			
				F			
				E			
				C			
				BEV			
				A2C			
				A2Ev			
				A1C			
				Pay			
				A-1 Ev			
				BN			
				Pay			
				GN			
				CI			
				Cinn			
				U			
				Trent			
				Pay			
				BRF			
				Gw			
				SP			
				Pdc			
				Camb			
				PE			
				TD			
				PBTD			
				I.P.			
Sylv.							
Plug g Permit				CORES, D.S.T.'s, Shows, L.C.Z.'s.			
Plug g Comm.							
Plug g Comp.							
Plug g Record							
Site Recl'm							
Site App'l.							
R-7217							

P/N 34968

☒ FIELD
☒ EXPLORATORY WYBELL - 256.12 PERMIT 34968
☐ FACILITY D.P.
☐ OTHER RECORDS DUE:

OPERATOR: Traverse Oil Co.FARM: Weber 3-8"C"COUNTY Grand Trav.TWP. MayfieldLOCATION SE NW NE, S8 T25 RT1

NL _____ SL _____ EL _____ WL _____

CASING RECORD

SIZE	AMOUNT	CEMENT
16"	52	
11 7/8"	566	500
10		
8 7/8"	2785	300
7		
6		
5 1/2"	6149	300
Liner		

CONTRACTOR
 Reef Drlg.

ROTARY ☒CABLE ☐COMB. ☐

FREEDOM #1

9/10/81 KOP at 3550'
 to 4012 will spud PM

KOP 3700

9/14 Ø 77/8" hole at
 5589 in B Sal-t

9/16 RTD 77/8" hole at
 6049 (MD) in BNia

Iss tent. PI prior to log
 by Schlumb WOO
 9/17/81

ELEVATIONS

RIG FLOOR
K.B. 1109.8
R.T.Platf. 1108.3
GROUND 1094.3
DRLG. COMM. 9/10/81
DRLG. COMP. 9/17/81
WELL COMP. 1/11/82
DEEP. COMM.
DEEP. COMP.
LOST CIRC. ZONES

POROSITY

STRAY
MARSH
BE.
TL
DD
RCD
DR
SZ
RICH.
E
A1
NIAG.
TRENT
BRF
VW

WELL COMPLETED AS:
 PRODUCING FORMATION
 GRAVITY API

OIL ☒ GAS ☐

N/A

(N) IP

(A) IP 140 RPT & 100 M-F & 100 G-W

CHOKE _____ TP _____ CP _____

FORM.	DEPTH	LOG	DATUM
DRIFT	MD/TVD		
TG	BOD		
BL			
STRAY			
MARSH			
CRR			
SUN			
BE			
ANT			
TF			
TL	BB 3698/3697.5		
ALP	BI 4130. 4126.9		
BELL	SAL 4434. 4429		
DD	FU 4465 4459.8		
RCA	FS 4498 4492.7		
RCD	EU 5106 5097.5		
DR	DU 5228. 5218.9		
SYLV	DS 5242 5332.8		
BB	CSH 5254 5244.7		
BI	BU 5328 5318.8		
SAL	BS 5370 5318.8		
E	A2C 5760 5360		
D	A2E 5860 5843.4		
C	A1C 5968 5949		
B EVAP	B Nia 6054 6083		
A2CARB	GR 6148 6123.9		
A2EVAP	DTD 6149 MD		
A1CARB	6125.9 TVD		
A1EVAP	LTD 6144 MD		
B NIAG			
W NIAG			
CL			
CINN			
TRENT			
BRF			
GW			
SP			
PDC			
CAMB			
PREC			
PBTD			
T.D.			

WELL PLUGGING RECORD

(Submit in TRIPLICATE Within 30 Days After Plugging is Completed)

PERMIT NUMBER
34968

FIELD NAME
Mayfield 8

COMPLETE NAME(S) AND ADDRESS OF WELL OWNER

Mosbacher Energy Company, 712 Main, Suite 2200, Houston, TX. 77002-3290

COMPLETE LEASE OR FARM NAME(S)

Weber

WELL NUMBER
3-8C

WELL LOCATION

SE ¼ NW ¼ NE ¼ SEC. 8 T. 25N R. 11W

TOWNSHIP
Mayfield

COUNTY
Gr. Traverse

TYPE OF WELL (Oil, Gas, Dry Hole, etc.)

Dry Hole

TOTAL DEPTH
6149'

FORMATION
Niagran

DATE PLUGGING STARTED
6/9/86

DATE PLUGGING COMPLETED
6/13/86

DEPT. REPRESENTATIVE(S) WHO ISSUED PERMIT OR WITNESSED PLUGGING
Jerome F. Wendel

CASING RECORD

SIZE CASING	DEPTH SET	AMOUNT RECOVERED	SHOT OR RIPPED
16	52'	--	--
11-3/4	866'	--	--
8-5/8	3380'	2789'	2789'
KOP @	3800	--	--
5-1/2	6149	4400	4400

BRIDGES OR PLUGS

TYPE (Brush, Stone, Cement, Mechanical, etc.)	DEPTH PLACED	SACKS OF CEMENT AND ADDITIVES
Cement Retainer	6000	50 SXS
Cement plug	3450	100 SXS
Cement plug	2600	75 SXS
Cement plug	1700	75 SXS
Cement plug	900	75 SXS
Cement plug	60	15 SXS

Were tools, tubing, casing, etc., lost or left in the hole before or during plugging?

☐ YES ☒ NO

If yes, give details:

Was a Service Company pump mud, spot cement, or set bridge plugs?

☒ YES ☐ NO

If yes, give name and address:

Welltech Rig #159, 2284 Enterprise Dr.
Mt. Pleasant, MI. 48858

Was the well plugged by a Company or Contractor other than Owner or Operator?

☐ YES ☒ NO

If yes, give name and address:

Representatives of Owner, Operator, Company, or Contractor who witnessed plugging:

Don Hester

DESCRIBE IN DETAIL HOW WELL WAS PLUGGED

(SEE ATTACHED)

(USE REVERSE SIDE IF NEEDED)

CERTIFICATION

"I certify that I am authorized by said Owner or Operator to make this report; and that this report was prepared under my supervision and direct control and that the facts stated herein are true, correct and complete to the best of my knowledge."

NAME AND TITLE (Typed or Printed)

Frances Tepera, Engineering Asst.

SIGNATURE

Frances Tepera

DATE (Month, Day, Year)

6/17/86

COMPANY NAME AND ADDRESS

Mosbacher Energy Company
712 Main, Suite 2200
Houston, TX 77002-3290

Description of Detail (cont.) or Other Supplemental Data:

DEPARTMENT USE ONLY

Supplemental Plugging Data and Site Conditions:

Loc. levelled & contoured. slopes in gravel pit re-shaped. all equip removed from loc.

FINAL INSPECTIONS BY DEPARTMENT REPRESENTATIVES

SIGNATURE

DIVISION

DATE

Jerome F Wendell

Geol. Survey

7/15/86

OPERATIONS IN SEQUENCE:

Page C-39

600 psi SICP. Blew well dead. Pumped 142 bbl 10# brine in casing.
Well on vacuum.

Welded 2" nipple in 5-1/2" casing, pulling nipple.

Moved in tubing string.

OPERATIONS IN SEQUENCE:

MIRU Welltech Rig #159.

Tried changing out rams in BOP's. (2 hr rig time)

Installed BOP's, ran in hole w/tubing, picked up off ground 4374' of
2-3/8" & 1626' of 2-7/8".

Set cement retainer @ 6000'.

Had trouble getting rabbit to go thru tubing, (7 hr going in hole).
Stung out of retainer.

Circ fresh water around tubing. 133 bbl used.

Stung back in and ran injection test-6 BPM @ 100 psi,

Hydraulic pump went out on rig.

SION @ 9:30 pm.

OPERATIONS IN SEQUENCE:

Repaired hydraulic pump on rig.

Squeezed 50 sx common cement in perf's.

FPF 1600 psi.

Spotted 50 sx on top of retainer.

TOH w/tubing.

Tried to pull 5-1/2" casing, worked on rig clutch 3 1/2 hr.

Clutch finally repaired, able to pull slips on 5 1/2" casing.

RU Sego.

Free point and shot off 5 1/2" @ 4400'. Pulled 16 jts. 5 1/2" casing.

Welltech casing tongs were washing casing.

SION @ 8:30 pm.

OPERATIONS IN SEQUENCE:

RU Casing crew.

TOH w/5 1/2" casing. Total of 114 joints (4441').

TIH w/tubing to 3450'. Spot 100 sx.

TOH w/tubing. Free point and cement 8" casing @ 2800'.

SION.

OPERATIONS IN SEQUENCE:

RU Niagaran. Lay down 69 joints 8-5/8" casing. (Total 2789').

TIH w/tbg to 2600'. Spot 75 sx cement.

COOH, ly down tbg.

Spot 75 sx @ 1700', 75 sx @ 900' & 15 sx @ 60'.

RD MO service rig.

Welded plate on 11-3/4" below ground. Cut and capped all flow lines
Below ground.

STATE OF MICHIGAN
DEPARTMENT OF NATURAL RESOURCES
LOG OF OIL, GAS, DISPOSAL OR STORAGE WELL (ACT 61)
Submit in DUPLICATE Within 30 Days after Well Completion

PERMIT NUMBER
34594
DEEPENING PERMIT NUMBER

FEB 03 1983

Page C-40

NAME(S) & ADDRESS OF OWNER(S) SHOWN ON PERMIT Great Lakes Niagaran P.O. Box 466 Traverse City, MI 49684				NAME & ADDRESS OF DRILLING CONTRACTOR(S) Nicor Drilling Company Gaylord, MI 49735				
LEASE NAME(S) & WELL NUMBER SHOWN ON PERMIT Berry #2-8						DIRECTIONALLY DRILLED YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>		
SURFACE LOCATION NE/4 SW/4 NE/4		SECTION 8		TOWNSHIP 25N		RANGE 11W		
TOWNSHIP NAME Mayfield		COUNTY NAME Grand Traverse						
FOOTAGES (North/South) 854 Ft. from South		Line and 825		(East/West) Ft. from West		Line of quarter section		
SUBSURFACE LOCATION Same		SECTION		TOWNSHIP		RANGE		
TOWNSHIP NAME		COUNTY NAME						
FOOTAGES (North/South)		Line and		(East/West)		Line of quarter section		
TOWNSHIP NAME		COUNTY NAME						
DATE	DRILLING BEGUN 5/16/81		TOTAL DEPTH OF WELL Driller 6225 Log 6211		TYPE WELL Oil		ELEVATIONS	
	DRILLING COMPLETED 5/25/81		FORMATION AT T.D. Niagaran		FT. DRLD. - ROTARY TOOLS From - To 6211		K.B. 1104.3	R.F.
	WELL COMPLETED 12/21/81		PRODUCING FORMATION(S) Niagaran		FT. DRLD. - CABLE TOOLS From - To		R.T.	Grd. 1088.9

CASING, CASING LINERS AND CEMENTING

PERFORATIONS

SIZE	WHERE SET	CEMENT	Ft. Pulled	DATE	NUMBER HOLES	INTERVAL PERFORATED	OPEN	
16"	90	Driven					YES	NO
11 3/4"	890	300 sx		6/15/81	12	6000-6006		
8 5/8"	3362	300 sx		12/15/81	7	6021-6024		
5 1/2"	6210	250 sx	4500					

GROSS PAY INTERVALS

ALL OTHER OIL AND GAS SHOWS OBSERVED OR LOGGED

FORMATION	OIL OR GAS	FROM	TO	FORMATION	OIL OR GAS	DEPTH	WHERE OBSERVED (X)					
Niagaran	Oil	6000	6024	-			Sam- ples	Odor	Pits	Mud Line	Gas Log.	Fill Up

STIMULATION BY ACID OR FRACTURING

WATER FILL UP (F.U.) OR LOST CIRCULATION (L.C.) (X)

DATE	Interval Treated	Materials and amount used	FORMATION	F.U.	L.C.	DEPTH	AMOUNT
6/15/81	6000-6006	500 gals 28% acid					
6/30/81	"	4000 gals 15% HCL Acid					
"	"	3000 gals 15% HCL Gelled					
12/15/81	6021-6024	500 gals 28% Acid					

MECHANICAL LOGS, LIST EACH TYPE RUN

DEPTH CORRECTION DEVIATION SURVEY PLUGGED BACK

Brand	(X)	LOG TYPES	LOGGED INTERVALS	DEPTH	CORRECT'N	RUN AT	DEGREES	YES	NO	DEPTH
Schlumberger	X	CNL/LDT	200-6211							
Birdwell		DLL/MLL	5700-6205							

PRODUCTION TEST DATA

L - Bbls/day	GRAVITY - °API	COND. Bbls/day	GAS - MCF/day	WATER - Bbls/day	H ₂ S - Grains/100 cu. ft.	B.H.P. AND DEPTH
20	46	-	-	100	nil	-

I AM RESPONSIBLE FOR THIS REPORT. THE INFORMATION IS COMPLETE AND CORRECT.

DATE 2/1/83	NAME AND TITLE (PRINT)	Linda McConnell	Agent
-------------	------------------------	-----------------	-------

NOTICE REPORT COMPLETE SAMPLE AND FORMATION RECORD AND DRILL STEM TEST INFORMATION ON REVERSE SIDE R - 7210

FORMATION RECORD

(ATTACH ADDITIONAL SHEETS IF NECESSARY)

Page C-41

ELEVATION USED:	GEOLOGIST NAME:	TOPS TAKEN FROM:	
KB: 1104.3	McConnell	<input type="checkbox"/> DRILLERS LOG	<input type="checkbox"/> SAMPLE LOG <input checked="" type="checkbox"/> ELECTRIC LOG

TO	FORMATION (TYPE, COLOR, HARDNESS)	FROM	TO	FORMATION (TYPE, COLOR, HARDNESS)
----	--------------------------------------	------	----	--------------------------------------

NOTE: IF WELL DIRECTIONALLY DRILLED, ADD TRUE VERTICAL DEPTH FORMATION TOPS WHERE APPROPRIATE.

0	780	Drift - sandstone		
780	1502	Base of Drift - sandstone		
1502	1712	Antrim - Shale		
1712	1787	Traverse Fmt - ls, lt gy		
1787	2352	Traverse Lime - ls, lt to m/brn		
2352	2455	Bell Shale- sh, dk gy		
2455	2640	Dundee - ls, m/brn		
2640	3212	Detroit River Salt - salt		
3212	3612	Base Det River Salt - Anhy		
3612	3740	Amherstburg -ls, dk brn		
3740	4139	Bois Blanc -chert		
4139	4437	Bass Islands - dol, m/brn		
4437	4468	G Unit-sh, lt gy		
4468	4500	F Unit-dol, lt brn tan		
4500	5106	F Salt -slat		
5106	5226	E Unit - Dol, m/brn		
5226	5256	D Unit - salt		
5256	5328	C Shale-shale		
5328	5356	B Unit - dol, lt brn		
5356	5746	B Salt - See Mud Log		
5746	5832	A2 Carb		
5832	5952	A2 Evap		
5952	6000	A1 Carb		
6000		Reef		

IF WELL WAS CORED, ATTACH CORE DESCRIPTION

DRILL STEM TEST DATA

STATE OF MICHIGAN
DEPARTMENT OF NATURAL RESOURCES
GEOLOGICAL SURVEY DIVISION

Page C-42

WELL PLUGGING RECORD

(Submit in TRIPLICATE Within 30 Days After Plugging is Completed)

PERMIT NUMBER

34594

FIELD NAME

FEB 03 1993

COMPLETE NAME(S) AND ADDRESS OF WELL OWNER

Great Lakes Niagaran, P.O. Box 466, Traverse City, MI 49684

COMPLETE LEASE OR FARM NAME(S)

Berry 2-8

WELL NUMBER

2-8

WELL LOCATION

NE 1/4 SW 1/4 NE 1/4 SEC. 8 T.25N R.11W

TOWNSHIP

Mayfield

COUNTY

Grand Traverse

TYPE OF WELL (Oil, Gas, Dry Hole, etc.)

Oil

TOTAL DEPTH

6210

FORMATION

Niagaran

DATE PLUGGING STARTED

1/4/83

DATE PLUGGING COMPLETED

1/11/83

DEPT. REPRESENTATIVE(S) WHO ISSUED PERMIT OR WITNESSED PLUGGING

Jerry Wendel

CASING RECORD

SIZE CASING	DEPTH SET	AMOUNT RECOVERED	SHOT OR RIPPED
16"	90	Driven	
11 3/4"	890		
8 5/8"	3362		
5 1/2"	6210	4500'	

BRIDGES OR PLUGS

TYPE (Brush, Stone, Cement, Mechanical, etc.)	DEPTH PLACED	SACKS OF CEMENT AND ADDITIVES
Cement	5950	50 sx
"	4500	100 sx

Were tools, tubing, casing, etc., lost or left in the hole before or during plugging?

☒ YES ☐ NO

If yes, give details:

See Casing Record

Did a Service Company pump mud, spot cement, or set bridge plugs?

☒ YES ☐ NO

If yes, give name and address:

Dowell
Kalkaska, MI

Was the well plugged by a Company or Contractor other than Owner or Operator?

☒ YES ☐ NO

If yes, give name and address:

T & J Tank #1
Kalkaska, MI

Representatives of Owner, Operator, Company, or Contractor who witnessed plugging:

John Vandekerckhof

DESCRIBE IN DETAIL HOW WELL WAS PLUGGED

Set Retainer at 5950. Perfs Would not take cement. Dumped 50 sx on top of retainer at 5950. Feepointed, cut & pulled 5 1/2" casing at 4500'. Spotted 100 sx High dense cement as Kickoff plug.

(USE REVERSE SIDE IF NEEDED)

CERTIFICATION

"I certify that I am authorized by said Owner or Operator to make this report; and that this report was prepared under my supervision and direction and that the facts stated herein are true, correct and complete to the best of my knowledge."

NAME AND TITLE (Typed or Printed) Linda McConnell, Sec/Treas

McConnell Consulting, Inc.

COMPANY NAME AND ADDRESS

McConnell Consulting, Inc.

SIGNATURE

DATE (Month, Day, Year)

2/2/83

1515 Cass

Traverse City, MI 49684

STATE OF MICHIGAN
DEPARTMENT OF NATURAL RESOURCES
LOG OF OIL, GAS, DISPOSAL STORAGE WELL (ACT 61)
Submit in DUPLICATE Within 30 Days after Well Completion

PERMIT NUMBER
6359
DEE: **ING PERMIT NUMBER**
Page C-43
JUL 09 1983

NAME(S) & ADDRESS OF OWNER(S) SHOWN ON PERMIT Great Lakes Niagaran P.O. Box 466 Traverse City, MI 49684				NAME & ADDRESS OF DRILLING CONTRACTOR(S) McLachlan Drilling Company Evart, MI 49631				
LEASE NAME(S) & WELL NUMBER SHOWN ON PERMIT Berry 2-8A						DIRECTIONALLY DRILLED YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>		
SURFACE LOCATION NE$\frac{1}{4}$ SW$\frac{1}{4}$ NE$\frac{1}{4}$		SECTION 8		TOWNSHIP T25N		RANGE R11W		
TOWNSHIP NAME Mayfield		COUNTY NAME Grand Traverse						
FOOTAGES (North/South) 854 Ft. from South Line and 825 Ft. from West Line of quarter section								
SUBSURFACE LOCATION NE$\frac{1}{4}$ SW$\frac{1}{4}$ NE$\frac{1}{4}$		SECTION 8		TOWNSHIP T25N		RANGE R11W		
TOWNSHIP NAME Mayfield		COUNTY NAME Grand Traverse						
FOOTAGES (North/South) 984 Ft. from South Line and 760 Ft. from West Line of quarter section								
DATE	DRILLING BEGUN 1-17-83		TOTAL DEPTH OF WELL Driller 6065 Log 6063		TYPE WELL Oil		ELEVATIONS	
	DRILLING COMPLETED 1-25-83		FORMATION AT T.D. Niagaran		FT. DRLD. - ROTARY TOOLS From _____ To _____		K.B. 1103.3	R.F.
	WELL COMPLETED 5-8-83		PRODUCING FORMATION(S) Niagaran		FT. DRLD. - CABLE TOOLS From _____ To _____		R.T.	Grd. 1088.9

CASING, CASING LINERS AND CEMENTING

PERFORATIONS

SIZE	WHERE SET	CEMENT	Ft. Pulled	DATE	NUMBER HOLES	INTERVAL PERFORATED	OPEN	
							YES	NO
16"	90	Driven						
11 3/4"	890	300 SX		2-5-83	18	5880-5977		
8 5/8"	3362	300 SX		4-2-83	4	6022-6025		
5 1/2"	6064	150 SX						

GROSS PAY INTERVALS

ALL OTHER OIL AND GAS SHOWS OBSERVED OR LOGGED

FORMATION	OIL OR GAS	FROM	TO	FORMATION	OIL OR GAS	DEPTH	WHERE OBSERVED (X)					
							Sam- ples	Odor	Pits	Mud Line	Gas Log.	Fill Up
AlCarb	Oil	5880	5910									
Niagaran	Oil	5940	5978	None								

STIMULATION BY ACID OR FRACTURING

WATER FILL UP (F.U.) OR LOST CIRCULATION (L.C.) (X)

DATE	Interval Treated	Materials and amount used	FORMATION	F.U.	L.C.	DEPTH	AMOUNT
2-6-83	5880-5977	3600 gals 28% acid	None				
2-16-83	5880-5977	5000 gals 28% acid					
2-24-83	5966-5977	15,000 gals 28% acid					
2-25-83	5880-5910	2000 gals 28% acid					
4-6-83	6022-6025	1000 gals 20% acid					

4-8-83 **5880-5910** **12,000 gals 20% acid (Frac job)**
5-6-83 **6022-6025** **18,000 gals 20% acid (Frac job)**
MECHANICAL LOGS, LIST EACH TYPE RUN DEPTH CORRECTION DEVIATION SURVEY PLUGGED BACK

Brand	(X)	LOG TYPES	LOGGED INTERVALS	DEPTH	CORRECT'N	RUN AT	DEGREES	YES	NO	DEPTH
Schlumberger	X	LDT/CNL	4000-6060			See attached				
Birdwell		DLL/MLL	4000-6060							

PRODUCTION TEST DATA

OIL - Bbls/day	GRAVITY - °API	COND. Bbls/day	GAS - MCF/day	WATER - Bbls/day	H ₂ S - Grains/100 cu. ft.	B.H.P. AND DEPTH
30	46	0	--	100	Nil	1921 psi 5929

I AM RESPONSIBLE FOR THIS REPORT. THE INFORMATION IS COMPLETE AND CORRECT.

DATE 5-26-83	NAME AND TITLE (PRINT) Linda McConnell	SIGNATURE <i>Linda McConnell</i>
------------------------	--	-------------------------------------

NOTICE REPORT COMPLETE SAMPLE AND FORMATION RECORD AND DRILL STEM TEST INFORMATION ON REVERSE SIDE

R - 7210
Rev. 3/77

FIELD/FACILITY NAME
Wildcat

WELL NAME & NUMBER

Berry et al #2-8A

WELL LOCATION

NE 1/4 of SW 1/4 of NE 1/4 Section 8 T25N R11W

TOWNSHIP

Mayfield

COUNTY

Grand Traverse

TOTAL DEPTH

6064'

FORMATION

Niagaran

PLUGGING/REWORK STARTING DATE

2/3/86

PLUGGING/REWORK COMPLETION DATE

2/6/86

TOTAL DEPTH AFTER REWORK

surf.

MECHANICAL LOGS RUN

WELL COMPLETED FOR

FORMATION AND ZONE

RECORD OF WELL: ☒ PLUGGING ☐ REWORK
(MAIL THREE COPIES TO THE DISTRICT OFFICE WITHIN 30 DAYS AFTER COMPLETION OF PLUGGING OR REWORK)

NAME AND ADDRESS OF WELL OWNER

Great Lakes Niagaran
c/o Louis A. Smith
603 Bay Street
Traverse City, MI 49684

CASING SIZE	WHERE SET	AMOUNT RECOVERED	SHOT OR HIPPLED	TYPE OF BRIDGES OR PLUGS	DEPTH PLACED	SACKS OF CEMENT & ADDITIVE
16"	80	none		cement	30'	15 sx Cl A
113/4"	893	"		"	950'	75 sx Cl A
85/8"	3562	2500	shot	"	1800'	75 sx Cl A
5 1/4"	6064	4380	"	"	2500'	75 sx Cl A
				"	3400	100 sx Cl A

Cement & retnr.

5800' 50/50 sx Cl A

WERE TOOLS, TUBING, CASING, ETC. LOST OR LEFT IN THE HOLE BEFORE OR AFTER PLUGGING? IF YES, GIVE DETAILS.

yes - see above

DID A SERVICE COMPANY PUMP MUD, SPOT CEMENT, OR SET BRIDGE PLUGS? IF YES, GIVE NAME AND ADDRESS.

Yes: Dowell

Kalkaska, MI

WELL PLUGGING/REWORK CONTRACTOR AND ADDRESS

Niagaran Well Services
Traverse City, MI 49684

PERMITEE'S PLUGGING WITNESS

JACK ROCKS

NAME(S) OF DNR REPRESENTATIVE WHO:

Jerry Wendel

☐ ISSUED PERMIT

☒ WITNESSED PLUGGING

WELL CASING RECORD — BEFORE REWORK

Casing		Cement		Perforations		Acid or Fracture Treatment Record	Perforations If plugged, how?
Size	Depth	Sacks	Type	From	To		
16"	80	drvn	n/a				
113/4"	893	n/a	n/a				
85/8"	3362	n/a	n/a				
5 1/2"	6064	n/a	n/a	5880	5977		

WELL CASING RECORD — AFTER REWORK (Indicate additions and changes only)

Casing		Cement		Perforations		Acid or Fracture Treatment Record	Perforations If plugged, how?
Size	Depth	Sacks	Type	From	To		

DESCRIBE IN DETAIL HOW WELL WAS PLUGGED OR REWORKED.

Set 5 1/2" cmt. retnr. at 5800'. Spot 50 sx Cl A cmt. below and 50 sx Cl A on top of retnr. TOOH. Freept. & cut 5 1/2" csg. off at 4380', LD same. TIH w/tubg. to 3400'. Spot 100 sx Cl A cmt. at 3400'. TOOH w/tubg. Freept. and cut 85/8" csg. off at 2500'. LD same. TIH w/tubg. to 1800'. Spot 75 sx Cl A cmt. LD tubg. to 950'. Spot 75 sx cl A at 950'. LD tubg. to 30'. Spot 15 sx Cl A cmt. Cut wellhead off 4' below grd. level and cap w/1/2" steel plate.

ATTACHMENT D
UNDERGROUND SOURCES OF DRINKING WATER

Geology

The Glacial Drift is the only source of groundwater in Grand Traverse County. The Glacial Drift consists of gravel, sand, silt and clay. These unconsolidated deposits ranges in thickness from 100 to 900 feet. Most domestic wells in the County are 50 to 150 feet deep and yield at least 20 GPM. Industrial wells generally deeper than 150 feet are at times capable of producing 250 GPM. The U.S. Geological Survey Investigation Report 90-4122 333 published in 1990 showed fresh water flow in the vicinity of the Weber 4-8 to be towards the Southwest. This same report listed the generalized depth to water-bearing deposits in the area to be 150 to 200 feet.

The base of the drift (top of Coldwater shale) was encountered at 781' G.L. (+324' above Sea Level) in the Weber No. 4-8. The four other penetrations within the 1/4-mile Area of Review encountered the base of the drift between 319' and 343' above sea level

Bedrock Aquifers

Bedrock in the area is the Coldwater shale of Paleozoic age. The shale is described as being light to medium gray in color, firm and slightly calcareous. The Coldwater is about 725 feet thick at the Weber 4-8 wellsite and is underlain with the Antrim shale.

Water Quality

Nineteen samples of groundwater were collected in Mayfield Township, Grand Traverse County in 1985. Analyses by the U.S. Geological Society were as follows:

<u>Specific Conductance</u>			<u>Nitrate</u>			<u>Chloride</u>		
<u>Max.</u>	<u>Mean</u>	<u>Min.</u>	<u>Max.</u>	<u>Mean</u>	<u>Min.</u>	<u>Max.</u>	<u>Mean</u>	<u>Min.</u>
932	516	251	8.8	2.4	0.1	96	15	0.6

Glacial Drift & Water Supply

Figure D-1 shows the 1/4 mile AOR and all water wells found within Section 8, the West Quarter of Section 9, the South Quarter of Section 5 of Township 25 North, Range 11 West of Grand Traverse County Michigan. Information on these water wells is summarized on Table D-1. Water well records are at the end of this Attachment.

Figure D-2 shows the Water-table Configuration in Grand Traverse County, Michigan. Figure D-3 shows the Generalized Depth to Water-bearing Deposits in Grand Traverse County, Michigan.

Water Quality Data, Water-table Configuration and Generalized Depth to water-bearing deposits is from:

"HYDROLOGICAL AND LAND USE IN GRAND TRAVERSE COUNTY, MICHIGAN U.S." Geological Survey, Water-Resources Investigations Report 90-4122. Prepared in cooperation with: Grand Traverse County and the Michigan Department of Natural Resources Geological Survey Division.

Figure D-4 is an Isopac of Drift Thickness in Grand Traverse County, Michigan.

Drift Isopac Map from:

"GRAND TRAVERSE COUNTY DRIFT THICKNESS MAP" by C. Robert Reszka, drawn by Gregory A. Wilson. Department of Natural Resources Geological Survey Division #3772 DT, Posted 1-18-2005.

Figure D-1

Map showing all water wells found within the West quarter of Section 9, South quarter of Section 5 and all of Section 8 of T25N, R11W, Grand Traverse County MI.




TABLE D-1

Water wells within the West quarter of Section 9, South quarter of Section 5 and all of Section 8 of T25N, R11W, Grand Traverse County MI. (Data From - www.deq.state.mi.us/well-logs/)

Section	Owner of Well (As per permit)	Permit No.	Location	SHL QQQ	Date Completed	
5	Joe Harp	-	Miller Rd. 3/4 mi. west of M37	SWSESW	9/7/1973	214
5	Allen Dietter	-	Jct M37 & M113	SESESE	9/16/1971	93
5	Fred Murphy	-	Corner M37 & Miller Rd.	SESESE	8/1/1974	80
5	Wes Herden	-	1/10 mi. NW of Jct M37 & M113	SESESE	10/23/1978	80
5	Schmidt Real Est.	-	Miller Rd. 1/4 mi. west of M37	SWSESE	2/20/1980	105
8	Ken Berry	13545	0.4 mi. S. of M113 on w. side of M37	SESENE	6/9/1986	81
8	Chris M. Bott	17307	Appr. 1 mi. W. of M37 on N. side Harrand Rd.	SWSWSW	8/9/1981	232
8	Steve Endres	19537	5170 West Harrand Rd.	SWSWSW	8/8/1991	181
8	Ronald W. Spitzer	19876	1/4 mi. W. of M37 On Harrand Rd.	E1/2SWSE	9/13/1991	244
8	Stanwolf		1/4 mi. W. of M37 On Harrand Rd.	SWSESE	9/15/1978	122
8	Tolas Oil & Gas Co.	44604	Lease Miller 1-8	NWNENW	11/5/1991	229
8	Gerald Glazier		1/2 mi. of Bott rd. on Miller Rd.	NWNW	10/16/1978	190
8	Dean Bott	14609	Off Harrand Rd. on W. side of Bott Rd	NESESW	7/16/1987	
8	Jack Zimmerman		3/4 mi. W. of M37 On Harrand Rd.	SESWSW	8/4/1987	109
8	Greg Bott		3/4 mi. on Bott Rd S. from Miller Rd.	NESW	8/3/1978	107
9	Gerald Glazier		150' E. of M37 & 300' N. of Harrand Rd	SWSWSW	4/23/1970	129
9	Richard Seltz	12052	Bet. M113 & Harrand Rd. on E. side M37	SWNWSW	3/11/1985	153
9	Jack Zimmerman		0.2 mi. E. of M37 on S. side M113	NENWNW	3/6/1984	70


← This is a typo
Should be 122' based on Water well record

Figure D-2

DEPARTMENT OF THE INTERIOR
U.S. GEOLOGICAL SURVEY

Prepared in cooperation with
GRAND TRAVERSE COUNTY and the
MICHIGAN DEPARTMENT OF NATURAL RESOURCES

WATER-RESOURCES INVESTIGATIONS REPORT 90-4122
Plate 2




Water-table configuration in Grand Traverse County, Michigan.

Figure D-3

Prepared in cooperation with
GRAND TRAVERSE COUNTY and the
MICHIGAN DEPARTMENT OF NATURAL RESOURCES


DEPARTMENT OF THE INTERIOR
U.S. GEOLOGICAL SURVEY

WATER-RESOURCES INVESTIGATIONS REPORT 90-4122
Plate 3



Generalized depth to water-bearing deposits in Grand Traverse County, Michigan.

Figure D-4




NOV 01 1973

WATER WELL RECORD


ACT 294 PA 1965

MICHIGAN DEPARTMENT
OF
PUBLIC HEALTH

1 LOCATION OF WELL		Fraction	Section Number	Town Number	Range Number
County <u>Grand Traverse</u>	Township Name <u>Mary Field</u>	<u>SW 1/4 SE 1/4 SW 1/4</u>	<u>5</u>	<u>25 N 1/2</u>	<u>11 W</u>
Distance And Direction from Road Intersections <u>3/4 Mi. W. of M-37 on Miller Rd</u>		3 OWNER OF WELL: <u>Joe + Gerald Harp</u>			
Street address & City of Well Location <u>Kingsey, Mich</u>		Address <u>Kingsey, Mich</u>			
Locate with "X" in section below 		4 WELL DEPTH: (completed) Date of Completion <u>214</u> ft. <u>Sept 7, 1973</u>			
		5 <input checked="" type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jettied <input type="checkbox"/> Bored <input type="checkbox"/> _____			
		6 USE: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public Supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air Conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test Well <input type="checkbox"/> _____			
		7 CASING: Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Height: Above/Below Diam. _____ Surface _____ ft. Weight _____ lbs./ft. Drive Shoe? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>			
		4 in. to <u>210</u> ft. Depth _____ in. to _____ ft. Depth			
2 FORMATION		THICKNESS OF STRATUM	DEPTH TO BOTTOM OF STRATUM	8 SCREEN:	
<u>Clay</u>		<u>7</u>	<u>7</u>	Type: <u>Stainless</u> Dia.: <u>3"</u>	
<u>Sand</u>		<u>40</u>	<u>47</u>	Slot/Gauze <u>7</u> Length <u>48"</u>	
<u>Clay</u>		<u>20</u>	<u>67</u>	Set between <u>210</u> ft. and <u>214</u> ft.	
<u>Sand Fine</u>		<u>30</u>	<u>147</u>	Fittings: <u>K Parker + 2' EXT.</u>	
<u>Fine Sand + water</u>		<u>40</u>	<u>187</u>	9 STATIC WATER LEVEL _____ ft. below land surface	
<u>Clay</u>		<u>20</u>	<u>207</u>	10 PUMPING LEVEL below land surface <u>170</u> ft. after <u>3</u> hrs. pumping <u>12</u> g.p.m.	
<u>Coarse Sand + water</u>				_____ ft. after _____ hrs. pumping _____ g.p.m.	
				11 WATER QUALITY in Parts Per Million: Iron (Fe) _____ Chlorides (Cl) _____ Hardness _____ Other _____	
				12 WELL HEAD COMPLETION: <input type="checkbox"/> In Approved Pit <input checked="" type="checkbox"/> Pitless Adapter <input type="checkbox"/> 12" Above Grade	
				13 Well Grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Neat Cement <input type="checkbox"/> Bentonite <input type="checkbox"/> _____ Depth: From <u>5</u> ft. to <u>80</u> ft.	
				14 Nearest Source of possible contamination <u>80</u> feet <u>W</u> Direction <u>Septic Tank</u> Type _____ Well disinfected upon completion <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
				15 PUMP: <input type="checkbox"/> Not installed Manufacturer's Name <u>Gould</u> Model Number <u>5 11 STAGE</u> Volts <u>115</u> Length of Drop Pipe <u>185</u> ft. capacity <u>7</u> G.P.M. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating	
16 Remarks, elevation, source of data, etc. <u>NOOD INFO BY DRILLER ITEM NO. 16</u> <u>CORRECTED</u> <u>CCADITION</u>		17 WATER WELL CONTRACTOR'S CERTIFICATION: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Benson Welding, Inc.</u> 0778 REGISTERED BUSINESS NAME REGISTRATION NO. <u>Mesick, Mich.</u> Address <u>Douglas Benson</u> Date <u>Sept 10, 1973</u> Signed AUTHORIZED REPRESENTATIVE			

MAR 23 1972

WATER WELL RECORD
ACT 294 PA 1965MICHIGAN DEPARTMENT
OF
PUBLIC HEALTH

1 LOCATION OF WELL		3 OWNER OF WELL:					
County GRAND TRAVERSE	Township Name MAYFIELD	Fraction SE 1/4 SE 1/4	Section Number 5	Town Number 25 N.B.	Range Number 11 W.		
Distance And Direction from Road Intersections Jct. of M-37 - M113		Address ALLEN DIETTER					
Street address & City of Well Location Locate with "X" in section below		4 WELL DEPTH: (completed) Date of Completion 92 ft. 9-16-71					
<div style="text-align: center;">Sketch Map: </div>		5 <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input checked="" type="checkbox"/> Bored <input type="checkbox"/>					
		6 USE: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public Supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air Conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test Well <input type="checkbox"/>					
2 FORMATION		THICKNESS OF STRATUM		DEPTH TO BOTTOM OF STRATUM		7 CASING: Threaded <input checked="" type="checkbox"/> Welded <input type="checkbox"/> Height: Above/Below Surface 2 ft. to 87 ft. Depth 92 ft. Weight 3.75 lbs./ft. Drive Shoe? Yes <input type="checkbox"/> No <input type="checkbox"/>	
CLAY		10		10		8 SCREEN: Type: BRASS Dia.: 1 1/4" Star Gauge 60 Length 5' Set between 87 ft. and 92 ft. Fittings:	
GRAVEL		30		40			
CLAY		10		50			
SAND		25		75		9 STATIC WATER LEVEL 74 ft. below land surface	
WATER SAND		17		92		10 PUMPING LEVEL below land surface _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m.	
						11 WATER QUALITY in Parts Per Million: Iron (Fe) _____ Chlorides (Cl) _____ Hardness _____ Other _____	
						12 WELL HEAD COMPLETION: <input type="checkbox"/> In Approved Pit <input type="checkbox"/> Pitless Adapter <input type="checkbox"/> 12" Above Grade	
						13 Well Grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Neat Cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Depth: From _____ ft. to _____ ft.	
						14 Nearest Source of possible contamination _____ feet _____ Direction _____ Type _____ Well disinfected upon completion <input type="checkbox"/> Yes <input type="checkbox"/> No	
						15 PUMP: <input type="checkbox"/> Not Installed Manufacturer's Name RAPIDAYTON Model Number 20 Edge HP 1 Volts 230 Length of Drop Pipe 78 ft. capacity _____ G.P.M. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Jet <input type="checkbox"/> Reciprocating	
16 Remarks, elevation, source of data, etc. CORRECTED BY: REVISION BY:		17 WATER WELL CONTRACTOR'S CERTIFICATION: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. PHIL'S WELL DRILLING 0481 REGISTERED BUSINESS NAME REGISTRATION NO. Address 10785 Grandview Rd T.C. Signed Phil Shamowski Date 10-21-71 AUTHORIZED REPRESENTATIVE					

WATER WELL RECORD

ACT 294 PA 1985

MICHIGAN DEPARTMENT
OF
PUBLIC HEALTH

1 LOCATION OF WELL

County

Township Name

Fraction

Section Number

Town Number


Range Number

Grand Traverse May Field
 Corner M-37 & Miller Rd. Kingsley
 Mich.

Street address & City of Well Location

Locate with "X" in section below

Sketch Map:



3 OWNER OF WELL:

Address

Fred Murphy
 Kingsley, Michigan

4 WELL DEPTH: (completed) Date of Completion

80 ft. 8-1-74

5 ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug
☐ Hollow rod ☐ Jotted ☒ Bored ☐

6 USE: ☒ Domestic ☐ Public Supply ☐ Industry
☐ Irrigation ☐ Air Conditioning ☐ Commercial
☐ Test Well ☐

7 CASING: Threaded ☐ Welded ☐ Diam.

Height: Above/Below

4 in. to 75 ft. Depth Surface 1 ft.
 Weight 1.00 lbs./ft.

Drive Shoe? Yes ☐ No ☒

8 SCREEN:

Type: DRIVE Dia.: 4"

Slot/Gauge 12 Length 5'

Set between 75 ft. and 80 ft.

Fittings: LEAD COLLAR

9 STATIC WATER LEVEL

60 ft. below land surface

10 PUMPING LEVEL below land surface

ft. after hrs. pumping g.p.m.

ft. after hrs. pumping g.p.m.

11 WATER QUALITY in Parts Per Million:

Iron (Fe) Chlorides (Cl)

Hardness Other

12 WELL HEAD COMPLETION: ☐ In Approved Pit☐ Pitless Adapter ☒ 12" Above Grade13 Well Grouted? ☐ Yes ☒ No☐ Neat Cement ☐ Bentonite ☐

Depth: From ft. to ft.

14 Nearest Source of possible contamination

60 feet SW Direction septic Type

Well disinfected upon completion ☒ Yes ☐ No

15 PUMP:

☒ Not installed

Manufacturer's Name

Model Number HP Volts

Length of Drop Pipe ft. capacity G.P.M.

Type: ☐ Submersible☐ Jet ☐ Reciprocating

USE A 2ND SHEET IF NEEDED

16 Remarks, elevation, source of data, etc.

ADDED INFO BY DRILLER, ITEM NO.

CORRECTED BY

ELEVATION BY

ELEVATION

DEPTH TO ROCK

17 WATER WELL CONTRACTOR'S CERTIFICATION:

This well was drilled under my jurisdiction and this report is true
 to the best of my knowledge and belief.

CLIFF WELL DRILL CO.

REGISTERED BUSINESS NAME

REGISTRATION NO.

Address 6410 CENTER RD TRAVERSE CITY, MICH.

Signed Frank W. Dymally

AUTHORIZED REPRESENTATIVE



Date 8-5-74

JAN 16 1979

WATER WELL RECORD

ACT 294 PA 1965

MICHIGAN DEPARTMENT
OF
PUBLIC HEALTH

1 LOCATION OF WELL		TOWNSHIP NAME		Fraction	Section Number	Town Number	Range Number
County <u>Grand Traverse</u>		<u>Mayfield</u>		<u>N 1/2 E 1/4 SE 1/4</u>	<u>5</u>	<u>T 25 N 1/2</u>	<u>R 11 E 1/2</u>
Distance And Direction from Road Intersection <u>1/2 MILE N.W. 1/4 INTERSECTION</u> <u>11-37 + 113</u>							
Street address & City of Well Location Locate with "X" in section below				Sketch Map:			
							
2 FORMATION		THICKNESS OF STRATUM	DEPTH TO BOTTOM OF STRATUM	3 OWNER OF WELL:			
<u>Clay</u>		<u>20</u>	<u>20</u>	Address <u>4072 N-37 S</u> <u>Kingsley Mich.</u>			
<u>Sand clay</u>		<u>36</u>	<u>56</u>	4 WELL DEPTH: (completed) <u>80</u> ft. Date of Completion <u>10-23-78</u>			
<u>Water sand</u>		<u>24</u>	<u>80</u>	5 <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dig <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jatted <input checked="" type="checkbox"/> Bored <input type="checkbox"/>			
				6 USE: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public Supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air Conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test Well <input type="checkbox"/>			
				7 CASING: Threaded <input checked="" type="checkbox"/> Welded <input type="checkbox"/> Height: Above/Below Surface <u>11</u> ft. Diam. <u>4</u> in. to <u>76</u> ft. Depth <u>11</u> lbs./ft. Weight <u>11</u> lbs./ft. Drive Shoe? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>			
				8 SCREEN:			
				Type: <u>UESCO</u> Dia.: <u>4</u> Slot <u>10</u> Length <u>4</u> Set between <u>76</u> ft. and <u>80</u> ft. Fittings: <u>Coupler</u>			
				9 STATIC WATER LEVEL <u>56</u> ft. below land surface			
				10 PUMPING LEVEL below land surface <u>70</u> ft. after <u>1</u> hrs. pumping <u>12</u> a.p.m. _____ ft. after _____ hrs. pumping _____ a.p.m.			
				11 WATER QUALITY in Parts Per Million: Iron (Fe) _____ Chlorides (Cl) _____ Hardness _____ Other _____			
				12 WELL HEAD COMPLETION: <input type="checkbox"/> In Approved Pit <input checked="" type="checkbox"/> Pitless Adapter <input type="checkbox"/> 12" Above Grade			
				13 Well Grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Neat Cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Grout Depth: From <u>10</u> ft. to <u>56</u> ft.			
				14 Nearest Source of possible contamination <u>75</u> feet <u>N</u> Direction <u>SEPTIC</u> Type Well disinfected upon completion <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No			
				15 PUMP: <input type="checkbox"/> Not installed Manufacturer's Name <u>FLINT & MULLING</u> Model Number <u>53A8</u> HP <u>2</u> Volts <u>230</u> Length of Drop Pipe <u>65</u> ft. capacity <u>12</u> G.P.M. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating			
16 Remarks, elevation, source of data, etc. ADDED INFO BY DRILLER, ITEM NO. *CORRECTED BY *ADDITION BY ELEVATION DEPTH TO ROCK				17 WATER WELL CONTRACTOR'S CERTIFICATION: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Robert J. Sullivan</u> C. 1244 REGISTERED BUSINESS NAME REGISTRATION NO. Address <u>6410 Corp. Eastman Rd. Mil.</u> Signed <u>Robert J. Sullivan</u> Date <u>10-23-78</u> AUTHORIZED REPRESENTATIVE			

APR 30 1980

WATER WELL RECORD

ACT 284 PA 1966

MICHIGAN DEPARTMENT
OF
PUBLIC HEALTH

1 LOCATION OF WELL

County GRAND TRAVERSE	Township Name MAYFIELD	Fraction SW 1/4 SE 1/4	Section Number #5	Town Number 25 N.W.	Range Number 11 E.W.
---------------------------------	----------------------------------	----------------------------------	-----------------------------	-------------------------------	--------------------------------


Distance And Direction from Road Intersections

MILLER RD 1/4 mi. W of RT #37
MAYFIELD, MI 49666

Street address & City of Well Location

Locate with "X" in section below

Sketch Map:



2 FORMATION	THICKNESS OF STRATUM	DEPTH TO BOTTOM OF STRATUM	3 OWNER OF WELL:
CLAY & GRAVEL	2	2	Address: SCHMIDT REAL ESTATE 402 E. FRONT ST. TRAVERSE CITY, MI 49664
CLAY	13	15	
SAND & GRAVEL	59	74	
Sand	31	105	
			4 WELL DEPTH: (completed) 105 ft. Date of Completion 2-22-80
			5 <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dig <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored
			6 USE: <input type="checkbox"/> Domestic <input type="checkbox"/> Public Supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air Conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test Well
			7 CASING: Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Height: Above/Below Surface 200 ft. Diam. 5" PVC 100' in. to 100' ft. Depth Weight 200 lbs./ft. Drive Shoe? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
			8 SCREEN: Type: STAINLESS Dia.: 2 INCH Slot/Screen 10 Length 5 FEET Set between 100 ft. and 105 ft. Fittings: K-PACKER - PLUG BOTTOM
			9 STATIC WATER LEVEL 87 ft. below land surface
			10 PUMPING LEVEL below land surface 87 ft. after 1 hrs. pumping 87 ft. after 1 hrs. pumping
			11 WATER QUALITY in Parts Per Million: Iron (Fe) _____ Chlorides (Cl) _____ Hardness _____ Other _____
			12 WELL HEAD COMPLETION: <input type="checkbox"/> In Approved Pit <input checked="" type="checkbox"/> Pitless Adaptor <input type="checkbox"/> 12" Above Grade
			13 Well Grouted? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Neat Cement <input type="checkbox"/> Bentonite <input type="checkbox"/> _____ Depth: From _____ ft. to _____ ft.
			14 Nearest Source of possible contamination: 50 foot NE Direction SEPTIC Type Well disinfected upon completion <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
			15 PUMP: <input type="checkbox"/> Not installed Manufacturer's Name AER MOTOR Model Number SDX-50 HP 1/2 Volts 230 Length of Drop Pipe 85 ft. capacity 8 G.P.M. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating

USE A 2ND SHEET IF NEEDED

16 Remarks, elevation, source of data, etc.

ADDED INFO BY DRILLER, ITEM NO.

*CORRECTED BY

**ADDITION BY

ELEVATION

DEPTH TO ROCK

17 WATER WELL CONTRACTOR'S CERTIFICATION:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

REGISTERED BUSINESS NAME

REGISTRATION NO.

Address

Signed

AUTHORIZED REPRESENTATIVE

Date

GEOLOGICAL SURVEY NO.

MICHIGAN DEPARTMENT OF PUBLIC HEALTH

WATER WELL AND PUMP RECORD

 1 3 5 4 5
 PERMIT NUMBER

1 LOCATION OF WELL County <u>GRAND TRAVERSE</u> Township Name <u>MAYFIELD</u> Fraction <u>SE 1/4</u> <u>NE 1/4</u> Section Number <u>8</u> Town Number <u>7.25</u> N/S <u>N/S</u> Range Number <u>R. 11</u> E/W <u>E/W</u>																
Distance And Direction From Road Intersection <u>1/4 MILE SOUTH OF M-113 ON M-37, WEST SIDE OF ROAD.</u> Street Address & City of Well Location <u>7390 M-37 South</u> Locate with "X" in Section Below <div style="border: 1px solid black; padding: 5px; margin: 5px;"> </div>																
2 FORMATION DESCRIPTION <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 40%;">FORMATION DESCRIPTION</th> <th style="width: 10%;">THICKNESS OF STRATUM</th> <th style="width: 10%;">DEPTH TO BOTTOM OF STRATUM</th> </tr> </thead> <tbody> <tr> <td>SAND</td> <td>20</td> <td>20</td> </tr> <tr> <td>GRAVEL</td> <td>40</td> <td>60</td> </tr> <tr> <td>CLAY</td> <td>1</td> <td>61</td> </tr> <tr> <td>WATER SAND</td> <td>20</td> <td>81</td> </tr> </tbody> </table>	FORMATION DESCRIPTION	THICKNESS OF STRATUM	DEPTH TO BOTTOM OF STRATUM	SAND	20	20	GRAVEL	40	60	CLAY	1	61	WATER SAND	20	81	3 OWNER OF WELL: <u>KEN BERRY</u> Address <u>7390 M-37 South</u> Address Same As Well Location? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No 4 WELL DEPTH: (completed) <u>81</u> ft. Date of Completion <u>6-9-86</u> 5 <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Auger <input type="checkbox"/> Jolted <input type="checkbox"/> 6 USE: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Type I Public <input type="checkbox"/> Type III Public <input type="checkbox"/> Irrigation <input type="checkbox"/> Type IIa Public <input type="checkbox"/> Heat pump <input type="checkbox"/> Test Well <input type="checkbox"/> Type IIb Public <input type="checkbox"/> 7 CASING: <input type="checkbox"/> Steel <input type="checkbox"/> Threaded <input type="checkbox"/> Height: Above/Below <input checked="" type="checkbox"/> Plastic <input checked="" type="checkbox"/> Welded Surface <u>1</u> ft. <u>5</u> in. to <u>76</u> ft. depth Weight <u>3</u> lbs./ft. <u>5</u> in. to <u>76</u> ft. depth Grouted Drill Hole Diameter <u>6 3/4</u> in. to <u>81</u> ft. depth Drive Shoe <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No 8 SCREEN: <input type="checkbox"/> Not installed Type <u>PVC</u> Diameter <u>4 INCH</u> Slot/Screen <u>10</u> Length <u>5 FEET</u> Set between <u>76</u> ft. and <u>81</u> ft. FITTINGS: <input checked="" type="checkbox"/> K-Packer <input type="checkbox"/> Lead Packer <input type="checkbox"/> Gramer Check <input checked="" type="checkbox"/> Blank above screen <u> </u> ft. Other <u> </u> 9 STATIC WATER LEVEL: <u>35</u> ft. below land surface <input type="checkbox"/> Flow 10 PUMPING LEVEL: below land surface <u> </u> ft. after <u> </u> hrs. pumping at <u> </u> G.P.M. <u> </u> ft. after <u> </u> hrs. pumping at <u> </u> G.P.M. 11 WELL HEAD COMPLETION: <input checked="" type="checkbox"/> Well adapter <input type="checkbox"/> 12" above grade <input type="checkbox"/> Basement offset <input type="checkbox"/> Approved pit 12 WELL GROUTED? <input type="checkbox"/> No <input checked="" type="checkbox"/> Yes From <u> </u> to <u> </u> ft. <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Other <u>SAND</u> No. of bags of cement <u> </u> Additives <u> </u> 13 Nearest source of possible contamination Type <u>SEPTIC</u> Distance <u>50</u> ft. Direction <u> </u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No 14 PUMP: <input type="checkbox"/> Not installed <input type="checkbox"/> Pump Installation Only Manufacturer's name <u>RED JACKET</u> Model number <u>2W</u> HP <u>1/2</u> Volts <u>230</u> Length of Drop Pipe <u>60</u> ft. capacity <u>10</u> G.P.M. TYPE: <input checked="" type="checkbox"/> Submersible <u>1" PVC</u> PRESSURE TANK: <u>X-TROL</u> Manufacturer's name <u> </u> Model number <u>WX202</u> Capacity <u>40</u> Gallons
FORMATION DESCRIPTION	THICKNESS OF STRATUM	DEPTH TO BOTTOM OF STRATUM														
SAND	20	20														
GRAVEL	40	60														
CLAY	1	61														
WATER SAND	20	81														
15. Remarks, elevation, source <u>RECEIVED</u> Mich. Dept. of Public Health SEP 22 1986 Bureau of Environmental and Occupational Health - GWOS																
16. WATER WELL CONTRACTOR'S CERTIFICATION: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>PHILS WELL DRILLING 0481</u> REGISTERED BUSINESS NAME <u>10785 GRANDVIEW RD</u> REGISTRATION NO. <u>T. E</u> Address <u>Phil Sharnowski</u> Date <u>6-13-86</u> Signed <u> </u> AUTHORIZED REPRESENTATIVE <u> </u> Authority: <u> </u> Completion: <u> </u> Penalty: <u> </u> Act 368 PA 1978 Required Conviction of a violation of any provision is a misdemeanor.																

D67d 2/84


GEOLOGICAL SURVEY COPY

GEOLOGICAL SURVEY NO.

MICHIGAN DEPARTMENT OF PUBLIC HEALTH

WATER WELL AND PUMP RECORD

 1 7 3 0 7
 PERMIT NUMBER

1 LOCATION OF WELL County <u>GRAND TRAVERSE</u> Township Name <u>MAYFIELD</u> Fraction <u>SW 1/4 SW 1/4 SW 1/4</u> Section Number <u>8</u> Town Number <u>T. 25 N.</u> Range Number <u>R. 11 W.</u> Distance And Direction From Road Intersection <u>APPROXIMATELY 1 MILE WEST OF M-37 ON</u> <u>NARRAND ROAD NORTH SIDE OF ROAD</u> Street Address & City of Well Location <u>NARRAND ROAD</u> Locate with "X" in Section Below 		3 OWNER OF WELL: <u>CHRIS M. Bott</u> Address <u>336 N.E. SILVER LAKE RD.</u> Address Same As Well Location? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No																									
2 FORMATION DESCRIPTION <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 40%;">FORMATION DESCRIPTION</th> <th style="width: 20%;">THICKNESS OF STRATUM</th> <th style="width: 40%;">DEPTH TO BOTTOM OF STRATUM</th> </tr> </thead> <tbody> <tr> <td><u>SAND & STONES</u></td> <td><u>0-60</u></td> <td></td> </tr> <tr> <td><u>GRAVEL</u></td> <td><u>60-85</u></td> <td></td> </tr> <tr> <td><u>SAND & GRAVEL</u></td> <td><u>85-102</u></td> <td></td> </tr> <tr> <td><u>SAND & CLAY</u></td> <td><u>102-128</u></td> <td></td> </tr> <tr> <td><u>CLAY & SILT</u></td> <td><u>128-210</u></td> <td></td> </tr> <tr> <td><u>CLAY</u></td> <td><u>210-222</u></td> <td></td> </tr> <tr> <td><u>SAND</u></td> <td><u>222-232</u></td> <td></td> </tr> </tbody> </table>		FORMATION DESCRIPTION	THICKNESS OF STRATUM	DEPTH TO BOTTOM OF STRATUM	<u>SAND & STONES</u>	<u>0-60</u>		<u>GRAVEL</u>	<u>60-85</u>		<u>SAND & GRAVEL</u>	<u>85-102</u>		<u>SAND & CLAY</u>	<u>102-128</u>		<u>CLAY & SILT</u>	<u>128-210</u>		<u>CLAY</u>	<u>210-222</u>		<u>SAND</u>	<u>222-232</u>		4 WELL DEPTH: <u>232</u> ft. Date Completed <u>8/9/89</u> <input checked="" type="checkbox"/> New Well <input type="checkbox"/> Replacement Well 5 <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Auger <input type="checkbox"/> Jetted 6 USE: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Type I Public <input type="checkbox"/> Type II Public <input type="checkbox"/> Irrigation <input type="checkbox"/> Type Ia Public <input type="checkbox"/> Heat pump <input type="checkbox"/> Test Well <input type="checkbox"/> Type Iib Public 7 CASING: <input type="checkbox"/> Steel <input type="checkbox"/> Threaded <input type="checkbox"/> Welded <u>5"</u> <input checked="" type="checkbox"/> Plastic <input type="checkbox"/> Diameter <u>5"</u> in. to <u>232</u> ft. depth <u>232</u> in. to <u>232</u> ft. depth <u>232</u> in. to <u>232</u> ft. depth Height: Above/Below Surface <u>5DR-31</u> ft. Weight <u>5DR-31</u> lbs./ft. Drive Shoe <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
FORMATION DESCRIPTION	THICKNESS OF STRATUM	DEPTH TO BOTTOM OF STRATUM																									
<u>SAND & STONES</u>	<u>0-60</u>																										
<u>GRAVEL</u>	<u>60-85</u>																										
<u>SAND & GRAVEL</u>	<u>85-102</u>																										
<u>SAND & CLAY</u>	<u>102-128</u>																										
<u>CLAY & SILT</u>	<u>128-210</u>																										
<u>CLAY</u>	<u>210-222</u>																										
<u>SAND</u>	<u>222-232</u>																										
Dig 41066		8 SCREEN: <input type="checkbox"/> Not Installed Type <u>PVC</u> Diameter <u>4"</u> Slot/Gauge <u>10</u> Length <u>5 FT.</u> Set between <u>227</u> ft. and <u>232</u> ft. FITTINGS: <input checked="" type="checkbox"/> K-Packer <input type="checkbox"/> Lead Packer <input type="checkbox"/> Bramer Check <input type="checkbox"/> Blank above screen <u> </u> ft. Other <u> </u> 9 STATIC WATER LEVEL: <u>130</u> ft. below land surface <input type="checkbox"/> Flow 10 PUMPING LEVEL: below land surface <u> </u> ft. after <u> </u> hrs. pumping at <u> </u> G.P.M. <u> </u> ft. after <u> </u> hrs. pumping at <u> </u> G.P.M.																									
USE A 2ND SHEET IF NEEDED		11 WELL HEAD COMPLETION: <input checked="" type="checkbox"/> Pitless adapter <input type="checkbox"/> 12" above grade <input type="checkbox"/> Basement offset <input type="checkbox"/> Approved pit 12 WELL GROUTED? <input type="checkbox"/> No <input checked="" type="checkbox"/> Yes From <u> </u> to <u> </u> ft. <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Other <u>Welding</u> No. of bags of cement <u> </u> Additives <u> </u> 13 Nearest source of possible contamination Type <u>SEPTIC</u> Distance <u>50</u> ft. Direction <u> </u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Was old well plugged? <input type="checkbox"/> Yes <input type="checkbox"/> No																									
15. Remarks, elevation, source of data, etc. 		14 PUMP: <input type="checkbox"/> Not installed <input type="checkbox"/> Pump installation Only Manufacturer's name <u>Red Jacket</u> Model number <u>2-W</u> HP <u>3/4</u> Volts <u>230</u> Length of Drop Pipe <u>215</u> ft. capacity <u>10</u> G.P.M. TYPE: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Jet PRESSURE TANK: Manufacturer's name <u>Well Ex 101</u> Model number <u>WX 203</u> Capacity <u>80</u> Gallons																									
17. Dig Operator's Name <u>Bob Nelson</u>		16. WATER WELL CONTRACTOR'S CERTIFICATION: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Phil's Well Drilling 0481</u> REGISTERED BUSINESS NAME <u>19785 Grand View Rd. T.C.</u> Address <u>Phil's Well Drilling</u> Signed <u>Phil's Well Drilling</u> Date <u>8/10/89</u> AUTHORIZED REPRESENTATIVE																									

087d 12/85

 Authority: Act 388 PA 1878
 Completion: Required
 Penalty: Conviction of a violation of any provision is a misdemeanor.

GEOLOGICAL SURVEY COPY

GEOLOGICAL SURVEY NO.

MICHIGAN DEPARTMENT OF PUBLIC HEALTH
WATER WELL AND PUMP RECORD

PERMIT NUMBER

1 LOCATION OF WELL County: Grand Traverse		Township Name: Mayfield		Fraction: SW 1/4 SW 1/4 SW 1/4		Section Number: 8		Town Number: 25 N 13		Range Number: 11 EW	
Distance And Direction From Road Intersection 5170 West Howard Rd.											
Street Address & City of Well Location Locate with "X" in Section Below						3 OWNER OF WELL: Steve Endres Address: 5170 West Howard Rd. Buckley, Mich Address Same As Well Location? <input type="checkbox"/> Yes <input type="checkbox"/> No					
						4 WELL DEPTH: 101 FT. Date Completed: 8-8-91 <input checked="" type="checkbox"/> New Well <input type="checkbox"/> Replacement Well					
						5 <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Auger <input type="checkbox"/> Hollow rod <input type="checkbox"/> Auger <input type="checkbox"/> Jetted <input type="checkbox"/>					
6 USE: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Type I Public <input type="checkbox"/> Type III Public <input type="checkbox"/> Irrigation <input type="checkbox"/> Type IIa Public <input type="checkbox"/> Heat pump <input type="checkbox"/> Test Well <input type="checkbox"/> Type IIb Public <input type="checkbox"/>						7 CASING: <input type="checkbox"/> Steel <input type="checkbox"/> Threaded <input type="checkbox"/> Plastic <input checked="" type="checkbox"/> Welded Height: Above/Below Surface: SPK-21 Weight: _____ lbs./ft. Drive Shoe: <input type="checkbox"/> Yes <input type="checkbox"/> No					
2 FORMATION DESCRIPTION						THICKNESS OF STRATUM		DEPTH TO BOTTOM OF STRATUM			
Sand Gravel & Rocks						0-63					
Clay & Sand						63-105					
Sand & Gravel & silt						105-112					
Silt & Clay						112-176					
Sand						176-181					
<div style="text-align: center;"> RECEIVED DEC 31 1991 GRAND TRAVERSE COUNTY HEALTH DEPARTMENT </div>						8 SCREEN: <input type="checkbox"/> Not Installed Type: Wellscreen Diameter: 4" Cloth/Gauge: 10 Length: 5 FT. Set between: 176 ft. and 181 ft. FITTINGS: <input checked="" type="checkbox"/> K-Packer <input type="checkbox"/> Lead Packer <input type="checkbox"/> Bromer Check <input checked="" type="checkbox"/> Blank above screen 2 ft. Other: _____					
						9 STATIC WATER LEVEL: 160 ft. below land surface <input type="checkbox"/> Flow					
						10 PUMPING LEVEL: below land surface _____ ft. after _____ hrs. pumping at _____ G.P.M. _____ ft. after _____ hrs. pumping at _____ G.P.M.					
						11 WELL HEAD COMPLETION: <input checked="" type="checkbox"/> Pitless adaptor <input type="checkbox"/> 12" above grade <input type="checkbox"/> Basement offset <input type="checkbox"/> Approved pit					
						12 WELL GROUTED? <input type="checkbox"/> No <input checked="" type="checkbox"/> Yes From 0 to 25 ft. <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Other: Volckay No. of bags of cement: _____ Additives: _____					
<div style="text-align: center;"> RECEIVED MICH. DEPT. OF PUBLIC HEALTH JAN 10 1992 </div>						13 Nearest source of possible contamination Type: septic Distance: 50 ft. Direction: _____ Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Was old well plugged? <input type="checkbox"/> Yes <input type="checkbox"/> No					
						14 PUMP: <input type="checkbox"/> Not installed <input type="checkbox"/> Pump installation Only Manufacturer's name: Red Jacket Model number: 2-W HP: 3/4 Volts: 230 Length of Drop Pipe: 170 ft. capacity: 10 G.P.M. TYPE: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Jet PRESSURE TANK: Welltex Manufacturer's name: Welltex Model number: WX 203 Capacity: 10 G.P.M.					
16. Remarks, elevation, source of data, etc.						BUREAU OF ENVIRONMENTAL AND OCCUPATIONAL HEALTH WELL CONTRACTOR'S CERTIFICATION: I have drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Phil's Well Drilling 04801 REGISTERED BUSINESS NAME: _____ REGISTRATION NO.: _____ Address: 3303 Kenzie School Rd. Signed: Paul F. Ring Date: 8/19/91 AUTHORIZED REPRESENTATIVE					
17. Rig Operator's Name: Doug Schetter											

D67d 2/89

GEOLOGICAL SURVEY COPY

Act 368 PA 1978
Required
Conviction of a violation
of any provision is a
misdemeanor.


087d 2/89

Authority:	Act 368 PA 1978
Completion:	Required
Penalty:	Conviction of a violation of any provision is a misdemeanor.

GEOLOGICAL SURVEY SAMPLE NO.

JAN 16 1979

WATER WELL RECORD
ACT 294 PA 1965MICHIGAN DEPARTMENT
OF
PUBLIC HEALTH

1 LOCATION OF WELL		TOWNSHIP NAME		FRACTION		SECTION NUMBER		TOWN NUMBER		RANGE NUMBER	
County <u>Grand T.C.</u>		<u>MAYFIELD</u>		<u>6W 4E 5E 1/4</u>		<u>8</u>		<u>25</u> N.E.		<u>R 11 E W.</u>	
Distance And Direction from Road Intersections <u>1/4 mile west of M37 on Harward Rd</u>						3 OWNER OF WELL: <u>STAN Wolf</u> Address _____					
Street address & City of Well Location Locate with "X" in section below						4 WELL DEPTH: (completed) Date of Completion <u>122</u> ft. <u>7-15-78</u>					
						5 <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input checked="" type="checkbox"/> Bored <input type="checkbox"/>					
						6 USE: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public Supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air Conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test Well <input type="checkbox"/>					
2 FORMATION						7 CASING: Threaded <input checked="" type="checkbox"/> Welded <input type="checkbox"/> Diam. _____ Height: Above/Below Surface <u>1</u> ft. Weight _____ lbs./ft. Drive Shoe? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>					
						8 SCREEN: Type: <u>stainless</u> Dia.: <u>4"</u> Slot <u>10</u> Length <u>4'</u> Set between <u>118</u> ft. and <u>122</u> ft. Fittings: _____					
THICKNESS OF STRATUM						9 STATIC WATER LEVEL <u>100</u> ft. below land surface					
DEPTH TO BOTTOM OF STRATUM						10 PUMPING LEVEL below land surface <u>105</u> ft. after <u>1</u> hrs. pumping <u>20</u> g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m.					
Dry sand & clay						11 WATER QUALITY in Parts Per Million: Iron (Fe) _____ Chlorides (Cl) _____ Hardness _____ Other _____					
water sand						12 WELL HEAD COMPLETION: <input type="checkbox"/> In Approved Pit <input checked="" type="checkbox"/> Pitless Adapter <input type="checkbox"/> 12" Above Grade					
						13 Well Grouted? <input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Neat Cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Depth: From _____ ft. to _____ ft.					
						14 Nearest Source of possible contamination <u>60</u> feet <u>N</u> Direction _____ Type _____ Well disinfected upon completion <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No					
						15 PUMP: <input type="checkbox"/> Not installed Manufacturer's Name <u>FXW</u> Model Number _____ HP <u>1/2</u> Volts <u>220</u> Length of Drop Pipe <u>115</u> ft. capacity <u>8.5</u> G.P.M. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating					
16 Remarks, elevation, source of data, etc. ADDED INFO BY DRILLER: ITEM NO. _____ CORRECTED BY _____ ADDITION BY _____ ELEVATION _____ DEPTH TO ROCK _____						17 WATER WELL CONTRACTOR'S CERTIFICATION: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Don Inman Well Drilling</u> REGISTERED BUSINESS NAME REGISTRATION NO. _____ Address <u>4689 Betsie River Rd 1286</u> Signed <u>Don Inman</u> Date <u>10-10-78</u> AUTHORIZED REPRESENTATIVE					

D67d

100M (Rev. 12-68)

GEOLOGICAL SURVEY COPY

GEOLOGICAL SURVEY DIVISION
 P O BOX 30020
 LANSING, MICHIGAN-48909

LOCATION DATA			NAME & ADDRESS OF DRILLING CONTRACTOR(S)		
NAME(S) & ADDRESS OF OWNER(S) SHOWN ON PERMIT Tolas Oil & Gas Company 306 E Broadway Mt Pleasant, MI 48858					
LEASE NAME(S) & WELL NUMBER SHOWN PERMIT Miller 1-8			PERMIT NUMBER 44604		
COUNTY Grand Traverse	TOWNSHIP Mayfield	FRACTION NW 1/4 NE 1/4 NW 1/4	SECTION NO. 8	TOWN NO. 25 N 3	RANGE NO. 11 R 3
2. FORMATION DESCRIPTION		THICKNESS OF STRATUM	DEPTH TO BOTTOM OF STRATUM	3. WELL DEPTH (completed) 229 ft Date of Completion 11/05/91	
Red Clay		25	25	4. <input type="checkbox"/> Casing tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> <input type="checkbox"/> Hollow tool <input type="checkbox"/> Auger <input type="checkbox"/> Jetted <input type="checkbox"/>	
Gravel & Red Clay Sand		65	90	5. CASING Diameter <input type="checkbox"/> Steel <input type="checkbox"/> Threaded <input type="checkbox"/> Welded 4 <input checked="" type="checkbox"/> 209 in to _____ ft depth Surface 2 ft _____ in to _____ ft depth Weight _____ lbs/ft Gauging Drill Hole Diameter _____ in to _____ ft depth Drive Pipe <input type="checkbox"/> Yes <input type="checkbox"/> No _____ in to _____ ft depth	
Tan Clay		40	130	6. SCREEN <input type="checkbox"/> Not installed Type Plastic Diameter 4 ft Slot/Gauge 12 Length 20 ft Set between 209 ft and 229 ft TINGS <input type="checkbox"/> K Packer <input type="checkbox"/> Lead Packer <input type="checkbox"/> Bypass Check <input type="checkbox"/> Blank above screen _____ ft Other _____	
Gray Clay		75	205	7. STATIC WATER LEVEL ____ 144 ____ ft below land surface <input type="checkbox"/> Flow	
Medium Sand		24	229	8. PUMPING LEVEL below land surface ____ ft after _____ hrs pumping at _____ GPM ____ ft after _____ hrs pumping at _____ GPM	
				9. WELL IDENTIFICATION <input type="checkbox"/> No <input checked="" type="checkbox"/> Yes from _____ <input type="checkbox"/> Next closest <input checked="" type="checkbox"/> Nearest <input type="checkbox"/> Other _____ No. of bags of cement _____ Address _____	
				10. PUMP <input type="checkbox"/> Not installed <input type="checkbox"/> Pump installation by _____ Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of Dump Pipe _____ ft capacity _____ GPM TYPE <input type="checkbox"/> Submersible <input type="checkbox"/> Jet _____	
				11. REMARKS (ELEVATION, SOURCE OF DATA, WATER QUALITY, ETC.)	
(USE A 2ND SHEET IF NEEDED)					
12. AUTHORIZED REPRESENTATIVE CERTIFICATION (THIS WELL WAS DRILLED UNDER MY AUTHORITY AND THIS REPORT IS TRUE TO THE BEST OF MY KNOWLEDGE AND BELIEF.)					
NAME J&M Well Drilling Inc. PRINTED TYPE ADDRESS Rt. 1 Box 7B Elmira Mi. 49730 SIGNED Ron Shyrack DATE 11/11/91 DATE A 2ND SHEET OR ATTACH SUPPLEMENTS IF NEEDED FOR 1200 WORDS					

GEOLOGICAL SURVEY SAMPLE No.

JAN 16 1979

WATER WELL RECORD
ACT 294 PA 1985MICHIGAN DEPARTMENT
OF
PUBLIC HEALTH

1 LOCATION OF WELL		TOWNSHIP NAME		FRACTION		SECTION NUMBER		TOWN NUMBER		RANGE NUMBER	
Grand Traverse		Mayfield		1/4 NW 1/4		8		25 N/2		11 E/W.	
Distance And Direction from Road Intersection 1/2 mile west of B.T. Rd. on Miller Rd.											
Sketch Map: <div style="display: flex; align-items: center;"> <div style="border: 1px solid black; width: 100px; height: 100px; position: relative; margin-right: 10px;"> N W 1 MI. </div> <div style="border: 1px solid black; width: 200px; height: 100px; position: relative;"> Miller Rd. B.T. Rd. </div> </div>											
3 OWNER OF WELL: Gerald Glazien Traverse City, Mich											
4 WELL DEPTH: (completed) Date of Completion 190 ft. 10-16-78											
5 <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jatted <input type="checkbox"/> Bored											
6 USE: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public Supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air Conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test Well											
7 CASING: Threaded <input checked="" type="checkbox"/> Welded <input type="checkbox"/> Diam. 4 in. to 185 ft. Depth 110 lbs./ft. Height Above/Below Surface 1 ft. Drive Shoe? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>											
8 SCREEN: Type: S.S. Dia. 4" Slot/Groove .010 Length 5' Set between 185 ft. and 190 ft. Fittings:											
9 STATIC WATER LEVEL 165 ft. below land surface											
10 PUMPING LEVEL below land surface ft. after hrs. pumping G.P.M.											
11 WATER QUALITY in Parts Per Million: Iron (Fe) Chloride (Cl) Hardness Other											
12 WELL HEAD COMPLETION: <input type="checkbox"/> In Approved Pit <input checked="" type="checkbox"/> Pitless Adapter <input checked="" type="checkbox"/> 12" Above Grade											
13 Well Grouted <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Neat Cement <input checked="" type="checkbox"/> Bentonite <input checked="" type="checkbox"/> SAND Depth: From ft. to ft.											
14 Nearest Source of possible contamination 50 feet Direction Supt. Type Well disinfected upon completion <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No											
15 PUMP: <input type="checkbox"/> Not installed Manufacturer's Name Red Jacket Model Number 2-W HP 1/4 Volts 230 Length of Drop Pipe 175 ft. capacity 10 G.P.M. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating											
16 REMARKS, ELEVATION, SOURCE OF DATA, ETC. <div style="border: 1px solid black; padding: 5px;"> ADDITIONAL INFO BY DRILLER, ITEM NO *CORRECTED BY **ADDITION BY ELEVATION DEPTH TO ROCK </div>											
17 WATER WELL CONTRACTOR'S CERTIFICATION: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. REGISTERED BUSINESS NAME: 0481 Address: 10785 Grandview Rd. T.C. Signed: [Signature] Date: 10-13-78 AUTHORIZED REPRESENTATIVE											

D67d



100M (Rev. 12-68)

GEOLOGICAL SURVEY COPY

GEOLOGICAL SURVEY NO.

MICHIGAN DEPARTMENT OF PUBLIC HEALTH
WATER WELL AND PUMP RECORD

				1	4	6	0	9
PERMIT NUMBER								

1 LOCATION OF WELL County GRAND TRAVERSE		Township Name MAYFIELD		Fraction NE 1/4 SE 1/4 SW 1/4		Section Number 8		Town Number T. 25 N.		Range Number R. 11 W.	
Distance And Direction From Road Intersection off HARRAND ROAD ON Bott ROAD, WEST SIDE OF ROAD.						3 OWNER OF WELL: DEAN BOTT Address 7134 S. NANNAH ROAD Address Same As Well Location? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No					
Street Address & City of Well Location Bott Road						4 WELL DEPTH: Date Completed 7/16/87 122 FT. <input checked="" type="checkbox"/> New Well <input type="checkbox"/> Replacement Well					
Locate with "X" in Section Below 						Sketch Map: 					
2 FORMATION DESCRIPTION				THICKNESS OF STRATUM		DEPTH TO BOTTOM OF STRATUM		5 CASING: <input type="checkbox"/> Steel <input type="checkbox"/> Threaded <input checked="" type="checkbox"/> Plastic <input checked="" type="checkbox"/> Welded Diameter 5 in. to 11 7/8 ft. depth Height: Above/Below Surface 1 ft. Weight 3 lbs./ft. Drive Shoe <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
SAND & ROCKS				8		8		6 USE: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Type I Public <input type="checkbox"/> Type III Public <input type="checkbox"/> Irrigation <input type="checkbox"/> Type IIa Public <input type="checkbox"/> Heat pump <input type="checkbox"/> Test Well <input type="checkbox"/> Type IIb Public			
SAND & GRAVEL				47		55		7 SCREEN: <input type="checkbox"/> Not Installed Type PVC Diameter 4 1/4 INCH Slot/Gauge 10 Length 5 FEET Set between 117 ft. and 122 ft. Fittings: <input checked="" type="checkbox"/> K-Packer <input type="checkbox"/> Lead Packer <input type="checkbox"/> Bremer Check <input checked="" type="checkbox"/> Blank above screen ft. Other			
GRAVEL				26		81		9 STATIC WATER LEVEL: 82 ft. below land surface <input type="checkbox"/> Flow			
SAND				41		122		10 PUMPING LEVEL: below land surface _____ ft. after _____ hrs. pumping at _____ G.P.M. _____ ft. after _____ hrs. pumping at _____ G.P.M.			
								11 WELL HEAD COMPLETION: <input checked="" type="checkbox"/> Flareless adapter <input type="checkbox"/> 12" above grade <input type="checkbox"/> Basement offset <input type="checkbox"/> Approved pit			
								12 WELL GROUTED? <input type="checkbox"/> No <input checked="" type="checkbox"/> Yes From _____ to _____ ft. <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Other WOLCLAY No. of bags of cement _____ Additives _____			
								13 Nearest source of possible contamination Type SEPTIC Distance 50 ft. Direction _____ Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Was old well plugged? <input type="checkbox"/> Yes <input type="checkbox"/> No			
RECEIVED Mich. Dept. of Public Health SEP 24 1987 Bureau of Environmental and Occupational Health - CWOS								14 PUMP: <input type="checkbox"/> Not installed <input type="checkbox"/> Pump Installation Only Manufacturer's name RED JACKET Model number SW HP 1/2 Volts 230 Length of Drop Pipe 100 ft. capacity _____ G.P.M. TYPE: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> 1" PVC PRESSURE TANK: WELL X-TROL Manufacturer's name WEXCOR Capacity 40 Gallons			
								15. Remarks, elevation, source of data, etc.			
17. Rig Operator's Name: DOUG SCHETTER				16. WATER WELL CONTRACTOR'S CERTIFICATION: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. PHIL'S WELL DRILLING 0481 REGISTERED BUSINESS NAME REGISTRATION NO. Address 10785 GRANDVIEW RD TC Signed Phil Sherman Date 7-25-87							

D67d 12/85


GEOLOGICAL SURVEY COPY

Act 368 PA 1978
Required
Conviction of a violation
of any provision is a
misdemeanor.

GEOLOGICAL SURVEY SAMPLE No.

OCT 18 1977

WATER WELL RECORD
ACT 294 PA 1966MICHIGAN DEPARTMENT
OF
PUBLIC HEALTH

1 LOCATION OF WELL County <u>Grand Traverse</u> Township Name <u>MAYFIELD</u> Fraction <u>SE 1/4 SW 1/4</u> Section Number <u>8</u> Town Number <u>T25 N. 1/2</u> Range Number <u>R11 E. W.</u> Distance And Direction from Road Intersections <u>3/4 MILE WEST OF M-37 ON HARRAND RD.</u> Street address & City of Well Location Locate with "X" in section below		3 OWNER OF WELL: Address <u>Jack Zimmerman</u> <u>1212 Hayfield Ave.</u> <u>Grand Traverse City, Mich.</u> 4 WELL DEPTH: (completed) Date of Completion <u>109 ft. 8-4-77</u>																
Sketch Map: 		5 <input checked="" type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dig <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> 6 USE: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public Supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air Conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test Well <input type="checkbox"/>																
2 FORMATION <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>FORMATION</th> <th>THICKNESS OF STRATUM</th> <th>DEPTH TO BOTTOM OF STRATUM</th> </tr> </thead> <tbody> <tr> <td><u>sand + gravel</u></td> <td><u>60</u></td> <td><u>60</u></td> </tr> <tr> <td><u>hard pan</u></td> <td><u>6</u></td> <td><u>66</u></td> </tr> <tr> <td><u>gravel</u></td> <td><u>34</u></td> <td><u>100</u></td> </tr> <tr> <td><u>water sandstone</u></td> <td><u>9</u></td> <td><u>109</u></td> </tr> </tbody> </table>		FORMATION	THICKNESS OF STRATUM	DEPTH TO BOTTOM OF STRATUM	<u>sand + gravel</u>	<u>60</u>	<u>60</u>	<u>hard pan</u>	<u>6</u>	<u>66</u>	<u>gravel</u>	<u>34</u>	<u>100</u>	<u>water sandstone</u>	<u>9</u>	<u>109</u>	7 CASING: Threaded <input checked="" type="checkbox"/> Welded <input type="checkbox"/> Diam. <u>4</u> in. to <u>105</u> ft. Depth Height: Above/Below Surface <u>11</u> ft. Weight <u>11</u> lbs./ft. Drive Shoe? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>	
FORMATION	THICKNESS OF STRATUM	DEPTH TO BOTTOM OF STRATUM																
<u>sand + gravel</u>	<u>60</u>	<u>60</u>																
<u>hard pan</u>	<u>6</u>	<u>66</u>																
<u>gravel</u>	<u>34</u>	<u>100</u>																
<u>water sandstone</u>	<u>9</u>	<u>109</u>																
8 SCREEN: Type: <u>Johnson</u> Dia.: <u>3"</u> Slot Gauge <u>12</u> Length <u>4'</u> Set between <u>105</u> ft. and <u>109</u> ft. Fittings: <u>Packer + set link</u>		9 STATIC WATER LEVEL <u>90</u> ft. below land surface 10 PUMPING LEVEL below land surface <u>100</u> ft. after <u>1</u> hrs. pumping <u>6</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m.																
11 WATER QUALITY in Parts Per Million: Iron (Fe) <u> </u> Chlorides (Cl) <u> </u> Hardness <u> </u> Other <u> </u>		12 WELL HEAD COMPLETION: <input type="checkbox"/> In Approved Pit <input checked="" type="checkbox"/> Pitless Adapter <input type="checkbox"/> 12" Above Grade																
13 Well Grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Neat Cement <input type="checkbox"/> Bentonite <u>gravel</u> Depth: From <u>0</u> ft. to <u>60</u> ft.		14 Nearest Source of possible contamination <u>100</u> feet <u>any</u> Direction <u> </u> Type <u> </u> Well disinfected upon completion <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No																
15 PUMP: <input type="checkbox"/> Not installed Manufacturer's Name <u>DALLEY</u> Model Number <u> </u> HP <u>1/2</u> Volts <u>220</u> Length of Drop Pipe <u>100</u> ft. capacity <u>10</u> G.P.M. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating		17 WATER WELL CONTRACTOR'S CERTIFICATION: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Cliff Well Drilling Co. 1244</u> REGISTERED BUSINESS NAME REGISTRATION NO. Address <u>6410 Capital Rd. Grand Traverse City, Mich.</u> Signed <u>Robert K. Kinnick</u> Date <u>8-8-77</u> AUTHORIZED REPRESENTATIVE																
16 Remarks, elevation, source of data, etc. USE A 2ND SHEET IF NEEDED																		

D67d

100M (Rev. 12-68)

GEOLOGICAL SURVEY COPY

GEOLOGICAL SURVEY SAMPLE NO. WATER WELL RECORD
ACT 294 PA 1965MICHIGAN DEPARTMENT
OF
PUBLIC HEALTH 11

1 LOCATION OF WELL			3 OWNER OF WELL:		
County GRAND TRAVERSE	Township Name MAYFIELD	Fraction 1/4 NE 1/4 SW 1/4	Section Number 8	Town Number 25 N/A.	Range Number 10 E/W.
Distance And Direction from Road Intersections 3/4 MILE ON BOTT RD SOUTH FROM MILLER RD.			Address 7700 BOTT RD		
Street address & City of Well Location Locate with "X" in section below			4 WELL DEPTH: (completed) Date of Completion 107 ft. 8-3-78		
<div style="display: flex; align-items: center;"> <div style="border: 1px solid black; padding: 5px; margin-right: 10px;"> </div> <div> <p>Sketch Map</p> <p>MILLER RD. 113</p> <p>BOTT RD. 37</p> </div> </div>			5 <input checked="" type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jotted <input checked="" type="checkbox"/> Bored <input type="checkbox"/>		
			6 USE: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public Supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air Conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test Well <input type="checkbox"/>		
2 FORMATION			7 CASING: Threaded <input checked="" type="checkbox"/> Welded <input type="checkbox"/> Height: Above/Below Surface 1 ft.		
			Weight 11.09 lbs./ft. Drive Shoe? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>		
THICKNESS OF STRATUM			8 SCREEN:		
DEPTH TO BOTTOM OF STRATUM			Type: S.S. Dia.: 4"		
SAND 8 8			Slot/Groove .010 Length 5'		
GRAVEL 43 51			Set between 102 ft. and 107 ft.		
ROCK 16 67			Fittings:		
SAND 15 82			9 STATIC WATER LEVEL 82 ft. below land surface		
WATER SAND 25 107			10 PUMPING LEVEL below land surface		
			ft. after ___ hrs. pumping ___ g.p.m.		
			ft. after ___ hrs. pumping ___ g.p.m.		
			11 WATER QUALITY in Parts Per Million:		
			Iron (Fe) ___ Chlorides (Cl) ___		
			Hardness ___ Other ___		
			12 WELL HEAD COMPLETION: <input type="checkbox"/> In Approved Pit		
			<input checked="" type="checkbox"/> Pitless Adapter <input type="checkbox"/> 12" Above Grade		
			13 Well Grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
			<input type="checkbox"/> Neat Cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/>		
			Depth: From ___ ft. to ___ ft.		
			14 Nearest Source of possible contamination		
			50 feet Direction SEPTIC Type		
			Well disinfected upon completion <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
			15 PUMP:		
			<input type="checkbox"/> Not installed		
			Manufacturer's Name Red Jacket		
			Model Number 2-10 H.P. Volts 230		
			Length of Drop Pipe 90 ft. capacity 10 G.P.M.		
			Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating		
16 Remarks, elevation, source of data, etc. S.P.			17 WATER WELL CONTRACTOR'S CERTIFICATION:		
			<p>This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.</p> <p>PHIL'S WELL DRILLING 0491</p> <p>REGISTERED BUSINESS NAME REGISTRATION NO.</p> <p>Address 10785 GRAND VIEW RD. T.C.</p> <p>Signed Phil Shernack Date 8-3-78</p> <p>AUTHORIZED REPRESENTATIVE</p>		

D67d

100M (Rev. 12-68)


GEOLOGICAL SURVEY COPY

WATER WELL RECORD

ACT 294 PA 1985

MICHIGAN DEPARTMENT Page D-23

OF
PUBLIC HEALTH


1 LOCATION OF WELL		Fraction	Section Number	Town Number	Range Number
County	Township Name	SW <input type="checkbox"/> SW <input type="checkbox"/> SW <input type="checkbox"/>	9	25 N.S.	11 E.W.
Distance And Direction from Road Intersections 120' E. of M-37 800' N. of HARRARD RD		3 OWNER OF WELL: Gerald GLAZIER Address			
Street address & City of Well Location Locate with "X" in section below		4 WELL DEPTH: (completed) Date of Completion 129 ft. 4-23-70			
<div style="text-align: center;">Sketch Map: </div>		5 <input checked="" type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Auger <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored			
		6 USE: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public Supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air Conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test Well			
7 CASING: <input type="checkbox"/> Threaded <input checked="" type="checkbox"/> Welded <input type="checkbox"/> Height: Above/Below Surface Diam. 4 in. to 129 ft. Depth 11 lbs./ft. Drive Shoe? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>		8 SCREEN: Type: BRASS Diam. 4" Length 5' 375.00 Slot/Bore 10/10 Set between 127 ft. and 129 ft. 129 3.00 Fittings: LEAD PACKER			
2 FORMATION		9 STATIC WATER LEVEL 103 ft. below land surface			
CLAY		10 PUMPING LEVEL below land surface ft. after hrs. pumping g.p.m.			
SAND		ft. after hrs. pumping g.p.m.			
CLAY		11 WATER QUALITY in Parts Per Million: Iron (Fe) Chlorides (Cl) Hardness Other			
GRAVEL		12 WELL HEAD COMPLETION: <input type="checkbox"/> In Approved Pit <input checked="" type="checkbox"/> Pitless Adapter <input type="checkbox"/> 12" Above Grade			
WATER SAND		13 Well Grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Neat Cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Depth: From ft. to ft.			
		14 Nearest Source of possible contamination 75 feet NE Direction Twp. 11 S. R. 14 E. Type Well disinfected upon completion <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No			
		15 PUMP: <input type="checkbox"/> Not installed Manufacturer's Name F x W Model Number HP 1/2 Volts 230 Length of Drop Pipe 116 ft. capacity G.P.M. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating			
16 Remarks, elevation, source of data, etc. Added data by driller, item no. WORKED BY: K. J. [unclear]		17 WATER WELL CONTRACTOR'S CERTIFICATION: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. PHIL'S WELL DRILLING 0481 REGISTERED BUSINESS NAME REGISTRATION NO. Address 10785 Harborside Rd T.C. Signed Phil Shamowski Date 4-30-70 AUTHORIZED REPRESENTATIVE			

D57d 2/84

WATER WELL AND PUMP RECORD

PART 127 ACT 368, P.A. 1978

PERMIT NU Page D-25

1. LOCATION OF WELL		FRACTION		SECTION NUMBER	TOWN NUMBER	RANGE NUMBER
County	Township Name	NE 1/4 NW 1/4 NW 1/4		9	T. 25 N. 13	R. 11 W.
Distance And Direction From Road Intersection		3. OWNER OF WELL				
2 MILE EAST OF M-37 ON M-113. SOUTH SIDE OF ROAD		JACK ZIMMERMAN Address 1719 APACHE PASS Address Same As Well Location? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No				
Street Address & City of Well Location		4. WELL DEPTH: (completed) 70 ft. Date of Completion 3-6-84				
Locate with "X" in Section Below		5. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input checked="" type="checkbox"/> Auger <input type="checkbox"/> Jetted <input type="checkbox"/>				
		6. USE: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Type I Public <input type="checkbox"/> Type III Public <input type="checkbox"/> Irrigation <input type="checkbox"/> Type IIA Public <input type="checkbox"/> Heat pump <input type="checkbox"/> Test Well <input type="checkbox"/> Type IIB Public <input type="checkbox"/>				
		7. CASING: <input checked="" type="checkbox"/> Steel <input checked="" type="checkbox"/> Threaded <input type="checkbox"/> Plastic <input type="checkbox"/> Welded Diameter 4 in. to 66 ft depth Grouted Drill Hole Diameter 4 in. to 66 ft depth Height Above/Below Surface 4 ft. Weight 11 lbs./ft. Drive Shoe <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No				
2. FORMATION DESCRIPTION		THICKNESS OF STRATUM	DEPTH TO BOTTOM OF STRATUM	8. SCREEN: <input type="checkbox"/> Not Installed		
Sand		12	12	Type Johnson Diameter 4		
Clay		24	36	Slot/Gauge 10 Length 4		
wet gravel		36	62	Set between 66 ft. and 70 ft.		
water sand		8	70	FITTINGS: <input type="checkbox"/> K-Packer <input checked="" type="checkbox"/> Lead Packer <input type="checkbox"/> Bremer Check <input type="checkbox"/> Blank above screen <input type="checkbox"/> Other		
				9. STATIC WATER LEVEL 36 ft. below land surface <input type="checkbox"/> Flow		
				10. PUMPING LEVEL: below land surface 50 ft. after 1 hrs. pumping at 35 G.P.M.		
				11. WELL HEAD COMPLETION <input checked="" type="checkbox"/> Pitless adapter <input type="checkbox"/> 12" above grade <input type="checkbox"/> Basement offset <input type="checkbox"/> Approved pit		
				12. WELL GROUTED? <input type="checkbox"/> No <input checked="" type="checkbox"/> Yes From 0 to 36 ft. <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Other mud		
				13. Nearest source of possible contamination Type Syntex Distance 60 ft. Direction W		
				Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
				14. PUMP: <input type="checkbox"/> Not Installed <input type="checkbox"/> Pump Installation Only		
				Manufacturer's name Flint & Walling		
				Model number 51808 HP 1/2 Volts 110		
				Length of Drop Pipe 50 ft. capacity 10 G.P.M.		
				TYPE: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Jet		
				PRESSURE TANK: Manufacturer's name own tank 42 gal.		
				Model number Capacity Gallons		
15. Remarks, elevation, source of data, etc.		16. WATER WELL CONTRACTOR'S CERTIFICATION: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Cliff Wall Outing 8. 28-1244 REGISTERED BUSINESS NAME REGISTRATION NO. Address 6410 South Rd. Traverse City Mich. Signed Robert J. Zimmerman Date 3-6-84 AUTHORIZED REPRESENTATIVE				

ATTACHMENT F

MAPS AND CROSS SECTIONS OF GEOLOGIC STRUCTURE OF AREA

Regional Geology

Grand Traverse County is located on the Northwest flank of the Michigan Basin as indicated on Figure F-1. The regional dip to the south into the basin is about 30-40 feet per mile. The basin extends into northwest Ohio and northeast Indiana and covers all of the lower peninsula of Michigan. To the West-Northwest is the Wisconsin Dome. To the southeast is the structural axis of the Findlay Arch and to the southwest is the axis of the Kankakee Arch. A generalized East-West geologic cross section is included as Figure F-2. Figure F-3 is a generalized stratigraphic column for the State of Michigan.

Area Geology

A cross section of the geologic structure through the area of interest is presented in Figure F-5. Figure F-4 shows the trace of this cross sections.

The injection zone is the Traverse Limestone of Devonian age from 1750' to 2344'. (Total depth of well 2200') The top confining zone is the Coldwater and Antrim Shales from 781 feet to 1750'. The bottom confining zone is the Bell Shale from 2344 feet to 2448 feet.

The following sample descriptions were prepared by Geologist Warren A. Baumann and Jim Sanborn. - *Thur info is based on what?*

Drift	0 to 781'	Sand & gravel. Sm redish shales.
Coldwater	781' to 1506'	Sh, lt-med grys, frm, sub rnd, sli calc, pyr.
Antrim	1506' to 1750'	Shale, blk to dk brn, frm-britt, sub rnd v. grainy text, fnt yel glo flor.
Trav. Form	1750' to 1816'	Sh, lt grys frm, sub rnd. Smdolic, brn stringers, v. calc. pyr.
Trav. Lime	1816' to 1870'	Ls, lt tan to buff, fxltn, mhd, gd, intrxltn & micro pore porosity, no vis, stn, cln.
Trav. Lime	1870' to 2100'	Ls, lt-med brns, vfxln, hd dns arg, sm gy shale, stringers, Trs, sue porosity cln, abnt fos.
Trav. Lime	2100' to 2200'	Ls, med gy brn to crmy tans, vfxln, hd dns, arg, sm gd micro, por porosity. intrvl from 2100 - 50. No stn - fos.

The Coldwater shale of the Mississippian System (Paleozoic age) consist primarily of gray and bluish gray shale. The shale is micraceous in some areas and usually contains small amounts of limestone, dolomite, siltstone or sandstone. In the Weber 4-8, the Coldwater Shale was described as being light to medium gray in color, firm and slightly calcareous. The Coldwater is about 725 feet thick at the Weber 4-8 wellsite and is underlain with the Antrim shale.

Below the Coldwater is the Antrim Shale of Devonian age. The Antrim is predominately a dark gray to black and brown, hard, thin-bedded, brittle carbonaceous shale. In the Weber 4-8, the Antrim Shale was described as being black to dark brown, firm, brittle with a very grainy texture. At the Weber 4-8 wellsite the Antrim is about 245 feet thick.

Below the Antrim is the Traverse Group of Devonian age. The Traverse group is generally divided into three units. These units are the Traverse Formation, Traverse Limestone and the Bell Shale. Some consider the Traverse Formation to be a transition zone between the Antrim Shale and Traverse Limestone. This formation generally is composed of Gray shale in the upper portion and graduates to more calcareous shale and limestone near the base. In the Weber 4-8, the Traverse Formation was described as being a light gray firm shale with small brown dolmitic stringers. The Traverse Formation is 60 to 70 feet thick in the vicinity of the Weber 4-8.


The middle unit of the Traverse Group is the Traverse Limestone. In Western Michigan the Traverse Limestone is predominately pure limestone with some beds of dolomite. A series of porosity zones is often present in the upper portion of the Limestone. In the Weber 4-8, the Traverse Limestone was described as being light tan to buff, with intercrystalline and micro porosity and small hard dense shale and sandstone stringers. The Traverse Limestone is over 500 feet thick in the area of the Weber 4-8.

The lowermost formation of the Traverse Group is the Bell Shale. The Bell Shale is a little over 100 feet thick in the area of interest.

Below the Bell Shale is the Dundee Formation of Devonian age. The Dundee is a Limestone predominately buff to brownish in color, and normally fine to coarsely crystalline. The Dundee is 180 to 200 feet thick in the vicinity of the Weber 4-8.

Below the Dundee is the Detroit River Group. The rocks of the Detroit River Group are variously composed dolomite, anhydrite, salt, limestone and sandstone.

FIGURE F-1
MICHIGAN REGIONAL GEOLOGY MAP



From Bulletin 57
Indiana Geological Survey

FIGURE F-2
GENERALIZED EAST-WEST CROSS-SECTION MICHIGAN BASIN




Figure F-4



Map of Trace of Cross Section

Figure F-5






Figure 6




Map Antrim Production

Figure F-7



Structure Map
Top of Trenton

Figure F-8



Isopach Map of Trenton

ATTACHMENT H
OPERATING DATA

This permit application is for the purpose of adding leachate water from the Glen's Sanitary Landfill to the saltwater presently being injected into the Weber #4-8 Saltwater Disposal Well.


The Weber #4-8 was originally drilled in November of 1982 under Michigan Permit #36221. Team Completion L.L.C. submitted a Permit Application to dispose of saltwater from wells owned by other operators in the area and USEPA Permit #MI-055-2D-C034 was issued on April 8, 2003. Approval to start injection into the Weber #4-8 was received on July 23, 2004.

Sodium Chloride/Calcium Chloride brine water produced from the Niagaran is being injected into the Traverse and Traverse Lime Formation between 1791 and 2200 feet. [The brine has a specific gravity of from 1.02 to 1.07 (8.5 to 8.9 pounds/gallon).] Daily disposal rates are between 29 and 88 gallons per minute (1000 bbl to 3000 bbl per day) with no surface pressure. Typical analysis of the brine water is shown on page H-2! - increased

It is proposed that in addition to the present brine water being injected that leachate from the Glen's Sanitary Landfill at Maple City, Michigan be injected. With the addition of the leachate the anticipate daily injection rates are between 29 and 146 gallons per minute (1000 bbl to 5000 bbl per day). It is expected that the combined waste fluids will be injected at zero surface pressure and no pumps will be required.

Two analysis of the leachate from the Glen's Sanitary Landfill is shown on pages H-3 through H-13. The first sample was collected on August 30, 2006 and the second sampled on May 22, 2007.

ANALYSIS OF INJECTED BRINE WATER



(231) 369-3308
(231) 369-3329
(800) 253-1412
Fax: (231) 369-3331

Midwest

Analytical Laboratories, Inc.
P.O. Box 467
Kalkaska, MI 49646

Company: Team Services
P.O. Box 1104
Kalkaska, MI 49646

Operator: Schmude Oil Co.
Well Name: Townsite 1-17 HD
Permit #: 39888
Location: SE-NE-NE, Sec. 17
T27N-R7W, Kalkaska Twp
Kalkaska County

Project #: na
Location: Townsite 1-17 HD
Sample Date: 06/26/02
Sample of: Water
Submitted Date: 06/26/02
Sample Point: na
Sampled by: Team Services
Analysis Date: 07/09/02
Analysis #: 262602

EPA Method	Cations	mg/L	Detection Limit
273.1	Sodium	47000	0.01 mg/L
258.1	Potassium	16800	0.04 mg/L
215.1	Calcium	78200	0.04 mg/L
242.1	Magnesium	8300	0.01 mg/L
236.1	Iron (Total)	52	1 mg/L
208.1	Barium	7	1 mg/L
EPA Method	Anions	mg/L	Detection Limit
325.3	Chloride	225000	1 mg/L
375.4	Sulfate	83	10 mg/L
310.1 Alkalinity as	Carbonate	nd	1 mg/L
310.1 Alkalinity as	Bicarbonate	62	1 mg/L
376.2	Sulfide	nd	1.0 mg/L
	Total Dissolved Solids	375504	—
Result			
120.1	Resistivity(Ohm-m)	0.047	@ 25 Deg. C
150.1	pH	4.81	@ 25 Deg. C
—	Specific Gravity	1.256	@ 60 Deg. F(Water=1)

nd=not detected

USEPA Methods for the Chemical Analysis of Water and Wastes, 3rd. Edition

ANALYSIS OF LEACHATE WATER



GEOCHEMICAL TESTING

Environmental and Energy Analysis

2005 N Center Ave
Somerset PA 15501

814/443-1671
814/445-8686
FAX: 814/445-6729

Friday, September 29, 2006

DEBBIE JOHNSTON
GLEN'S SANITARY LANDFILL INC
WASTE MANAGEMENT OF N MICHIGAN
518 E TRAVERSE HIG
MAPLE CITY, MI 49664

TEL:
FAX

RE: GLENS 500 A

Dear DEBBIE JOHNSTON:

Order No.: G0608586

Geochemical Testing received 1 sample(s) on 8/31/2006 for the analyses presented in the following report.

There were no problems with the analyses and all QC data met NELAC, EPA, and laboratory specifications except where noted in the Case Narrative.

If you have any questions regarding these tests results, please feel free to call.

Sincerely,

William Thuermer

David M. Glessner
Laboratory Manager

Susan K. Gerhard
Project Manager

Report(s) To:
DON CONWAY



AUG-13-2007 13:34 FROM: GLENS LANDFILL

231-228-5991

TO: 2312584470

Page H-4
May 2008**Geochemical Testing**

Date: 29-Sep-06

CLIENT: GLEN'S SANITARY LANDFILL INC
Project: GLENS 500 A
Lab Order: G0608586

CASE NARRATIVE

No problems were encountered during analysis of this work order number, except as noted.

The determinative step for cyanide was subcontracted to STL-Buffalo. A copy of the subcontractor's laboratory report is enclosed with this Analytical Report. This laboratory meets NELAC and EPA laboratory accreditations. The reference method from this lab for total cyanide is EPA 335.2, "Cyanide, total".

Qualifiers:

ND - Not Detected at the Reporting Limit

J - Indicates an estimated value.

U - The analyte was not detected at or above the listed concentration, which is below the laboratory quantization limit.

B - Analyte detected in the associated Method Blank

S - Spike Recovery outside accepted recovery limits

R - RPD outside accepted recovery limits

E - Value above quantitation range

* - Value exceeds Action Limit

H - Method Hold Time Exceeded



AUG-13-2007 13:35 FROM: GLENS LANDFILL

231-228-5991

TO: 2312584470

Page H-5
May 2008

Laboratory Results

Geochemical Testing

Date: 29-Sep-06

CLIENT: GLEN'S SANITARY LANDFILL INC
 Lab Order: G0608586
 Project: GLENS 500 A
 Lab ID: G0608586-001
 Matrix: LEACHATE

Client Sample ID: Tank B

Sampled By: Gosling Czubak, Inc.
 Collection Date: 8/30/2006 11:00:00 AM
 Received Date: 8/31/2006

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
FIELD PARAMETERS						
		FLD				Analyst:
pH (Field)	8.32			S.U.	0	8/30/2006 11:00:00 AM
Specific Conductance (Field)	10560			umhos/cm	0	8/30/2006 11:00:00 AM
Temperature (Field)	27.1			deg C	0	8/30/2006 11:00:00 AM
INORGANIC NON-METALS						
Alkalinity to pH 4.5	3800	SM 18 2320B	5	mg/L CaCO3	1	Analyst: SAG 9/6/2006 9:55:00 PM
INORGANIC NON METALS						
Bicarbonate	3540	SM4500-CO2D	5	mg/L CaCO3	1	Analyst: SAG 9/6/2006 9:55:00 PM
INORGANIC NON-METALS						
Chloride	1600	EPA 325.2	20	mg/L	10	Analyst: SLY 9/7/2006 10:19:46 AM
TOTAL CYANIDE						
Cyanide, total	0.01	SM 18 4500-CN-C&E	0.01	U mg/L	1	Analyst: SUB 9/8/2006
INORGANIC NON-METALS						
Carbonate	68	SM4500-CO2D	5	mg/L CaCO3	1	Analyst: SAG 9/6/2006 9:55:00 PM
INDICATOR ORGANIC PARAMETERS						
Chemical Oxygen Demand	1130	HACH 8000	5	mg/L	1	Analyst: AND 9/6/2006 12:20:00 PM
PHYSICAL TESTS						
Specific Conductance	9970	EPA 120.1	1	umhos/cm	1	Analyst: SAG 9/6/2006 9:55:00 PM
INORGANIC NON-METALS						
Ammonia Nitrogen	508	EPA 350.1D	30.0	mg/L as N	200	Analyst: SLY 9/26/2006
INORGANIC NON-METALS						
Nitrite Nitrogen	< 0.05	SM4500-B	0.05	mg/L as N	1	Analyst: MAP 9/1/2006 10:15:00 AM
INORGANIC NON-METALS						
Nitrate Nitrogen	< 0.05	EPA 353.2	0.05	mg/L as N	1	Analyst: SLY 9/5/2006 1:19:02 PM
PH BY SM 4500 H+B						
pH	8.31	SM4500-H+B	0	su	1	Analyst: SAG 9/6/2006 9:55:00 PM
INDICATOR ORGANIC PARAMETERS						
Phenolics	188	EPA 420.1	100	ug/L	10	Analyst: MMR 9/18/2006 10:20:00 AM
INORGANIC NON-METALS						
Sulfate	< 10	EPA 375.4	10	mg/L	1	Analyst: SLY 9/6/2006
NOTES:						
S - Outlying spike recovery observed. A duplicate analysis was performed with similar results indicating a matrix effect.						
PHYSICAL TESTS						
Total dissolved solids	4810	SM2540-C	10	mg/L	1	Analyst: SAG 8/31/2006 7:51:00 PM



Laboratory Results

Date: 29-Sep-06

Geochemical Testing

CLIENT: GLEN'S SANITARY LANDFILL INC
Lab Order: G0608586
Project: GLENS 500 A
Lab ID: G0608586-001
Matrix: LEACHATE

Client Sample ID: Tank B

Sampled By: Gosling Czubak, Inc.
Collection Date: 8/30/2006 11:00:00 AM
Received Date: 8/31/2006

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
INORGANIC NON METALS						Analyst: LAN
Total Inorganic Nitrogen	26.6	0.04		mg/L as N	1	8/5/2006
INORGANIC METALS						Analyst: JLH
		EPA 200.7				
Barium	0.04	0.01		mg/L	1	9/5/2006 7:00:00 PM
Calcium	47.8	0.1		mg/L	1	9/5/2006 7:00:00 PM
Cobalt	0.019	0.005		mg/L	1	9/5/2006 7:00:00 PM
Iron	2.16	0.05		mg/L	1	9/5/2006 7:00:00 PM
Magnesium	112	0.1		mg/L	1	9/5/2006 7:00:00 PM
Manganese	0.04	0.01		mg/L	1	9/5/2006 7:00:00 PM
Nickel	0.12	0.01		mg/L	1	9/5/2006 7:00:00 PM
Potassium	530	5.0		mg/L	10	9/5/2006 3:40:00 PM
Sodium	1370	2.0		mg/L	10	9/5/2006 3:40:00 PM
Vanadium	0.031	0.005		mg/L	1	9/5/2006 7:00:00 PM
Zinc	0.03	0.01		mg/L	1	9/5/2006 7:00:00 PM
INORGANIC METALS						Analyst: NPT
		EPA 200.8				
Antimony	< 10	10		µg/L	10	9/12/2006 3:45:00 PM
Arsenic	24.4	10		µg/L	10	9/12/2006 3:45:00 PM
Beryllium	< 10	10		µg/L	10	9/14/2006 3:35:00 PM
Cadmium	< 2.0	2.0		µg/L	10	9/12/2006 3:45:00 PM
Chromium	51.6	20.0		µg/L	10	9/12/2006 3:45:00 PM
Copper	36.0	20.0		µg/L	10	9/19/2006 6:05:00 PM
Lead	< 10	10		µg/L	10	9/12/2006 3:45:00 PM
Selenium	24.3	10		µg/L	10	9/12/2006 3:45:00 PM
Silver	< 5.0	5.0		µg/L	10	9/12/2006 3:45:00 PM
Thallium	< 2.0	2.0		µg/L	10	9/12/2006 3:45:00 PM
VOLATILE ORGANIC COMPOUNDS						Analyst: JW
		EPA 8260B				
1,1,1,2-Tetrachloroethane	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
1,1,1-Trichloroethane	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
1,1,2,2-Tetrachloroethane	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
1,1,2-Trichloroethane	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
1,1-Dichloroethane	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
1,1-Dichloroethene	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
1,2,3-Trichloropropane	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
1,2-Dibromo-3-chloropropane	< 5.0	5.0		µg/L	1	9/2/2006 5:51:00 AM
1,2-Dibromoethane	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
1,2-Dichlorobenzene	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
1,2-Dichloroethane	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
1,2-Dichloropropane	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
1,4-Dichlorobenzene	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
2-Hexanone	< 5.0	5.0		µg/L	1	9/2/2006 5:51:00 AM



Laboratory Results

Geochemical Testing

Date: 29-Sep-06

CLIENT: GLEN'S SANITARY LANDFILL INC

Client Sample ID: Tank B

Lab Order: G0608586

Project: GLENS 500 A

Sampled By: Gosling Czubak, Inc.

Lab ID: G0608586-001

Collection Date: 8/30/2006 11:00:00 AM

Matrix: LEACHATE

Received Date: 8/31/2006

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
VOLATILE ORGANIC COMPOUNDS				EPA 8260B		Analyst: JW
4-Methyl-2-Pentanone	1.9	1.0		µg/L	1	9/2/2006 5:51:00 AM
Acetone	57.1	25.0		µg/L	1	9/2/2006 5:51:00 AM
Acrylonitrile	< 5.0	5.0		µg/L	1	9/2/2006 5:51:00 AM
Benzene	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
Bromochloromethane	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
Bromomethane	< 5.0	5.0		µg/L	1	9/2/2006 5:51:00 AM
Carbon Disulfide	< 5.0	5.0		µg/L	1	9/2/2006 5:51:00 AM
Carbon Tetrachloride	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
Chlorobenzene	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
Chlorodibromomethane	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
Chloroethane	< 5.0	5.0		µg/L	1	9/2/2006 5:51:00 AM
Chloromethane	< 5.0	5.0		µg/L	1	9/2/2006 5:51:00 AM
cis-1,2-Dichloroethene	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
cis-1,3-Dichloropropene	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
Dibromomethane	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
Dichlorobromomethane	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
Ethylbenzene	2.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
Iodomethane	< 5.0	5.0		µg/L	1	9/2/2006 5:51:00 AM
Methyl Ethyl Ketone	17.6	5.0		µg/L	1	9/2/2006 5:51:00 AM
Methylene Chloride	< 5.0	5.0		µg/L	1	9/2/2006 5:51:00 AM
Styrene	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
Tetrachloroethene	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
Toluene	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
trans-1,2-Dichloroethene	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
trans-1,3-Dichloropropene	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
trans-1,4-Dichloro-2-butene	< 2.0	2.0		µg/L	1	9/2/2006 5:51:00 AM
Tribromomethane	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
Trichloroethene	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
Trichlorofluoromethane	< 5.0	5.0		µg/L	1	9/2/2006 5:51:00 AM
Trichloromethane	5.7	1.0		µg/L	1	9/2/2006 5:51:00 AM
Vinyl Acetate	< 1.0	1.0		µg/L	1	9/2/2006 5:51:00 AM
Vinyl Chloride	< 2.0	2.0		µg/L	1	9/2/2006 5:51:00 AM
Total Xylene	4.8	3.0		µg/L	1	9/2/2006 5:51:00 AM
Surr: 1,2-Dichloroethane-d4	113	70-130		%REC	1	9/2/2006 5:51:00 AM
Surr: 4-Bromofluorobenzene	110	70-130		%REC	1	9/2/2006 5:51:00 AM
Surr: Dibromofluoromethane	105	70-130		%REC	1	9/2/2006 5:51:00 AM
Surr: Toluene-d8	99.9	70-130		%REC	1	9/2/2006 5:51:00 AM
INDICATOR ORGANIC PARAMETERS				SM 18 5310-C		Analyst: JDN
Total Organic Carbon	304	0.5		mg/L	100	9/8/2006 5:31:00 PM



AUG-13-2007 13:35 FROM: GLENS LANDFILL

231-228-5991

TO: 2312584470

Page H-8
May 2008

GEOCHEMICAL TESTING

Environmental and Energy Analysis

2005 N Center Ave
Somerset PA 15501

814/443-1871
814/443-6666
FAX: 814/445-6729

Monday, June 25, 2007

DEBORA JOHNSTON
GLEN'S SANITARY LANDFILL INC
WASTE MANAGEMENT OF N MICHIGAN
518 E TRAVERSE HIG
MAPLE CITY, MI 49664

TEL:
FAX

RE: Glen's Sanitary Landfill 500A

Order No.: G0705558

Dear DEBORA JOHNSTON:

Geochemical Testing received 1 sample(s) on 5/23/2007 for the analyses presented in the following report.

There were no problems with the analyses and all QC data met NELAC, EPA, and laboratory specifications except where noted in the Case Narrative.

If you have any questions regarding these tests results, please feel free to call.

Sincerely,

David M. Glessner
Laboratory Manager

Susan K. Gerhard
Project Manager

Report(s) To:
DON CONWAY



Geochemical Testing

Date: 25-Jun-07

CLIENT: GLEN'S SANITARY LANDFILL INC
Project: Glen's Sanitary Landfill 500A
Lab Order: G0705558

CASE NARRATIVE

No problems were encountered during analysis of this work order number, except as noted.

Field parameter data was measured or analyzed by the sampler. The Chain-of-Custody or ancillary forms that record results provided by the sampler are enclosed with the Analytical Reports.

2-Methynaphthalene by Method 8260 is qualified with a "J" on all samples reported in this Lab Order, which signifies that there is increased uncertainty and that all results are estimates. The laboratory was unable to calibrate for this semi volatile compound at the Michigan Target Detection Limit of 5 ug/L. This compound's poor purging efficiency is the suspected cause and the reason that this compound is not specified in Method 8260.

Qualifiers: ND - Not Detected at the Reporting Limit
J - Indicates an estimated value.
U - The analyte was not detected at or above the listed concentration, which is below the laboratory quantitation limit.
B - Analyte detected in the associated Method Blank

S - Spike Recovery outside accepted recovery limits
R - RPD outside accepted recovery limits
E - Value above quantitation range
• - Value exceeds Action Limit
H - Method Hold Time Exceeded



Laboratory Results

Date: 23-Jun-07

Geochemical Testing

CLIENT: GLEN'S SANITARY LANDFILL INC
 Lab Order: G0705558
 Project: Glen's Sanitary Landfill 500A
 Lab ID: G0705558-001
 Matrix: LEACHATE

Client Sample ID: Tank B

Sampled By: Gosling Czubak, Inc.
 Collection Date: 5/22/2007 3:00:00 PM
 Received Date: 5/23/2007

Analytes	Result	Limit	Qual	Units	DF	Date Analyzed
FIELD PARAMETERS						
		FIELD				Analyst:
pH (Field)	6.37			S.U.	0	5/22/2007 3:00:00 PM
Specific Conductance (Field)	7470			umhos/cm	0	5/22/2007 3:00:00 PM
Temperature (Field)	18.6			deg C	0	5/22/2007 3:00:00 PM
INORGANIC NON-METALS						
Alkalinity to pH 4.5	2530	SM 2320B				Analyst: KMR
		5		mg/L CaCO3	1	5/24/2007 2:47:00 PM
INORGANIC NON METALS						
Bicarbonate	2480	SM 4500-CO2D				Analyst: KMR
		5		mg/L CaCO3	1	5/24/2007
TOTAL CYANIDE						
Cyanide, total	< 0.020	SM 4500-CN&E				Analyst: SLY
		0.020		mg/L	1	6/30/2007
INORGANIC NON-METALS						
Carbonate	44	SM 4500-CO2				Analyst: KMR
		5		mg/L CaCO3	1	5/24/2007
INDICATOR ORGANIC PARAMETERS						
Chemical Oxygen Demand	< 10	HACH 8000				Analyst: SAG
		10		mg/L	1	5/23/2007
INORGANIC NON-METALS						
Nitrate Nitrogen	0.02	EPA 300.0				Analyst: AND
		0.02	U	mg/L as N	1	5/23/2007 5:31:00 PM
Nitrite Nitrogen	0.02	0.02	U	mg/L as N	1	5/23/2007 5:31:00 PM
INORGANIC NON-METALS						
Chloride	1110	EPA 300.0				Analyst: AND
		1		mg/L	1	5/23/2007 5:31:00 PM
Sulfate	18	2		mg/L	1	5/23/2007 5:31:00 PM
INORGANIC NON-METALS						
Ammonia Nitrogen	370	EPA 350.1				Analyst: JPL
		0.04		mg/L as N	100	5/23/2007 11:38:35 PM
INDICATOR ORGANIC PARAMETERS						
Phenolics	< 50.0	EPA 420.1				Analyst: MNR
		50.0		ug/L	5	5/24/2007 10:10:00 AM
INORGANIC NON-METALS						
Total dissolved solids	3320	SM 2540 C				Analyst: KLS
		50		mg/L	5	5/23/2007 10:03:00 AM
INORGANIC NON METALS						
Total Inorganic Nitrogen	370	CALCULATED				Analyst: SKG
		0.04		mg/L as N	1	5/23/2007
INORGANIC METALS						
Barium	0.049	EPA 200.7				Analyst: GNG
		0.005		mg/L	1	5/25/2007 6:28:00 PM
Cobalt	0.015	0.015		mg/L	1	5/25/2007 6:28:00 PM
Iron	1.5	0.02		mg/L	1	5/25/2007 6:28:00 PM
Magnesium	62	1.0		mg/L	1	5/25/2007 6:28:00 PM
Manganese	0.083	0.005		mg/L	1	5/25/2007 6:28:00 PM
Potassium	300	0.2		mg/L	1	5/25/2007 6:28:00 PM



Laboratory Results

Date: 25-Jun-07

Geochemical Testing

CLIENT: GLEN'S SANITARY LANDFILL INC
 Lab Order: G0705558
 Project: Glen's Sanitary Landfill 500A
 Lab ID: G0705558-001
 Matrix: LEACHATE

Client Sample ID: Tank B

Sampled By: Gosling Czubak, Inc.
 Collection Date: 5/22/2007 3:00:00 PM
 Received Date: 5/23/2007

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
INORGANIC METALS						
		EPA 200.7				Analyst: GMB
Sodium	939	1		mg/L	10	5/29/2007 3:18:00 PM
Vanadium	0.022	0.002		mg/L	1	5/29/2007 6:28:00 PM
Zinc	0.03	0.01		mg/L	1	5/29/2007 6:28:00 PM
INORGANIC METALS						
		EPA 200.8				Analyst: NPT
Antimony	2	1		µg/L	1	5/29/2007 4:31:00 PM
Arsenic	12	1		µg/L	1	5/29/2007 4:31:00 PM
Beryllium	< 1	1		µg/L	1	5/30/2007 1:34:00 PM
Cadmium	< 0.2	0.2		µg/L	1	5/29/2007 4:31:00 PM
Chromium	32	1		µg/L	1	5/29/2007 4:31:00 PM
Copper	13	1		µg/L	1	5/29/2007 4:31:00 PM
Lead	1	1		µg/L	1	5/29/2007 4:31:00 PM
Nickel	57	2		µg/L	1	5/29/2007 4:31:00 PM
Selenium	8	1		µg/L	1	5/29/2007 4:31:00 PM
Silver	0.2	0.2	U	µg/L	1	5/30/2007 1:34:00 PM
Thallium	< 2	2		µg/L	1	5/29/2007 4:31:00 PM
VOLATILE ORGANIC COMPOUNDS						
		EPA 8260				Analyst: JAW
1,1,1,2-Tetrachloroethane	< 1.0	1.0		µg/L	1	5/29/2007 2:24:00 AM
1,1,1-Trichloroethane	< 1.0	1.0		µg/L	1	5/29/2007 2:24:00 AM
1,1,2,2-Tetrachloroethane	< 1.0	1.0		µg/L	1	5/29/2007 2:24:00 AM
1,1,2-Trichloroethane	< 1.0	1.0		µg/L	1	5/29/2007 2:24:00 AM
1,1-Dichloroethane	< 1.0	1.0		µg/L	1	5/29/2007 2:24:00 AM
1,1-Dichloroethene	< 1.0	1.0		µg/L	1	5/29/2007 2:24:00 AM
1,2,3-Trichloropropane	< 1.0	1.0		µg/L	1	5/29/2007 2:24:00 AM
1,2,4-Trichlorobenzene	< 5.0	5.0		µg/L	1	5/29/2007 2:24:00 AM
1,2,4-Trimethylbenzene	< 1.0	1.0		µg/L	1	5/29/2007 2:24:00 AM
1,2-Dibromo-3-chloropropane	< 5.0	5.0		µg/L	1	5/29/2007 2:24:00 AM
1,2-Dibromoethane	< 1.0	1.0		µg/L	1	5/29/2007 2:24:00 AM
1,2-Dichlorobenzene	< 1.0	1.0		µg/L	1	5/29/2007 2:24:00 AM
1,2-Dichloroethane	< 1.0	1.0		µg/L	1	5/29/2007 2:24:00 AM
1,2-Dichloropropane	< 1.0	1.0		µg/L	1	5/29/2007 2:24:00 AM
1,3,5-Trimethylbenzene	< 1.0	1.0		µg/L	1	5/29/2007 2:24:00 AM
1,3-Dichlorobenzene	< 1.0	1.0		µg/L	1	5/29/2007 2:24:00 AM
1,4-Dichlorobenzene	< 1.0	1.0		µg/L	1	5/29/2007 2:24:00 AM
2-Hexanone	< 5.0	5.0		µg/L	1	5/29/2007 2:24:00 AM
2-Methylnaphthalene	< 5.0	5.0		µg/L	1	5/29/2007 2:24:00 AM
4-Methyl-2-Pentanone	24.5	5.0		µg/L	1	5/29/2007 2:24:00 AM
Acetone	< 20.0	20.0		µg/L	1	5/29/2007 2:24:00 AM
Acrylonitrile	< 5.0	5.0		µg/L	1	5/29/2007 2:24:00 AM
Benzene	< 1.0	1.0		µg/L	1	5/29/2007 2:24:00 AM



AUG-13-2007 13:36 FROM: GLENS LANDFILL

231-228-5991

TD:2312584470

Page H-12
May 2008

Laboratory Results

Geochemical Testing

Date: 25-Jun-07

CLIENT: GLEN'S SANITARY LANDFILL INC

Client Sample ID: Tank B

Lab Order: G0705558

Project: Glen's Sanitary Landfill 500A

Sampled By: Gosling Czabak, Inc.

Lab ID: G0705558-001

Collection Date: 5/22/2007 3:00:00 PM

Matrix: LEACHATE

Received Date: 5/23/2007

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
VOLATILE ORGANIC COMPOUNDS				EPA 8260		Analyst: JAW
Bromochloromethane	< 1.0	1.0		µg/L	1	5/28/2007 2:24:00 AM
Bromomethane	< 5.0	5.0		µg/L	1	5/28/2007 2:24:00 AM
Carbon Disulfide	< 1.0	1.0		µg/L	1	5/28/2007 2:24:00 AM
Carbon Tetrachloride	< 1.0	1.0		µg/L	1	5/28/2007 2:24:00 AM
Chlorobenzene	< 1.0	1.0		µg/L	1	5/28/2007 2:24:00 AM
Chlorodibromomethane	< 1.0	1.0		µg/L	1	5/28/2007 2:24:00 AM
Chloroethane	< 5.0	5.0		µg/L	1	5/28/2007 2:24:00 AM
Chloromethane	< 5.0	5.0		µg/L	1	5/28/2007 2:24:00 AM
cis-1,2-Dichloroethene	< 1.0	1.0		µg/L	1	5/28/2007 2:24:00 AM
cis-1,3-Dichloropropene	< 1.0	1.0		µg/L	1	5/28/2007 2:24:00 AM
Dibromomethane	< 1.0	1.0		µg/L	1	5/28/2007 2:24:00 AM
Dichlorobromomethane	< 1.0	1.0		µg/L	1	5/28/2007 2:24:00 AM
Dichlorodifluoromethane	< 5.0	5.0		µg/L	1	5/28/2007 2:24:00 AM
Diethyl Ether	12.9	10		µg/L	1	5/28/2007 2:24:00 AM
Ethylbenzene	< 1.0	1.0		µg/L	1	5/28/2007 2:24:00 AM
Hexachloroethane	< 5.0	5.0		µg/L	1	5/28/2007 2:24:00 AM
Iodomethane	< 1.0	1.0		µg/L	1	5/28/2007 2:24:00 AM
Isopropylbenzene	< 5.0	5.0		µg/L	1	5/28/2007 2:24:00 AM
Methyl Ethyl Ketone	17.1	5.0		µg/L	1	5/28/2007 2:24:00 AM
Methylene Chloride	< 5.0	5.0		µg/L	1	5/28/2007 2:24:00 AM
Methyl-tert-butyl ether	< 5.0	5.0		µg/L	1	5/28/2007 2:24:00 AM
Naphthalene	< 5.0	5.0		µg/L	1	5/28/2007 2:24:00 AM
n-Propylbenzene	< 1.0	1.0		µg/L	1	5/28/2007 2:24:00 AM
Styrene	< 1.0	1.0		µg/L	1	5/28/2007 2:24:00 AM
Tetrachloroethene	< 1.0	1.0		µg/L	1	5/28/2007 2:24:00 AM
Toluene	< 1.0	1.0		µg/L	1	5/28/2007 2:24:00 AM
trans-1,2-Dichloroethene	< 1.0	1.0		µg/L	1	5/28/2007 2:24:00 AM
trans-1,3-Dichloropropene	< 1.0	1.0		µg/L	1	5/28/2007 2:24:00 AM
trans-1,4-Dichloro-2-butene	< 5.0	5.0		µg/L	1	5/28/2007 2:24:00 AM
Tribromomethane	< 1.0	1.0		µg/L	1	5/28/2007 2:24:00 AM
Trichloroethene	< 1.0	1.0		µg/L	1	5/28/2007 2:24:00 AM
Trichlorofluoromethane	< 1.0	1.0		µg/L	1	5/28/2007 2:24:00 AM
Trichloromethane	< 1.0	1.0		µg/L	1	5/28/2007 2:24:00 AM
Vinyl Chloride	< 1.0	1.0		µg/L	1	5/28/2007 2:24:00 AM
Total Xylene	< 2.0	2.0		µg/L	1	5/28/2007 2:24:00 AM
Surr: 1,2-Dichloroethene-d4	112	70-130		%REC	1	5/28/2007 2:24:00 AM
Surr: 4-Bromofluorobenzene	100	70-130		%REC	1	5/28/2007 2:24:00 AM
Surr: Dibromofluoromethane	108	70-130		%REC	1	5/28/2007 2:24:00 AM
Surr: Toluene-d8	101	70-130		%REC	1	5/28/2007 2:24:00 AM

INDICATOR ORGANIC PARAMETERS

SM 18 6310-C

Analyst: JDM



AUG-13-2007 13:36 FROM: GLENS LANDFILL

231-228-5991

TO: 2312584470

Page H-13
May 2008

Laboratory Results

Geochemical Testing

Date: 25-Jun-07

CLIENT: GLEN'S SANITARY LANDFILL INC

Client Sample ID: Tank B

Lab Order: G0705558

Project: Glen's Sanitary Landfill 500A

Sampled By: Gosling Czabak, Inc.

Lab ID: G0705558-001

Collection Date: 5/22/2007 3:00:00 PM

Matrix: LEACHATE

Received Date: 5/23/2007

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
INDICATOR ORGANIC PARAMETERS		8M 19 6310-C				Analyst: JDH
Total Organic Carbon	223	50.0		mg/L	100	5/30/2007 8:07:00 PM

ATTACHMENT I
FORMATION TESTING

An injection test of the Weber #4-8 on November 9, 1982 showed the well was capable of accepting at least 42 GPM (61 BPH) on vacuum.

Present injection rates are 1000 bbl to 3000 bbl per day with no surface pressure. Since it is expected that the combined waste fluids will be injected at zero surface pressure and no injection pumps are planned, no fracture determination tests are planned.

The calculated maximum pressure gradient at the bottom of the 5 1/2" casing was calculated as follows:

5 1/2" casing seat = 1791'
Max. S.G. of Inj. Fluid = 1.07

Max. Pressure At Casing seat:
 $1791 \times .433 \times 1.07 = 829.7 \text{ PSI}$

Max. Pressure Gradient at Casing seat:
 $829.7 / 1791 = 0.463 \text{ PSI/Ft.}$

$0.8 - [0.433(1.35)] 1750 - 14.7$ 27 This is based on what?

$[0.8 - (0.433(1.256))] 1791 - 14.7$

1.3

~~14.7~~ psi.g

362.34

$[0.8 - (0.433(1.35))] 1750 - 14.7$

ATTACHMENT J
WELL STIMULATION

To remove fines introduced during the drilling operation and to clean up the injection interval, the Weber #4-8 was treated with acid on November 07, 1982. Approximately 1000 gallons of 28% Hydrochloric acid was distributed across the Traverse Limestone injection interval. The interval treated was between 1791 and 2200 feet.

Occasional stimulations with Hydrochloric acid are anticipated through out the life of the well. Treatment will more than likely be approximately 1000 gallons of 28% Hydrochloric acid.

ATTACHMENT K
INJECTION PROCEDURES

The surface facility will consist of a concrete unloading ramp, piping header, storage tanks, basket strainer, well annulus pressure maintenance system, security fence and containment dikes. Brine water and leachate will be off loaded from the trucks into one of the storage tank and then gravity fed to the disposal well. (See Figure K-1)

Description of surface facility:

Unloading Ramp:

Concrete Pad- Approx. 20' by 80' with 6" containment curb

Storage Tanks:

6 to 8 - 400 BBL (16,800 Gal.) steel storage tanks

Filtration/Treatment:

Basket strainer - No other treatment or filtration is planned

Pumps:

None - Well takes fluid on a vacuum

Well annulus pressure maintenance system: (See Figure K-2)

Pressurized tank with pressure relief valve

Nitrogen supply

Necessary piping, valves and pressure regulator

Instrumentation:

Pressure/vacuum gauge on injection line

Pressure gauge on annulus system

Flow measuring device on injection line

Sight glass on pressurized annulus tank

Pollution Control:

Concrete Pad with curb for truck unloading

Containment dike around storage tanks

800 gal. concrete collection sump W/ pump

Safety/Security

6' high chain link fence w/ 3 strands barbed wire

Pole mounted light

Figure K-1
PLAN OF SURFACE FACILITIES
Weber #4-8





Figure K-2
PROPOSED ANNULUS
PRESSURE MAINTENANCE SYSTEM



ATTACHMENT L
CONSTRUCTION PROCEDURES

The Weber #4-8 was originally drilled as a saltwater disposal well in November 1982. After drilling a 12 1/4" hole, 8 5/8" casing was set at 911 feet. The casing was cemented to surface with 450 sacks of cement. A 7 7/8" hole was then drilled to the total depth of 2200' and 5 1/2" casing set at 1791'. The 5 1/2" casing was cemented to surface with 305 sacks of cement. Salt water was circulated to clean out the well, and a packer run on 2 7/8" tubing and set at 1750'. Bear Lake Disposal operated the well until it was acquired by Team Completions.

A copy of the original drilling and completion report is on pages L-2 and L-3. Page L-4 is a copy of Michigan's Form 7210, "Log of Oil, Gas, Disposal or Storage Well" dated November 9, 1982. Page L-5 contains the Formation Record prepared by Geologists Warren A. Baumann and Jim Sanborn.

Weber #4-8 - ORIGINAL DRILLING REPORT

Well Name: WEBER #4-8 SWD
Permit No: 36221
Mayfield Township, Grand Traverse County
Surf LOG: Sec. 8, T25N-R11W, SW NE NE, 1115'FNL & 1209'FEL
Spudded: 1:30 AM., 11-03-82
Completion: 11-08-82
DTD: 2200'TD. (no logs run)
Elevations: KB 1120.6' RF 1119.1' GL 1105.1'
Contractor: Reef Drilling Corporation, Rig #1
Status: SI (11-09-82)

Casing: 8 5/8" csg @ 911' w/450 sxs cmt.
5 1/2" csg @ 1791' w/305 sxs cmt.

Logs Run: None
Dev Surveys: 3/4° @ 2200'

11-02-82 Status - MI & RU. Cellar - 5'

11-03-82 Depth - 400', status - wo water, footage cut - 400',
rate - 1/2 mpf, wt - 9.1, vis - 55, run no - 1, size-make - 12
1/4" HTC, OSC3AJ, wob - 35 to 40,000 lbs, rs - 90 rpms, pp - 400
psi. Started losing fluid @ 200'±.

11-04-82 Depth - 1100', status - drlg, footage cut - 700', rate
- 1 1/2 mpf, wt - 8.5, vis - 31, run no - 1, size-make - 12 1/4"
HTC, OSC3AJ, wob - 45,000 lbs, rs - 90 rpms, pp - 600 psi, Run
no - 2 RR, size-make - 7 7/8" Reed TC, FP21J, wob - 25,000 lbs,
rs - 90 rpms, pp - 700 psi. Casing Detail: Ran 22 jts of 8
5/8", 24# used csg totaling 918.72'. Set shoe @ 911'. Dowell
cmt'd w/250 sxs Filler, 50-50 poz, 6% gel, 3% CaCl2 followed by
200 sxs Class A w/3% CaCl2. Displaced w/54 bbls fr wa. SI @
6:00 PM., 11-03-82. Circ'd 40 bbls of cmt to surf. Recip'd
pipe while cementing. Sample Tops BOD - 791'.

11-05-82 Depth - 2000', status - drlg w/bit #3, footage cut -
900', rate - 1 mpf, wt - 8.8, vis - 30, run no - 2 RR, size-
make - 7 7/8" RTC, FP21J, wob - 25,000 lbs, rs - 70 rpms, pp -
700 psi, Run no - 3 RR, size-make - 7 7/8" STC, F-4, wob -
40,000 lbs, rs - 70 rpms, pp - 1000 psi.

11-06-82 Depth - 2200'TD., status - circ @ TD w/salt water,
footage cut - 200', wt - 8.8, vis - 30, dev - 3/4° @ 2200', run
no - 3 RR, size-make - 7 7/8" STC, F-4, wob - 40,000 lbs, rs -

70 rpms, pp - 1000 psi. Csg Detail: Ran 42 jts of 5 1/2", 15.5#, used K-55, ST&C csg totaling 1794.68'. Set Howco pkr shoe @ 1791'. Howco cmt'd w/130 sxs 50-50 poz, 6% gel, 3% CaCl2 followed by 175 sxs Class A w/3% CaCl2. Displaced w/43 BFW. Bumped plug w/1000 psi. Float held OK. CIP @ 9:00 PM., 11-05-82. Circ'd 2 bbls cmt to surf.

11-07-82 Depth - 2200' TD. Status - WO location. Circ'd hole w/10.8 ppg salt water. TIH w/pkr on 55 jts of used 2 7/8" tbg. Set pkr @ 1750' (pkr type - 5 1/2" X 2 3/8" Shure Set tension), w/18,000# over string wt. NU 2 7/8" tbg head. Tested csg/tbg annulus to 300 psi, held OK. Established injection rate. Pumped 10.8 ppg salt water @ rates of 1 1/2 to 5 BPM w/pressures of 300 to 1200 psi prior to acidizing. RU Howco & treated open hole from 1791' - 2200* w/1000 gals 28% HCl acid. Flushed w/35 bbls 10.8 ppg brine @ 3.5 bpm + 500 - 800 psi. Max/Min rate = 1.75/1.5 bpm. Max/Min press = 1000/700 psi. ISIP = vacuum. Had 300 psi break @ 1 3/4 bpm when acid hit formation. After acid job, formation took 10.8 brine on a vacuum, estimated rate @ 2 BPM±. Put reserve pit of 8.8 ppg brine away @ 3 1/2 bpm w/200 psi. Went on a vacuum when done. Did not pump all of reserve pit, just water from top. Released rig @ 11:00 PM. 11-06-82.

11-08-82 HU temporary 2 7/8" surface line from the Weber #3-8C brine load out to disposal well. Started injection test at 12:30 PM. Rates on vacuum as follows:

HOUR	BBLS	BPH	REMARKS
0			
.25	10	40	
.50	23	92	
.75	17	68	
1.00	20	80	
1.25	15	60	
1.75	35	70	
2.00	9	36	
			Switched Tanks
3.25	95	76	Added 13 BW (producing tank)
4.50	50	40	Added 13 BW (producing tank)

SI test @ 4:30 Pm. In 4 1/2 hrs, injected a total of 24 bbls of 10.8 ppg brine on a vacuum. Avg rate for test = 61 bph.

MICHIGAN FORM 7210 DATED 11-09-82

STATE OF MICHIGAN DEPARTMENT OF NATURAL RESOURCES LOG OF OIL, GAS, DISPOSAL OR STORAGE WELL (ACT 61) Submit in DUPLICATE Within 30 Days after Well Completion				PERMIT NUMBER <div style="border: 1px solid black; padding: 2px; text-align: center;">36221</div>	
				DEEPENING PERMIT NUMBER <div style="border: 1px solid black; padding: 2px; text-align: center;"> </div>	
NAME(S) & ADDRESS OF OWNER(S) SHOWN ON PERMIT Reef Petroleum Corporation P.O. Box 148 Traverse City, MI 49685-0148			NAME & ADDRESS OF DRILLING CONTRACTOR(S) Reef Drilling Corporation P.O. Box 552 Mt. Pleasant, MI 48858		
LEASE NAME(S) & WELL NUMBER SHOWN ON PERMIT Weber #4-8					DIRECTIONALLY DRILLED YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>
SURFACE LOCATION SW NE NE		SECTION 8	TOWNSHIP 25N	RANGE 11W	TOWNSHIP NAME Mayfield
FOOTAGES (North/South) 1115 Ft. from North Line and 1209 Ft. from East Line of quarter section		COUNTY NAME Grand Traverse			
SUBSURFACE LOCATION SECTION TOWNSHIP RANGE		COUNTY NAME			
FOOTAGES (North/South) Ft. from Line and Ft. from Line of quarter section		COUNTY NAME			
DATE	DRILLING BEGUN 11-03-82		TOTAL DEPTH OF WELL Driller 2200' Log -		TYPE WELL Brine Disposal
	DRILLING COMPLETED 11-06-82		FORMATION AT T.D. Traverse Lime		ELEVATIONS K.B. 1120.6' R.F. 1119.1'
	WELL COMPLETED 11-08-82		PRODUCING FORMATION(S) Traverse Lime		FT. DRILD. - ROTARY TOOLS From Surf. To 2200'
			FT. DRILD. - CABLE TOOLS From - To -		R.T. Grd. 1105.1'

CASING, CASING LINERS AND CEMENTING

PERFORATIONS

SIZE	WHERE SET	CEMENT	Ft. Pulled	DATE	NUMBER HOLES	INTERVAL PERFORATED	OPEN	
							YES	NO
8 5/8"	911'	450 sxs #	None					
5 1/2"	1791'	305 sxs #	None					

GROSS PAY INTERVALS

ALL OTHER OIL AND GAS SHOWS OBSERVED OR LOGGED

FORMATION	OIL OR GAS	FROM	TO	FORMATION	OIL OR GAS	DEPTH	WHERE OBSERVED (X)					
							Sam- ples	Odor	Pits	Mud Line	Gas Log	Fill Up
None				None								

STIMULATION BY ACID OR FRACTURING

WATER FILL UP (F.U.) OR LOST CIRCULATION (L.C.) (X)

DATE	Interval Treated	Materials and amount used	FORMATION	F.U.	L.C.	DEPTH	AMOUNT
11-07-82	1791' - 2200'	1000 gals 28% HCl	None				

MECHANICAL LOGS, LIST EACH TYPE RUN

DEPTH CORRECTION DEVIATION SURVEY PLUGGED BACK

Brand	(X)	LOG TYPES	LOGGED INTERVALS	DEPTH	CORRECT'N	RUN AT	DEGREES	YES	NO	DEPTH
Schlumberger		None				2200'	3/4°			
Birdwell										

PRODUCTION TEST DATA

OIL - Bbls/day	GRAVITY - °API	COND. Bbls/day	GAS - MCF/day	WATER - Bbls/day	H ₂ S - Grains/100 cu. ft.	B.H.P. AND DEPTH
			61 BPH on vacuum			

I AM RESPONSIBLE FOR THIS REPORT. THE INFORMATION IS COMPLETE AND CORRECT.

DATE 11-09-82	NAME AND TITLE (PRINT) Ronald R. Suckle, Vice President-Operations	SIGNATURE <i>Ronald R. Suckle</i>
------------------	---	--------------------------------------

NOTICE REPORT COMPLETE SAMPLE AND FORMATION RECORD AND DRILL STEM TEST INFORMATION ON REVERSE SIDE

R - 7210
Rev. 3/77

FORMATION RECORD

Permit No. 36221

EVALUATION USED: 1120.6'K.B.		GEOLOGIST NAME: Warren A. Baumann/Jim Sanborn		TDPS TAKEN FROM: <input type="checkbox"/> DRILLERS LOG <input checked="" type="checkbox"/> SAMPLE LOG <input type="checkbox"/> ELECTRIC LOG	
---------------------------------	--	--	--	--	--

FROM	TO	FORMATION (TYPE, COLOR, HARDNESS)	FROM	TO	FORMATION (TYPE, COLOR, HARDNESS)
NOTE: IF WELL DIRECTIONALLY DRILLED, ADD TRUE VERTICAL DEPTH FORMATION TOPS WHERE APPROPRIATE.					
DRIPT					
0	781	Sand & gravel. Sm redish shales.			
COLDWATER					
781	1506	781 (+ 340) Sh, lt-med gry's, frm, sub rnd, sil calc, pyr.			
ANTRIM					
1506	1750	1506 (- 385) Shale, blk to dk brn, frm-britt, sub rnd v. grainy text, fnt yel glo flor.			
TRAV FORM					
1750	1816	1750 (- 629) Sh, lt gry's frm, sub rnd. Sm dolic, brn stringers, v. calc. pyr.			
TRAV LIME					
1816	1870	1816 (- 695) Ls, lt tan to buff, fxln, mhd, gd, intrxln & micro pore ϕ , no vis, stn, cln.			
1870	2100	Ls, lt-med brns, vfxln, hd dns arg, sm gy shale, stringers. Trs, suc ϕ cln, abnt fos.			
2100	2200	Ls, med gy brn to crmy tans, vfxln, hd dns, arg, sm gd micro, por ϕ intrvl from 2100 - 50. No stn - fos.			
DTD - 2200'					
IF WELL WAS CORED, ATTACH CORE DESCRIPTION					
DRILL STEM TEST DATA					

ATTACHMENT M


CONSTRUCTION DETAILS

Weber #4-8 -WELL CONSTRUCTION SUMMARY

The Weber #4-8 was drilled by Reef Petroleum Corporation in 1982.

- a. Location: Sec. 8, T25N, R11W, Mayfield Township, Grand Traverse County, MI
- b. Drilling Began: Nov. 03, 1982
- c. Well Completed: Nov. 8, 1982
- d. Total Depth: 2200' K.B. (15' above ground level)
- e. Formation at T.D.: Traverse Limestone
- f. Type completion - open hole
- g. Surface Casing*
8 5/8", 24.0 pound per foot casing set in 12 1/4" hole at 911' K.B. and cemented with 250 sacks of 50-50 pozmix containing 6% gel and 3% CaCl₂ and 200 sacks of Class A cement containing 3% CaCl₂. Circulated 40 barrels of cement to surface.
- h. Protection Casing
5 1/2", 15.5 pound per foot casing set in 7 7/8" hole at 1791' K.B. Cemented with 130 sacks of 50-50 pozmix, containing 6% gel and 3% CaCl₂ and 175 sacks of Class A cement containing 3% CaCl₂. displaced with 43 ~bls/ water. Circulated 2 barrels of cement to surface.
- i. Tubing
2 7/8" O.D., 6.5 pound per foot, carbon steel tubing
- j. Packer
Shure Set tension packer set at 1750' K.B.
- k. Annular Fluid
Water with corrosion inhibitor.

Figure M-1



RESOURCES SERVICES USA
Houston, Texas

TEAM COMPLETIONS
KALKASKA, MICHIGAN

WEBER 4-8

Scale: None


Date 12/01/07

B & B Oilfield Equipment Corp.

WELLHEAD SPECIALISTS

W. H. HAROLD BANKS
PRESIDENT
BUSINESS PH. (517) 773 8403

BOX 492
4741 EAST PICKARD
MT PLEASANT, MI 48858
HCS PH. (517) 828 6786



ATTACHMENT O
PLANS FOR WELL FAILURE

If Well #4-8 fails or is not usable, the well will be shut down until the condition is corrected. Any aqueous waste on site at the time of the failure will be held until the condition is corrected or will be hauled to a suitable offsite commercial treatment and disposal facility.

ATTACHMENT P
MONITORING PROGRAM

Continuously monitor pressure on the injection tubing.

Continuously monitor pressure between the tubing and the long string of casing.

Continuously monitor flow rate. The total volume of fluid injected can be determined from this information.

Daily monitor the annulus tank fluid level.

Record amount & type of liquid that is added or removed from annulus system.

File monthly, quarterly and annual reports required by US Environmental Protection Agency and the Michigan Department of Environmental Quality.

ATTACHMENT Q
PLUGGING AND ABANDONMENT PLAN
FOR WELL WEBER 4-8

(Prepared January 2008)

1. Notify regulatory agencies at least 45 days prior to commencement of plugging operations.
2. Pressure test casing tubing annulus to approximately 500 PSI. Run Temperature log from surface to bottom of casing (1791') to demonstrate external mechanical integrity.
3. Record pressure decay for 24 hours or for a time period specified by USEPA Director.
4. Flush well with approximately 100 barrels of clean brine.
5. Move in rig, pump and tank. Install blow out preventer.
6. Release packer and remove injection tubing and packer.
7. Run casing inspection survey on 5 1/2" casing from +1791' to the surface.
8. Run and set cement retainer in 5 1/2" casing at +1771'. Pump 150 sacks of cement through retainer. Release workstring from retainer.
9. After allowing sufficient time for the cement to set, pressure test casing to 500 PSI.
10. Run work string to top of cement retainer (or top of cement). Use Balance Method to place cement from approximately 1771' to +900'.
11. After allowing cement to set, tag top of cement.
12. Run work string to top of the second cement plug (+900'). Use Balance Method to place cement from +900' to surface.
13. Remove BOP and wellhead equipment. Release equipment
14. Install a permanent marker on the well site.
15. Prepare a plugging report and a final well status drawing.

ATTACHMENT R
NECESSARY RESOURCES

ATTACHMENT T
EXISTING PERMITS

EXISTING PERMITS:

Michigan Permit # 36221.

USEPA Permit #MI-055-2D-C034

ATTACHMENT U
DESCRIPTION OF BUSINESS

Team Completions has been involved in the transportation and disposal of oilfield salt water at this facility since approval was granted to operate the Weber 4-8 on July 23, 2004. Team Completions is now making application to dispose of leachate water from the Glen's Sanitary Landfill in addition to the salt water presently being injected into the Weber #4-8.

All fluids to be injected are considered to be nonhazardous per RCRA regulations.



July 15, 2008

US – EPA
REGION 5
77 West Jackson Blvd
Chicago, IL 60604-3590

Re: **Michigan DEQ Application for Permit to Convert and Operate Well
Weber # 4-8 SWD, Class II, Type "D"
Permit # MI-055-2D-C034**

Dear US – EPA:

With reference to the above Application, a Conformance Bond in the amount of TWENTY-THOUSAND AND NO/100 (\$20,000) is currently held at Northwestern Bank located at 112 S. Cedar Street, Kalkaska, MI. The Certificate of Deposit No. is 059001578.

Upon acceptance of this Application, Team Completions, LLC, will increase the bond amount to \$30,000.

If you have any questions or need additional information, please do not hesitate to contact me at 231-384-0306.

Sincerely,

TEAM COMPLETIONS, LLC

A handwritten signature in black ink, appearing to read "Michael J. Goggin".

Michael J. Goggin
Controller, CPA

MG:mrf

*P.O. Box 1104
Kalkaska, MI. 49646
231-258-9130 Fax 231-258-8760*



APPLICATION FOR PERMIT TO:

☐ DRILL ☐ DEEPEN ☒ CONVERT
AND OPERATE A WELL

By authority of Part 615 or Part 625 of Act 451 PA 1994, as amended.
Non-submission and/or falsification of this information
may result in fines and/or imprisonment.

1a. Part 615 Supervisor of Wells
☐ Oil and Gas
☒ Brine Disposal
☐ Hydrocarbon Storage
☐ Injection for Secondary
Recovery

1b. Part 625 Mineral Wells
☒ Waste Disposal
☐ Brine Production
☐ Processed brine disposal
☐ Storage
☐ Test, fee sched. on rev.

1c. Fee enclosed
☒ Yes
☐ No, revision of
application
☐ No, leg of horz
drainhole

2. List all previous permit numbers
MI #36221, USEPA #MI-055-2D-C034

3. Fed. ID. No. (do not use SSN)
38-3578027

4. Conformance bond
☐ Blanket ☒ Single well

5. ☐ Attached
☐ On file

6. Bond number

7. Bond amount

8. Applicant (name of permittee as bonded)
Team Completions L.L.C.

9. Address
P.O. Box 1104
Kalkaska
MI
49646

Phone
231.258.9130
I authorize DEQ 4 additional days
to process this application.
☐ Yes ☐ No

10. Lease or well name (be as brief as possible)
Weber

Well number
4-8

11. Surface owner
Team Completions L.L.C.

12. Surface location

SW 1/4 of NE 1/4 of NE 1/4 of Sec 8 T 25N R 11W

Township
Mayfield

County
Grand Traverse

13. If directional, bottom hole location

1/4 of 1/4 of 1/4 of Sec T R

Township

County

14. The surface location for this well is

1115 feet from nearest (N/S) N section line AND 1209 feet from nearest (E/W) E section line

15. Is this a directional well? ☒ No ☐ Yes If yes, complete line 15. The bottom hole location for this well is
feet from nearest (N/S) section line AND feet from nearest (E/W) section line

16. The bottom hole location (whether straight or directional) of this well is
feet from nearest (N/S) drilling unit line AND feet from nearest (E/W) drilling unit line

17. Kind of tools
☒ Rotary ☐ Cable ☐ Combination

18. Is sour oil or gas expected?
☒ No ☐ Yes ☐ H₂S Cont. plan enclosed

19. Base of lowest known fresh water aquifer
Formation Glacial Drift Depth 781'

20. Intended total depth
MD 2200 TVD

21. Formation at total depth
Traverse Lime

22. Producing/injection formation(s)
Traverse

23. Objective pool, field, or project
Injection well

24. PROPOSED DRILLING, CASING AND CEMENTING AND SEALING PROGRAM

HOLE			CASING			CEMENT			MUD	
Depth (MD)	Geol. Formation	Bit Dia.	O.D. Size	Wt/Ft	Grade Condition	Depth (MD)	Sacks	T.O.C.	W.O.C.	Wt. Vis.
911'	Coldwater	12 1/4"	8 5/8"	24#	used	911'	450	surf.		8.6 31
2200'	Traverse	7 7/8"	5 1/2"	15.5#	K-55, used	1791	305	surf.		8.8 30

25. DETAIL CEMENTING PROGRAM. IDENTIFY ALL CEMENT CLASSES, ADDITIVES, AND VOLUMES (IN CU. FT.) FOR EACH CASING STRING.

Surface 250 sxs 50-50 poz w/ 6% gel. 3% CaCl₂ + 200 sxs. Class A w/ 3% CaCl₂ - Circ'd 40 bbls cmt. to surface
Intermediate

Production/Injection 130 sxs 50-50 poz w/ 6% gel. 3% CaCl₂ + 175 sxs. Class A w/ 3% CaCl₂ - Circ'd 2 bbls cmt. to surface

26. Send correspondence and permit to

Name Team Completions
Address PO Box 1104 KALKASKA MI 49646

E-mail timt@teamcompaniesllc.com
Phone 231-357 1016

CERTIFICATION "I state that I am authorized by said applicant. This application was prepared under my supervision and direction. The facts stated herein are true, accurate and complete to the best of my knowledge."

Enclose permit fee of \$300 for all Part 615 wells; \$2,500 for a Part 625 waste disposal well; or \$500 for a brine production, processed brine disposal, or storage well. Make checks payable to State of Michigan.

DEQ Cashier use only.

27. Application prepared by (print or type) DON TINKER Phone 231-357-1016

28. Signature Don Tinker Date 6-24-08

Office of Geological Survey Use Only

Permit number API number Date issued Owner number

Team Completions
Kalkaska, Michigan

Application for Converting Weber 4-8
From a Class II Type D Disposal Well to a
Class I and Class II Type D Disposal Well

Well Identification

Name of Applicant : Team Completions L.L.C.
Address : PO Box 1088
Kalkaska, Michigan 49646

Well Name and Number: Weber 4-8
SW, NE, NE Sec 8, T25N, R11W
Mayfield Township
Grand Traverse County, Michigan

The following information is included in this section:

- Project Description
- MDEQ Form 7200-1 (Application For Permit)
- MDEQ Form 7200-3 (Environmental Impact Assessment)
- MDEQ Form 7200-14 (Injection Well Data)
- Surveyed Plat of Well Location

PROJECT DESCRIPTION

General Description

This Application for Permit is for the purpose of adding leachate water from the Glen's Sanitary Landfill to the saltwater presently being injected into the Weber #4-8 Saltwater Disposal Well.

The Weber #4-8 was originally drilled in November of 1982 under Michigan Permit #36221. The well is presently operated as a commercial saltwater disposal well under USEPA Class II, Type "D" Permit #MI-055-2D-C034.

The location of the well and surface facility is shown on the surveyed plat at the end of this attachment.

Type Injectate

Sodium Chloride/Calcium Chloride brine water produced from the Niagaran is presently being injected into the Traverse and Traverse Lime formation between 1791 and 2200 feet. The brine has a specific gravity of from 1.02 to 1.07 (8.5 to 8.9 pounds/gallon).

It is proposed that in addition to the present brine water being injected that leachate from the Glen's Sanitary Landfill at Maple City, Michigan be injected. Typical analysis of the leachate is shown on page in Attachment "H"

The anticipated daily injection rates are between 29 and 146 gallons per minute (1000 bbl to 5000 bbl per day). It is expected that the combined waste fluids will be injected at zero surface pressure and no pumps will be required.

The injectate is classified as non-hazardous as defined by Rule 299.9203 of Act No. 64 Hazardous Waste Management Act, 1979 PA 64 as amended.

Surface & Mineral Ownership

The proposed well is located on private property owned by Team Completions L.L.C.

Public Lands Involved

No State or Federal minerals and/or land interests are part of this project.

NOTICE OF INTENT

Notice of intent to complete Weber 4-8 as a Class I disposal well will be advertised in local newspaper.

SURFACE DESCRIPTION

Surrounding Area

The surrounding area is primarily used for agriculture with some oil and gas industry activities. Residences are scattered along area roads. Miller Road is approximately 1100' to the North, Highway 37 is approximately 1200' to the East, Harrand Road is approximately 4200' to the South and Botts Road is approximately 1400' to the West of the Weber 4-8 well.

There are no major waterways, lakes or streams with 1320' of Weber 4-8.

Current Land Use

The current use of the area is for the disposal of saltwater into the Weber 4-8. Present surface facilities consist of an unloading ramp, storage tanks, security fence and containment dikes.

**ENVIRONMENTAL IMPACT ASSESSMENT FOR MINERAL WELLS AND SURFACE FACILITIES**

To be submitted with an application for a well permit pursuant to Part 625, 1994 PA 451, as amended (The Act) or prior to construction of associated surface facilities located more than 300 feet from the proposed well.

Check all boxes and fill in all blanks that apply to the proposed well(s) or proposed surface facility.

Submit a *Soil Erosion and Sedimentation Control Plan* (EQP 7200-18) for each drill site, surface facility and flowline identified in the EIA.

This EIA is for (check one)

- ☐ Well only. Complete Parts A, B, D, E, and F
☐ Surface facility only (to be constructed more than 300 feet from the well). Complete Parts A1, A2, C, D, E, and F
☒ Well and surface facility. Complete all Parts.

A. PROJECT DESCRIPTION**1. Applicant**

Team Completions L.L.C.

2. Well name and number

Weber 4-8

3. Well type

- ☐ Artificial brine production well
☐ Natural brine production well
☐ Test well greater than 250' deep or penetrating below deepest freshwater aquifer
☐ Blanket test well(s) Number of proposed wells ___ Anticipated maximum depth _____
☐ Processed brine disposal well
☐ Single-source, non-commercial, waste disposal well
☒ Multi-source commercial non-hazardous waste disposal well
☐ Multi-source commercial hazardous waste disposal well
☐ Storage well

4. ☐ Yes ☒ No Is this well a replacement for an existing well?

If Yes, list

Existing well name and number
Current owner
Existing well type and status
Existing well location
Reason for replacement
Disposition of existing well

5. ☐ Yes ☒ No Is this well a reentry of an existing well?

If Yes, list

Existing well name and number
Current owner
Existing well type and status
Reason for reentry

6. ☐ Yes ☒ No Is the well expected to encounter hydrogen sulfide (H₂S)?

If Yes, list formations expected to contain H₂S and anticipated depths to tops of formations

Well drilled and completed in 2002.

7. ☐ Yes ☒ No Is the well expected to encounter oil or gas?

If Yes, list formations expected to contain oil or gas and anticipated depths to tops of formations

8. ☐ Yes ☒ No Will the well be drilled from an existing drill pad?

If Yes, list well name, number, permit number and status of all existing wells on the drill pad (if no wells, write "none")

No well to be drilled. Permit application is to inject Class I fluid in existing Class II well.

Show proposed well and all existing wells on accompanying scale map identified as applying to Part A1 of the EIA.

B. DRILLSITE

1. Drill site access route dimensions _____ feet x _____ feet.

Provide a detailed description of topography, drainage, soil type(s), direction and percentage of slopes, land cover and present land use for the drill site access route. Show route on accompanying scale map labeled **Part B1**.

2. Drill site dimensions _____ feet x _____ feet.

Provide a detailed description of topography, drainage, soil types(s), direction and percentage of slopes, land cover and present land use for the drill site. Show well site on accompanying scale map labeled **Part B2**

NOTE: If any "Yes" box in items B3, B4, B5, B6, B7 or B8 is checked, the corresponding feature(s) must be identified on an accompanying scale map identified as applying to Part B of the EIA.

3. ☐ Yes ☐ No Are drain tiles present on the drill site?

If Yes, how they will be handled if they are encountered?

No drill site required. Permit application is to inject Class I fluid in existing Class II well.

4. Are any of the following located within 600 feet of the proposed wellhead?

- ☐ Yes ☒ No Buildings
☐ Yes ☒ No Domestic fresh water wells
☐ Yes ☒ No Public roads
☐ Yes ☒ No Railroads
☐ Yes ☒ No Power lines
☐ Yes ☒ No Pipelines
☒ Yes ☐ No Other man-made features (list individual features)

Only existing Team Completions' roads, electric power and facilities within 600' of well.

5. Are any of the following located within 800 feet of the proposed wellhead?

- ☐ Yes ☒ No Type IIB public water wells Type II is a non-community water supply with ≥ 15 service connections or ≥ 25 individuals for not less than 60 days per year.
☐ Yes ☒ No Type III public water wells Type III is a public water supply which is neither Type I nor type II.

6. Are any of the following located within 1320 feet of the proposed wellhead?

- ☐ Yes ☒ No Surface waters and other environmentally sensitive areas
☐ Yes ☒ No Floodplains associated with surface waters
☐ Yes ☒ No Wetlands, as identified by sections 30301 to 30323 of the Act.
☐ Yes ☒ No Natural rivers, as identified by sections 30501 to 30515 of the Act
☐ Yes ☒ No Threatened or endangered species as identified by sections 36501 to 36507 of the Act

7. Are any of the following located within 2000 feet of the proposed wellhead?

- ☐ Yes ☒ No Type I public water wells
 Type I is a community water supply with year-round service, ≥ 15 living units or ≥ 25 residents.
- ☐ Yes ☒ No Type IIA public water wells Type II is a non-community water supply with ≥ 15 service connections or ≥ 25 individuals for not less than 60 days per year.

8. ☐ Yes ☒ No Are Great Lakes shorelines located within 1500 feet of the proposed wellhead?**9. ☐ Yes ☐ No Will fresh water be used to drill this well?**

If Yes, will the water be supplied from

- ☐ A "permanent" water well, to be retained after final completion OR used for drinking water (to be drilled and installed pursuant to Part 127 of 1979 PA 368, as amended) **OR**
- ☐ A "temporary" water well, to be plugged upon final completion and not used for drinking water **OR**
- ☐ Another source (identify)

If No, identify the drilling fluid to be used.

10. Drilling fluid pit location and handling and disposal of drill cuttings, muds and fluids

Anticipated depth to groundwater _____ Depth determined by _____

Pit type

- ☐ On site in-ground pit. Anticipated dimensions: L ____ W ____ D ____

Show proposed pit location on accompanying scale map labeled **Part B10**.

- ☐ Remote in-ground pit. Anticipated dimensions: L ____ W ____ D ____

Attach approval of landowner and show remote pit location on accompanying scale map labeled **Part B10**.

- ☐ On-site steel tanks with no in-ground pits (complete 10a and 10d below, do not complete 10b and 10c)

a. ☐ Yes ☐ No Will the well be drilled into or through bedded salt deposits?

If Yes,

- ☐ Yes ☐ No Will the drill cuttings contain solid salt?

If Yes, describe plans for handling and disposing of drill cuttings.

b. ☐ Yes ☐ No Will the drilling fluid pit contents be solidified after drilling?

If Yes, identify the pit solidification contractor and pit solidification method.

c. ☐ Yes ☐ No Will the drilling fluid pit contents be removed after drilling?

If Yes, identify the site for disposal of the removed material.

d. ☐ Yes ☐ No Will any pit fluid be disposed by a licensed liquid waste hauler?

If Yes, identify the waste hauler.

If No, describe disposal plans for pit fluids.

Well drilled in 2002

C. SURFACE FACILITY

1. ☒ **Yes** ☐ **No** **Will the well have associated surface facilities?**

If No, Do not complete the remainder of Part C.

If Yes,

- ☒ **Yes** ☐ **No** **Does a surface facility currently exist?**

If Yes, show facility location relative to the wellhead on a scale map labeled Part C1. Do not complete the remainder of Part C.

If No,

- ☐ **Yes** ☐ **No** **Has a location for the surface facility been chosen?**

If Yes, complete Parts C2 through C10

If No, at least 60 days prior to beginning construction, submit an EIA for the Surface Facility (this form), a facility plan, and a Soil Erosion and Sedimentation Control Plan (EQP 7200-18) to the Office of Geological Survey District Supervisor.

2. ☐ **Yes** ☒ **No** **Is the proposed surface facility site more than 300 feet from the wellhead?**

If Yes, complete Parts C3 through C10 and submit a map showing the location of the surface facility site relative to the wellhead.

If No, do not complete the remainder of Part C.

3. **Dimensions of surface facility access road:** ___ feet x ___ feet.

Describe the topography, drainage, soil type(s), direction and percentage of slopes, land cover and present land use:

4. **Dimensions of surface facility site:** ___ feet x ___ feet.

Describe the topography, drainage, soil type(s), direction and percentage of slopes, land cover and present land use:

NOTE: If any "Yes" box in items C5, C6, C7, C8, C9, or C10 is checked, the corresponding feature(s) must be identified on an accompanying scale map identified as applying to the appropriate section of Part C of the EIA.

- ☐ **Yes** ☐ **No** **Are drain tiles present on the proposed surface facility site?**

If Yes, discuss how they will be handled if they are encountered?

6. **Are any of the following located within 600 feet of the proposed surface facility site?**

- | | | |
|------------------------------|-----------------------------|--|
| <input type="checkbox"/> Yes | <input type="checkbox"/> No | Buildings |
| <input type="checkbox"/> Yes | <input type="checkbox"/> No | Domestic fresh water wells |
| <input type="checkbox"/> Yes | <input type="checkbox"/> No | Public roads |
| <input type="checkbox"/> Yes | <input type="checkbox"/> No | Railroads |
| <input type="checkbox"/> Yes | <input type="checkbox"/> No | Power lines |
| <input type="checkbox"/> Yes | <input type="checkbox"/> No | Pipelines |
| <input type="checkbox"/> Yes | <input type="checkbox"/> No | Other man-made features (list individual features) |

7. **Are any of the following located within 800 feet of the proposed surface facility site?**

- | | | |
|------------------------------|-----------------------------|--|
| <input type="checkbox"/> Yes | <input type="checkbox"/> No | Type IIB public water wells. Type II is a non-community water supply with ≥ 15 service connections or ≥ 25 individuals for not less than 60 days per year. |
| <input type="checkbox"/> Yes | <input type="checkbox"/> No | Type III public water wells. Type III is a public water supply which is neither Type I nor type II. |

8. Are any of the following located within 1320 feet of the proposed surface facility site?

- ☐ Yes ☐ No Surface waters and other environmentally sensitive areas
☐ Yes ☐ No Floodplains associated with surface waters
☐ Yes ☐ No Wetlands, as identified by sections 30301 to 30323 of the Act.
☐ Yes ☐ No Natural rivers, as identified by sections 30501 to 30515 of the Act
☐ Yes ☐ No Threatened or endangered species as identified by sections 36501 to 36507 of the Act

9. Are any of the following located within 2000 feet of the proposed surface facility site?

- ☐ Yes ☐ No Type I public water wells. Type I is a community water supply with year-round service, ≥ 15 living units or ≥ 25 residents.
☐ Yes ☐ No Type IIA public water wells Type II is a non-community water supply with ≥ 15 service connections or ≥ 25 individuals for not less than 60 days per year.

10. ☐ Yes ☐ No Are Great Lakes shorelines located within 1500 feet of the proposed surface facility site?**D. FLOWLINE**

☐ Yes ☒ No Will the well have an associated flow line?

If Yes,

Flow line rout dimensions _____ feet x _____

Show flow line route from well to the surface facility, junction with an existing flowline or gathering system, on a scale map labeled **Part C2**.

Anticipated maximum operating pressure (psig): _____

Describe leak detection program, including schedules of periodic pressure testing and periodic flowline patrols.

Flow line material: _____

Describe the topography, drainage, soil type(s), direction and percentage of slopes, land cover and present land use along the flow line route.

☐ Yes ☐ No Will the flowline be buried?

If Yes

Burial depth: _____ feet

Describe flowline route marking scheme.

If No, describe measures to protect flowline from vehicular damage.

E. MITIGATION OF IMPACTS FROM DRILLING AND/OR OPERATION

Describe measures to be taken to protect environmental and/or land use values at the well/surface facility sites(s)

No drilling required

F. CERTIFICATION

"I state that I am authorized by said applicant to prepare this document. It was prepared under my supervision and direction. The facts stated herein are true, accurate and complete to the best of my knowledge."

Don Tinker Member
Name and title (printed or typed)

Don Tinker
Authorized Signature

6-25-08
Date

Don TINKER

Enclose with Application For Permit To Drill



INJECTION WELL DATA

Supplemental information for drilling or converting to an injection well

By authority of Part 615 or Part 625 of Act 451 PA 1994, as amended.

Non-submission and/or falsification of this information
may result in fines and/or imprisonment.

Applicant

Team Completions L.L.C

P.O. Box 1104

Kalkaska, MI 49646

Well name and number

Weber 4-8

INSTRUCTIONS: Complete all portions of form which apply to this well. Attach supplemental documents as needed.

1. File a separate plat which identifies the depth and location of this proposed well and all producing, abandoned, or drilling wells within 1320 feet of it. Also identify the permittee of each producing well within 1320 feet of this proposed well.
2. Enclose a copy of the completion reports for all wells and the plugging records for all plugged wells shown on the plat. Identify what steps will be necessary to prevent injected fluids from migrating up or into inadequately plugged or completed wells.
3. If this is an existing well to be converted to an injection well, enclose this form with an Application To Change Well Status (form EQP 7200-6). Also enclose a copy of the completion report and geologic description and electric logs for this well.
4. Injection wells (except for gas storage) must receive a mechanical integrity test every 5 years pursuant to Rule 324.805.

5. Type of fluids to be injected

- ☒ Brine ☐ Natural Gas (omit #7 & #12)
☐ Fresh Water (omit #12) ☒ Other Landfill Leachate

6. Maximum expected injection rate 5000 BPD

7. Specific gravity of injected fluid 1.00 to 1.07

8. Maximum expected injection pressure 0

9. Maximum bottom hole injection pressure 1019 PSI

Show calculations $2200' \times .433 \times 1.07 + 0$ (surface press) =
1019 PSI (gradient = 0.463 PSI/FT)

10. Fracture pressure of confining formation 1343 PSI

Show calculations Est. at 0.75 PSI/FT

 $1791 \times 0.75 = 1343$ PSI

11. Fracture pressure of injection formation 1650 @ TD

Show calculations Est. at 0.75 PSI/FT

 $2200' \times 0.75 = 1650$ PSI

12. Chemical analysis of representative samples of injected fluid

Specific conductance 7470 - 9970

Cation (mg/l)

Calcium 47 - 78200

Sodium 939 - 47000

Magnesium 52 - 8300

Potassium 300 - 16800

Anions (mg/l)

Chloride 1110 - 225000

Sulfate < 10 - 83

Bicarbonate 62 - 3540

What was the source of this representative sample? Glen's Sanitary
Landfill and Townsite 1-17 HD13. Is this well to be completed in a potential or previous oil or gas
producing formation? ☐ Yes ☒ NoIf yes, provide a list of all offset permittees and proof of service of
notification of this application to all permittees by certified mail.14. Attach proposed plugging and abandonment plan. OR
Briefly list depths, volumes and types of cement and mechanical
plugs and depths where casing will be recovered.

Plugging and abandonment plan attached Section Q of report

Schematic of wellbore construction

Complete bottom of diagram as needed to conform with proposed construction
(e.g. show rat hole below casing, open hole completion, packer loc. etc.)

Fresh water fms., name & depth

Glacial Drift 781'

Base of freshwater, name & depth

Glacial Drift 781'

Surface casing 8 5/8"

Amount of cement 450 sacks

T.O.C. 40 bbls. circ. to surface

Intermediate casing (if applicable)

Amount of cement _____ sacks

T.O.C. _____

Long string casing 5 1/2"

Amount of cement 305 sacks

T.O.C. 2 bbls. circ. to surface

Confining formation(s) Coldwater Shale & Antrim

Depth to top 781'

Depth to base 1816

Injection formation(s) Traverse

Depth to top 1816'

Depth to base +/- 2344'

Tubing 2 7/8", 6.5# " x 1750

Packer Depth 1750'

Bottom TD or PBTD 2200 ft.

Date

15. Application prepared by (print or type):


Don Tinker

6-25-08

1/4 MILE AREA OF REVIEW WEBBER #4-8

WELLS WITHIN 1/4
MILE OF A.O.R.
(ALL P AND A)

NO.	P/N	WELL NO.
1	34968	3-8C
	34506	3-8B
	34469	3-8A
	34419	3-8
2	34469	3-8A
3	34506	3-8B
4	34968	3-8C
5	34594	2-8
6	34147	1-8
	36359	2-8A
7	34594	2-8A
	36359	2-8A
8	33644	1-8A
	33597	1-8
9	33644	1-8A



□ = SURFACE HOLE LOCATION

○ = BOTTOM HOLE LOCATION

■ = RESIDENCE



0' 400' 800'
SCALE: 1" = 800'

G:\PROJECT\CAP\30402

FARRIER SURVEYING

P.O. BOX 998
244 S. CEDAR STREET
KALKASKA, MI 49646
TEL (231) 258-8162
FAX (231) 258-3249

P.O. BOX 1105
502 CAYUGA STREET
BELLAIRE, MI 49615
TEL (231) 533-8161
FAX (231) 533-5206

CLIENT TEAM COMPLETIONS

DESCRIPTION WEBBER #4-8
SW/4-NE/4-NE/4 OF SEC. 8
T25N-R11W, MAYFIELD TOWNSHIP,
GRAND TRAVERSE COUNTY, MICHIGAN

DRAWN: JM

FILE No. 30402

CHECK: DF

Fd. Bk. Pg.

REVISED:

DATE: 11-8-02

11-26-02

SHEET: 1 of 1